



US Army Corps
of Engineers
Savannah District

Robins AFB Georgia

Solicitation Number

DACA21-03-R-0073

ADAL JSTARS Flight Simulator Facility

FY-04, Line Item UHZ 013004

Volume II of III - Technical Provisions - Divisions 3 through 12

October 2003

**THIS SOLICITATION IS UNRESTRICTED PURSUANT TO THE
"BUSINESS OPPORTUNITY DEVELOPMENT REFORM ACT OF 1988"
(PUBLIC LAW 100-656)**

**U.S. ARMY ENGINEER DISTRICT, SAVANNAH
CORPS OF ENGINEERS
100 WEST OGLETHORPE AVENUE
SAVANNAH, GEORGIA 31401-3640**

PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

01312A QUALITY CONTROL SYSTEM (QCS)
01320A PROJECT SCHEDULE
01330 SUBMITTAL PROCEDURES
01355A ENVIRONMENTAL PROTECTION
01420 SOURCES FOR REFERENCE PUBLICATIONS
01451A CONTRACTOR QUALITY CONTROL
01452A SPECIAL INSPECTION FOR SEISMIC-RESISTING SYSTEMS
01500 TEMPORARY CONSTRUCTION FACILITIES
01572A CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT
01670 RECYCLED / RECOVERED MATERIALS
01780A CLOSEOUT SUBMITTALS
01781 OPERATION AND MAINTENANCE DATA

DIVISION 02 - SITE WORK

02220 DEMOLITION
02231 CLEARING AND GRUBBING
02300a EARTHWORK
02315a EXCAVATION, FILLING AND BACKFILLING FOR BUILDINGS
02316a EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS
02364a TERMITICIDE TREATMENT MEASURES FOR SUBTERRANEAN TERMITE CONTROL
02510a WATER DISTRIBUTION SYSTEM
02531 SANITARY SEWERS
02550 BITUMINOUS PAVEMENT
02555A PREFABRICATED UNDERGROUND HEATING/COOLING DISTRIBUTION SYSTEM
02630a STORM-DRAINAGE SYSTEM
02763a PAVEMENT MARKINGS
02770a CONCRETE SIDEWALKS AND CURBS AND GUTTERS
02921a SEEDING
02922a SODDING
02930a EXTERIOR PLANTING

DIVISION 03 - CONCRETE

03100A STRUCTURAL CONCRETE FORMWORK
03150A EXPANSION JOINTS, AND CONTRACTION JOINTS
03200a CONCRETE REINFORCEMENT
03300 CAST-IN-PLACE STRUCTURAL CONCRETE

DIVISION 04 - MASONRY

04200 MASONRY
04435 ARCHITECTURAL CAST STONE
04810 NONBEARING MASONRY VENEER/STEEL STUD WALLS

DIVISION 05 - METALS

05120 STRUCTURAL STEEL
05210a STEEL JOISTS
05300a STEEL DECKING
05400a COLD-FORMED STEEL FRAMING
05500a MISCELLANEOUS METAL

DIVISION 06 - WOODS & PLASTICS

06100a ROUGH CARPENTRY
06200a FINISH CARPENTRY

DIVISION 07 - THERMAL & MOISTURE PROTECTION

07110a BITUMINOUS DAMPPROOFING
07416a STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM
07600a SHEET METALWORK, GENERAL
07840a FIRESTOPPING
07900a JOINT SEALING

DIVISION 08 - DOORS & WINDOWS

08110 STEEL DOORS AND FRAMES
08210 WOOD DOORS
08520a ALUMINUM AND ENVIRONMENTAL CONTROL ALUMINUM WINDOWS
08633 FIBERGLASS-SANDWICH-PANEL SYSTEMS
08710 DOOR HARDWARE
08810a GLASS AND GLAZING

DIVISION 09 - FINISHES

09100N METAL SUPPORT ASSEMBLIES
09250 GYPSUM BOARD
09510 ACOUSTICAL CEILINGS
09650A RESILIENT FLOORING
09670 FLUID-APPLIED FLOORING
09680A CARPET
09836 MULTI-COLOR TEXTURED INTERIOR COATING
09840A ACOUSTICAL WALL TREATMENT
09900 PAINTS AND COATINGS

DIVISION 10 - SPECIALTIES

10100A VISUAL COMMUNICATIONS SPECIALTIES
10201N METAL WALL LOUVERS
10270A RAISED FLOOR SYSTEM
10440 INTERIOR SIGNAGE

DIVISION 12 - FURNISHINGS

12490A WINDOW TREATMENT

DIVISION 13 - SPECIAL CONSTRUCTION

13080 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT
13100A LIGHTNING PROTECTION SYSTEM
13851A FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE
13930A WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION
13945A PREACTION AND DELUGE SPRINKLER SYSTEMS, FIRE PROTECTION

DIVISION 14 - CONVEYING SYSTEMS

14630a OVERHEAD ELECTRIC CRANES

DIVISION 15 - MECHANICAL

15070A SEISMIC PROTECTION FOR MECHANICAL EQUIPMENT
15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS

15181A CHILLED AND CONDENSER WATER PIPING AND ACCESSORIES
15400A PLUMBING, GENERAL PURPOSE
15569A WATER AND STEAM HEATING; OIL, GAS OR BOTH; UP TO 20 MBTUH
15700A UNITARY HEATING AND COOLING EQUIPMENT
15895 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEM
15951A DIRECT DIGITAL CONTROL FOR HVAC
15990A TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS
15995A COMMISSIONING OF HVAC SYSTEMS

DIVISION 16 - ELECTRICAL

16070A SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT
16415A ELECTRICAL WORK, INTERIOR
16710A PREMISES DISTRIBUTION SYSTEM

-- End of Project Table of Contents --

SECTION TABLE OF CONTENTS

DIVISION 03 - CONCRETE

SECTION 03100A

STRUCTURAL CONCRETE FORMWORK

05/98

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DESIGN

PART 2 PRODUCTS

- 2.1 FORM MATERIALS
 - 2.1.1 Omitted
 - 2.1.2 Forms For Class C Finish
 - 2.1.3 Omitted
 - 2.1.4 Omitted
 - 2.1.5 Omitted
 - 2.1.6 Form Ties
 - 2.1.7 Form Releasing Agents

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Formwork
 - 3.1.2 Omitted
 - 3.1.3 Omitted
- 3.2 CHAMFERING
- 3.3 COATING
- 3.4 REMOVAL OF FORMS

-- End of Section Table of Contents --

UFGS-03100A (May 1998)

SECTION 03100A

STRUCTURAL CONCRETE FORMWORK

05/98

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN HARDBOARD ASSOCIATION (AHA)

AHA ANSI/AHA A135.4 (1995) Basic Hardboard

DEPARTMENT OF COMMERCE (DOC)

DOC PS 1 (1996) Voluntary Product Standard -
Construction and Industrial Plywood

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Form Materials

Manufacturer's data including literature describing form materials, accessories, and form releasing agents.

Form Releasing Agents

Manufacturer's recommendation on method and rate of application of form releasing agents.

1.3 DESIGN

Forms shall be capable of producing a surface which meets the requirements of the class of finish specified in Section 03300 CAST-IN-PLACE STRUCTURAL CONCRETE. Forms shall be capable of withstanding the pressures resulting from placement and vibration of concrete.

PART 2 PRODUCTS

2.1 FORM MATERIALS

2.1.1 Omitted

2.1.2 Forms For Class C Finish

Forms for Class C finished surfaces shall be shiplap lumber; plywood conforming to DOC PS 1, Grade B-B concrete form panels, Class I or II; tempered concrete form hardboard conforming to AHA ANSI/AHA A135.4; other approved concrete form material; or steel, except that steel lining on wood sheathing shall not be used. Forms for round columns may have one vertical seam.

2.1.3 Omitted

2.1.4 Omitted

2.1.5 Omitted

2.1.6 Form Ties

Form ties shall be factory-fabricated metal ties, shall be of the removable or internal disconnecting or snap-off type, and shall be of a design that will not permit form deflection and will not spall concrete upon removal. Solid backing shall be provided for each tie. Except where removable tie rods are used, ties shall not leave holes in the concrete surface less than 1/4 inch nor more than 1 inch deep and not more than 1 inch in diameter. Removable tie rods shall be not more than 1-1/2 inches in diameter.

2.1.7 Form Releasing Agents

Form releasing agents shall be commercial formulations that will not bond with, stain or adversely affect concrete surfaces. Agents shall not impair subsequent treatment of concrete surfaces depending upon bond or adhesion nor impede the wetting of surfaces to be cured with water or curing compounds.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Formwork

Forms shall be mortar tight, properly aligned and adequately supported to produce concrete surfaces meeting the surface requirements specified in Section 03300 CAST-IN-PLACE STRUCTURAL CONCRETE and conforming to construction tolerance given in TABLE 1. Where forms for continuous surfaces are placed in successive units, the forms shall fit over the completed surface to obtain accurate alignment of the surface and to prevent leakage of mortar. Forms shall not be reused if there is any evidence of surface wear and tear or defects which would impair the quality of the surface. Surfaces of forms to be reused shall be cleaned of mortar from previous concreting and of all other foreign material before reuse. Form ties that are to be completely withdrawn shall be coated with a nonstaining bond breaker.

3.1.2 Omitted

3.1.3 Omitted

3.2 CHAMFERING

Except as otherwise shown, external corners that will be exposed shall be chamfered, beveled, or rounded by moldings placed in the forms.

3.3 COATING

Forms for Class C finished surfaces may be wet with water in lieu of coating immediately before placing concrete, except that in cold weather with probable freezing temperatures, coating shall be mandatory. Surplus coating on form surfaces and coating on reinforcing steel and construction joints shall be removed before placing concrete.

3.4 REMOVAL OF FORMS

Forms shall be removed preventing injury to the concrete and ensuring the complete safety of the structure. Formwork not supporting the weight of concrete may be removed when the concrete has attained sufficient strength to resist damage from the removal operation but not before at least 24 hours has elapsed since concrete placement.

TABLE 1

TOLERANCES FOR FORMED SURFACES

1. Variations from the plumb:	In any 10 feet of length ----- 1/4 inch
2. Variation from the level or from the grades indicated on the drawings:	In any 10 feet of length -----1/4 inch In any bay or in any 20 feet of length----- 3/8 inch
3. Variation of the linear building lines from established position in plan	In any 20 feet ----- 1/2 inch Maximum -----1 inch
4. Variation of distance between walls, partitions	1/4 inch per 10 feet of distance, but not more than 1/2 inch in any one bay, and not more than 1 inch total variation
5. Variation in the sizes and locations of sleeves, floor openings, and wall opening	Minus ----- 1/4 inch Plus ----- 1/2 inch
6. Variation in thickness of slabs	Minus ----- 1/4 inch Plus ----- 1/2 inch
7. Footings:	
a. Variation of dimensions in plan	Minus ----- 1/2 inch Plus ----- 2 inches when formed or plus 3 inches when placed against unformed excavation
b. Misplacement of eccentricity	2 percent of the footing width in the direction of misplacement but not more than

TABLE 1

TOLERANCES FOR FORMED SURFACES

	2 inches	
c. Reduction in thickness of specified thickness	Minus -----	5 percent
8. Variation in steps:	Riser -----	1/8 inch
a. In a flight of stairs	Tread -----	1/4 inch
b. In consecutive steps	Riser -----	1/16 inch
	Tread -----	1/8 inch

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 03 - CONCRETE

SECTION 03150A

EXPANSION JOINTS, AND CONTRACTION JOINTS

05/98

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 CONTRACTION JOINT STRIPS
- 2.2 PREFORMED EXPANSION JOINT FILLER
- 2.3 SEALANT
 - 2.3.1 Omitted
 - 2.3.2 Omitted
 - 2.3.3 Omitted
 - 2.3.4 Field-Molded Type

PART 3 EXECUTION

- 3.1 JOINTS
 - 3.1.1 Contraction Joints
 - 3.1.1.1 Joint Strips
 - 3.1.1.2 Sawed Joints
 - 3.1.1.3 Tooled Joints
 - 3.1.2 Expansion Joints
 - 3.1.3 Joint Sealant
 - 3.1.3.1 Omitted
 - 3.1.3.2 Joints With Field-Molded Sealant
- 3.2 OMITTED
- 3.3 CONSTRUCTION JOINTS

-- End of Section Table of Contents --

UFGS-03150A (May 1998)

Includes changes through Notice 1 (October 2000)

SECTION 03150A

EXPANSION JOINTS, AND CONTRACTION JOINTS
05/98

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN HARDBOARD ASSOCIATION (AHA)

AHA A135.4 (1995) Basic Hardboard

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 919 (1984; R 1998) Use of Sealants in Acoustical Applications

ASTM C 920 (1998) Elastomeric Joint Sealants

ASTM D 1751 (1999) Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)

ASTM D 1752 (1984; R 1996e1) Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction

ASTM D 5249 (1995) Backer Material for Use With Cold and Hot-Applied Joint Sealants in Portland-Cement Concrete and Asphalt Joints

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Preformed Expansion Joint Filler
Sealant

Manufacturer's literature, including safety data sheets, for preformed fillers and the lubricants used in their installation; field-molded sealants and primers (when required by sealant manufacturer).

Preformed Expansion Joint Filler
Sealant

Manufacturer's recommended instructions for installing preformed fillers, field-molded sealants; and waterstops; and for splicing non-metallic waterstops.

SD-07 Certificates

Preformed Expansion Joint Filler
Sealant

Certificates of compliance stating that the joint filler and sealant materials and waterstops conform to the requirements specified.

1.3 DELIVERY AND STORAGE

Material delivered and placed in storage shall be stored off the ground and protected from moisture, dirt, and other contaminants. Sealants shall be delivered in the manufacturer's original unopened containers. Sealants whose shelf life has expired shall be removed from the site.

PART 2 PRODUCTS

2.1 CONTRACTION JOINT STRIPS

Contraction joint strips shall be 1/8 inch thick tempered hardboard conforming to AHA A135.4, Class 1. In lieu of hardboard strips, rigid polyvinylchloride (PVC) or high impact polystyrene (HIPS) insert strips specifically designed to induce controlled cracking in slabs on grade may be used. Such insert strips shall have removable top section.

2.2 PREFORMED EXPANSION JOINT FILLER

Expansion joint filler shall be preformed material conforming to ASTM D 1751 or ASTM D 1752. Unless otherwise indicated, filler material shall be 3/8 inch thick and of a width applicable for the joint formed. Backer material, when required, shall conform to ASTM D 5249.

2.3 SEALANT

Joint sealant shall conform to the following:

- 2.3.1 Omitted
- 2.3.2 Omitted
- 2.3.3 Omitted

2.3.4 Field-Molded Type

ASTM C 920, Type M for horizontal joints or Type NS for vertical joints,

Class 25, and Use NT. Bond breaker material shall be polyethylene tape, coated paper, metal foil or similar type materials. The back-up material shall be compressible, non-shrink, nonreactive with sealant, and non-absorptive material type such as extruded butyl or polychloroprene rubber.

PART 3 EXECUTION

3.1 JOINTS

Joints shall be installed at locations indicated and as authorized.

3.1.1 Contraction Joints

Contraction joints may be constructed by inserting tempered hardboard strips or rigid PVC or HIPS insert strips into the plastic concrete using a steel parting bar, when necessary, or by cutting the concrete with a saw after concrete has set. Joints shall be approximately 1/8 inch wide and shall extend into the slab one-fourth the slab thickness, minimum, but not less than 1 inch.

3.1.1.1 Joint Strips

Strips shall be of the required dimensions and as long as practicable. After the first floating, the concrete shall be grooved with a tool at the joint locations. The strips shall be inserted in the groove and depressed until the top edge of the vertical surface is flush with the surface of the slab. The slab shall be floated and finished as specified. Working of the concrete adjacent to the joint shall be the minimum necessary to fill voids and consolidate the concrete. Where indicated, the top portion of the strip shall be sawed out after the curing period to form a recess for sealer. The removable section of PVC or HIPS strips shall be discarded and the insert left in place. True alignment of the strips shall be maintained during insertion.

3.1.1.2 Sawed Joints

Joint sawing shall be early enough to prevent uncontrolled cracking in the slab, but late enough that this can be accomplished without appreciable spalling but in no case later than 8 hours after time of placement. Concrete sawing machines shall be adequate in number and power, and with sufficient replacement blades to complete the sawing at the required rate. Joints shall be cut to true alignment and shall be cut in sequence of concrete placement. Sludge and cutting debris shall be removed.

3.1.1.3 Tooled Joints

Tooled joints as part of grid pattern in concrete walkway and entry areas around Recreation Center shall be made by use of a groove-cutting tool that provides a cut and troweled areas on both sides of grid. Grooves shall be cut and tooled after broom finish on slab is done and care shall be taken not to mar the brooming pattern.

3.1.2 Expansion Joints

Preformed expansion joint filler shall be used in expansion and isolation joints in slabs around columns and between slabs on grade and vertical surfaces where indicated. The filler shall extend the full slab depth, unless otherwise indicated. The edges of the joint shall be neatly

finished with an edging tool of 1/8 inch radius, except where a resilient floor surface will be applied. Where the joint is to receive a sealant, the filler strips shall be installed at the proper level below the finished floor with a slightly tapered, dressed and oiled wood strip temporarily secured to the top to form a recess to the size shown on the drawings. The wood strip shall be removed after the concrete has set. Contractor may opt to use a removable expansion filler cap designed and fabricated for this purpose in lieu of the wood strip. The groove shall be thoroughly cleaned of laitance, curing compound, foreign materials, protrusions of hardened concrete, and any dust which shall be blown out of the groove with oil-free compressed air.

3.1.3 Joint Sealant

Sawed contraction joints and expansion joints in slabs shall be filled with joint sealant, unless otherwise shown. Joint surfaces shall be clean, dry, and free of oil or other foreign material which would adversely affect the bond between sealant and concrete. Joint sealant shall be applied as recommended by the manufacturer of the sealant.

3.1.3.1 Omitted

3.1.3.2 Joints With Field-Molded Sealant

Joints shall not be sealed when the sealant material, ambient air, or concrete temperature is less than 40 degrees F. When the sealants are meant to reduce the sound transmission characteristics of interior walls, ceilings, and floors the guidance provided in ASTM C 919 shall be followed.

Joints requiring a bond breaker shall be coated with curing compound or with bituminous paint. Bond breaker and back-up material shall be installed where required. Joints shall be primed and filled flush with joint sealant in accordance with the manufacturer's recommendations.

3.2 OMITTED

3.3 CONSTRUCTION JOINTS

Construction joints are specified in Section 03300 CAST-IN-PLACE STRUCTURAL CONCRETE except that construction joints coinciding with expansion and contraction joints shall be treated as expansion or contraction joints as applicable.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 03 - CONCRETE

SECTION 03200A

CONCRETE REINFORCEMENT

09/97

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 OMITTED
- 1.4 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 OMITTED
- 2.2 OMITTED
- 2.3 REINFORCING STEEL
- 2.4 WELDED WIRE FABRIC
- 2.5 WIRE TIES
- 2.6 SUPPORTS
- 2.7 SYNTHETIC FIBER REINFORCEMENT

PART 3 EXECUTION

- 3.1 REINFORCEMENT
 - 3.1.1 Placement
 - 3.1.2 Splicing
- 3.2 WELDED-WIRE FABRIC PLACEMENT
- 3.4 SYNTHETIC FIBER REINFORCED CONCRETE

-- End of Section Table of Contents --

UFGS-03200A (September 1997)

SECTION 03200A

CONCRETE REINFORCEMENT

09/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ACI INTERNATIONAL (ACI)

ACI 318/318R (1995) Building Code Requirements for Structural Concrete and Commentary

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 185 (1997) Steel Welded Wire Fabric, Plain, for Concrete Reinforcement

ASTM A 615/A 615M (1996a) Deformed and Plain Billet-Steel Bars for Concrete Reinforcement

ASTM A 706/A 706M (1998) Low-Alloy Steel Deformed and Plain Bars for Concrete Reinforcement

ASTM C 1116 (1995) Fiber-Reinforced Concrete and Shotcrete

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)

CRSI MSP-1 (1996) Manual of Standard Practice

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation;

submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Reinforcement; G,AE

Detail drawings showing reinforcing steel placement, schedules, sizes, grades, and splicing and bending details. Drawings shall show support details including types, sizes and spacing.

SD-07 Certificates

Reinforcing Steel;

Certified copies of mill reports attesting that the reinforcing steel furnished contains no less than 25 percent recycled scrap steel and meets the requirements specified herein, prior to the installation of reinforcing steel.

1.3 OMITTED

1.4 DELIVERY AND STORAGE

Reinforcement and accessories shall be stored off the ground on platforms, skids, or other supports.

PART 2 PRODUCTS

2.1 OMITTED

2.2 OMITTED

2.3 REINFORCING STEEL

Reinforcing steel shall be deformed bars conforming to ASTM A 615/A 615M or ASTM A 706/A 706M, grades and sizes as indicated.

2.4 WELDED WIRE FABRIC

Welded wire fabric shall conform to ASTM A 185.

2.5 WIRE TIES

Wire ties shall be 16 gauge or heavier black annealed steel wire.

2.6 SUPPORTS

Bar supports for formed surfaces shall be designed and fabricated in accordance with CRSI MSP-1 and shall be steel or precast concrete blocks. Precast concrete blocks shall have wire ties and shall be not less than 4 inches square when supporting reinforcement on ground. Precast concrete block shall have compressive strength equal to that of the surrounding concrete. Where concrete formed surfaces will be exposed to weather or where surfaces are to be painted, steel supports within 1/2 inch of concrete surface shall be galvanized, plastic protected or of stainless steel. Concrete supports used in concrete exposed to view shall have the same color and texture as the finish surface. For slabs on grade, supports

shall be precast concrete blocks, plastic coated steel fabricated with bearing plates, or specifically designed wire-fabric supports fabricated of plastic.

2.7 SYNTHETIC FIBER REINFORCEMENT

Synthetic fiber shall be polypropylene with a denier less than 100 and a nominal fiber length of 2 inches.

PART 3 EXECUTION

3.1 REINFORCEMENT

Reinforcement shall be fabricated to shapes and dimensions shown and shall conform to the requirements of ACI 318/318R. Reinforcement shall be cold bent unless otherwise authorized. Bending may be accomplished in the field or at the mill. Bars shall not be bent after embedment in concrete. Safety caps shall be placed on all exposed ends of vertical concrete reinforcement bars that pose a danger to life safety. Wire tie ends shall face away from the forms.

3.1.1 Placement

Reinforcement shall be free from loose rust and scale, dirt, oil, or other deleterious coating that could reduce bond with the concrete. Reinforcement shall be placed in accordance with ACI 318/318R at locations shown plus or minus one bar diameter. Reinforcement shall not be continuous through expansion joints and shall be as indicated through construction or contraction joints. Concrete coverage shall be as indicated or as required by ACI 318/318R. If bars are moved more than one bar diameter to avoid interference with other reinforcement, conduits or embedded items, the resulting arrangement of bars, including additional bars required to meet structural requirements, shall be approved before concrete is placed.

3.1.2 Splicing

Splices of reinforcement shall conform to ACI 318/318R and shall be made only as required or indicated. Splicing shall be by lapping. Lapped bars shall be placed in contact and securely tied or spaced transversely apart to permit the embedment of the entire surface of each bar in concrete. Lapped bars shall not be spaced farther apart than one-fifth the required length of lap or 6 inches.

3.2 WELDED-WIRE FABRIC PLACEMENT

Welded-wire fabric shall be placed in slabs as indicated. Fabric placed in slabs on grade shall be continuous between expansion, construction, and contraction joints. Fabric placement at joints shall be as indicated. Lap splices shall be made in such a way that the overlapped area equals the distance between the outermost crosswires plus 2 inches. Laps shall be staggered to avoid continuous laps in either direction. Fabric shall be wired or clipped together at laps at intervals not to exceed 4 feet. Fabric shall be positioned by the use of supports.

3.4 SYNTHETIC FIBER REINFORCED CONCRETE

Fiber reinforcement shall be added to the concrete mix in accordance with the applicable sections of ASTM C 1116 and the recommendations of the

manufacturer, and in an amount of 0.1 percent by volume.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 03 - CONCRETE

SECTION 03300

CAST-IN-PLACE STRUCTURAL CONCRETE

11/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 OMITTED
- 1.3 OMITTED
- 1.4 SUBMITTALS
- 1.5 QUALIFICATIONS
- 1.6 OMITTED
- 1.7 OMITTED
- 1.8 GENERAL REQUIREMENTS
 - 1.8.1 Tolerances
 - 1.8.1.1 Floors
 - 1.8.1.2 Floors by the F-Number System
 - 1.8.2 Strength Requirements and w/c Ratio
 - 1.8.2.1 Strength Requirements
 - 1.8.2.2 Water-Cement Ratio
 - 1.8.3 Air Entrainment
 - 1.8.4 Slump
 - 1.8.5 Concrete Temperature
 - 1.8.6 Size of Coarse Aggregate
 - 1.8.7 Special Properties and Products
- 1.9 MIXTURE PROPORTIONS
 - 1.9.1 Proportioning Studies for Normal Weight Concrete
 - 1.9.2 Omitted
 - 1.9.3 Omitted
 - 1.9.4 Average Compressive Strength Required for Mixtures
 - 1.9.4.1 Computations from Test Records
 - 1.9.4.2 Computations without Previous Test Records
- 1.10 STORAGE OF MATERIALS
- 1.11 GOVERNMENT ASSURANCE INSPECTION AND TESTING
 - 1.11.1 Materials
 - 1.11.2 Fresh Concrete
 - 1.11.3 Hardened Concrete
 - 1.11.4 Inspection

PART 2 PRODUCTS

- 2.1 CEMENTITIOUS MATERIALS
 - 2.1.1 Portland Cement
 - 2.1.2 Omitted
 - 2.1.3 Omitted
 - 2.1.4 Pozzolan (Fly Ash)
 - 2.1.5 Ground Granulated Blast-Furnace (GGBF) Slag
- 2.2 AGGREGATES
 - 2.2.1 Fine Aggregate
 - 2.2.2 Coarse Aggregate
- 2.3 CHEMICAL ADMIXTURES
 - 2.3.1 Air-Entraining Admixture

- 2.3.2 Accelerating Admixture
- 2.3.3 Water-Reducing or Retarding Admixture
- 2.3.4 High-Range Water Reducer
- 2.3.5 Omitted
- 2.3.6 Omitted
- 2.3.7 Other Chemical Admixtures
- 2.4 CURING MATERIALS
 - 2.4.1 Impervious-Sheet
 - 2.4.2 Membrane-Forming Compound
 - 2.4.3 Burlap and Cotton Mat
- 2.5 WATER
- 2.6 NONSHRINK GROUT
- 2.7 OMITTED
- 2.8 LATEX BONDING AGENT
- 2.9 EPOXY RESIN
- 2.10 EMBEDDED ITEMS
- 2.11 FLOOR HARDENER
- 2.12 OMITTED
- 2.13 VAPOR BARRIER
- 2.14 JOINT MATERIALS
 - 2.14.1 Joint Fillers and Sealers
 - 2.14.2 Contraction Joints in Slabs
- 2.15 SYNTHETIC FIBERS FOR REINFORCING
- 2.16 FLOATING FLOOR SYSTEM MATERIAL
 - 2.16.1 Underslab Isolation Material
 - 2.16.2 Forming Board for Concrete
 - 2.16.3 Perimeter Isolation Board

PART 3 EXECUTION

- 3.1 PREPARATION FOR PLACING
 - 3.1.1 Foundations
 - 3.1.1.1 Concrete on Earth Foundations
 - 3.1.1.2 Omitted
 - 3.1.1.3 Excavated Surfaces in Lieu of Forms
 - 3.1.2 Preparation of Previously Placed Concrete
 - 3.1.3 Vapor Barrier
 - 3.1.4 Omitted
 - 3.1.5 Embedded Items
- 3.2 CONCRETE PRODUCTION
 - 3.2.1 Batching, Mixing, and Transporting Concrete
 - 3.2.1.1 General
 - 3.2.1.2 Batching Equipment
 - 3.2.1.3 Scales
 - 3.2.1.4 Batching Tolerances
 - 3.2.1.5 Moisture Control
 - 3.2.1.6 Concrete Mixers
 - 3.2.1.7 Stationary Mixers
 - 3.2.1.8 Truck Mixers
- 3.3 OMITTED
- 3.4 OMITTED
- 3.5 FIBER REINFORCED CONCRETE
- 3.6 TRANSPORTING CONCRETE TO PROJECT SITE
- 3.7 CONVEYING CONCRETE ON SITE
 - 3.7.1 Buckets
 - 3.7.2 Omitted
 - 3.7.3 Omitted
 - 3.7.4 Chutes
 - 3.7.5 Omitted

- 3.7.6 Concrete Pumps
- 3.8 PLACING CONCRETE
 - 3.8.1 Depositing Concrete
 - 3.8.2 Consolidation
 - 3.8.3 Cold Weather Requirements
 - 3.8.4 Hot Weather Requirements
 - 3.8.5 Prevention of Plastic Shrinkage Cracking
 - 3.8.6 Omitted
 - 3.8.7 Omitted
 - 3.8.8 Placing Flowable Concrete
- 3.9 JOINTS
 - 3.9.1 Construction Joints
 - 3.9.2 Contraction Joints in Slabs on Grade
 - 3.9.3 Expansion Joints
- 3.10 FINISHING FORMED SURFACES
 - 3.10.1 Omitted
 - 3.10.2 Class C Finish
- 3.11 REPAIRS
 - 3.11.1 Damp-Pack Mortar Repair
 - 3.11.2 Repair of Major Defects
 - 3.11.2.1 Surface Application of Mortar Repair
 - 3.11.2.2 Repair of Deep and Large Defects
- 3.12 FINISHING UNFORMED SURFACES
 - 3.12.1 General
 - 3.12.2 Rough Slab Finish
 - 3.12.3 Floated Finish
 - 3.12.4 Troweled Finish
 - 3.12.5 Omitted
 - 3.12.6 Non-Slip Finish
 - 3.12.6.1 Broomed
- 3.13 FLOOR HARDENER
- 3.14 OMITTED
- 3.15 CURING AND PROTECTION
 - 3.15.1 General
 - 3.15.2 Moist Curing
 - 3.15.3 Membrane Forming Curing Compounds
 - 3.15.4 Omitted
 - 3.15.5 Ponding or Immersion
 - 3.15.6 Cold Weather Curing and Protection
- 3.16 SETTING BASE PLATES AND BEARING PLATES
 - 3.16.1 Damp-Pack Bedding Mortar
 - 3.16.2 Nonshrink Grout
 - 3.16.2.1 Mixing and Placing of Nonshrink Grout
 - 3.16.2.2 Treatment of Exposed Surfaces
- 3.17 TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL
 - 3.17.1 Grading and Corrective Action
 - 3.17.1.1 Fine Aggregate
 - 3.17.1.2 Coarse Aggregate
 - 3.17.2 Quality of Aggregates
 - 3.17.3 Scales, Batching and Recording
 - 3.17.4 Batch-Plant Control
 - 3.17.5 Concrete Mixture
 - 3.17.6 Inspection Before Placing
 - 3.17.7 Placing
 - 3.17.8 Vibrators
 - 3.17.9 Curing Inspection
 - 3.17.10 Cold-Weather Protection
 - 3.17.11 Mixer Uniformity
 - 3.17.12 Reports

-- End of Section Table of Contents --

UFGS-03300 (November 2001)

SECTION 03300

CAST-IN-PLACE STRUCTURAL CONCRETE

11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ACI INTERNATIONAL (ACI)

ACI 117/117R	(1990; Errata) Standard Tolerances for Concrete Construction and Materials
ACI 211.1	(1991) Standard Practice for Selecting Proportions for Normal, Heavyweight, and Mass Concrete
ACI 214.3R	(1988; R 1997) Simplified Version of the Recommended Practice for Evaluation of Strength Test Results of Concrete
ACI 305R	(1999) Hot Weather Concreting
ACI 318/318R	(1999) Building Code Requirements for Structural Concrete and Commentary

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 182	(1991; R 1996) Burlap Cloth Made from Jute or Kenaf
--------------	---

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 1017/C 1017M	(1998) Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C 1059	(1999) Latex Agents for Bonding Fresh to Hardened Concrete
ASTM C 1064/C 1064M	(1999) Temperature of Freshly Mixed Portland Cement Concrete
ASTM C 1077	(1998) Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation
ASTM C 1107	(1999) Packaged Dry, Hydraulic-Cement Grout(Nonshrink)

ASTM C 1116	(2000) Fiber-Reinforced Concrete and Shotcrete
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM C 143/C 143M	(2000) Slump of Hydraulic Cement Concrete
ASTM C 150	(1999a) Portland Cement
ASTM C 171	(1997a) Sheet Materials for Curing Concrete
ASTM C 172	(1999) Sampling Freshly Mixed Concrete
ASTM C 173	(1994ael) Air Content of Freshly Mixed Concrete by the Volumetric Method
ASTM C 192/C 192M	(2000) Making and Curing Concrete Test Specimens in the Laboratory
ASTM C 231	(1997el) Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C 260	(2000) Air-Entraining Admixtures for Concrete
ASTM C 309	(1998a) Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C 31/C 31M	(2000el) Making and Curing Concrete Test Specimens in the Field
ASTM C 33	(1999ael) Concrete Aggregates
ASTM C 39/C 39M	(2001) Compressive Strength of Cylindrical Concrete Specimens
ASTM C 42/C 42M	(1999) Obtaining and Testing Drilled Cores and Sawed Beams of Concrete
ASTM C 494/C 494M	(1999ael) Chemical Admixtures for Concrete
ASTM C 618	(2000) Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Concrete
ASTM C 78	(1994) Flexural Strength of Concrete (Using Simple Beam With Third-Point Loading)
ASTM C 881	(1999) Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C 94/C 94M	(2000e2) Ready-Mixed Concrete
ASTM C 989	(1999) Ground Granulated Blast-Furnace Slag for Use in Concrete and Mortars

ASTM D 1752	(1984; R 1996e1) Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction
ASTM D 75	(1987; R 1997) Sampling Aggregates
ASTM E 1155	(1996) Determining Floor Flatness and Levelness Using the F-Number System
ASTM E 96	(2000) Water Vapor Transmission of Materials

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

NIST HB 44	(1997) NIST Handbook 44: Specifications, Tolerances, and other Technical Requirements for Weighing and Measuring Devices
------------	--

NATIONAL READY-MIXED CONCRETE ASSOCIATION (NRMCA)

NRMCA CPMB 100	(1996) Concrete Plant Standards \n/c\$\X
NRMCA QC 3	(1984) Quality Control Manual: Section 3, Plant Certifications Checklist: Certification of Ready Mixed Concrete Production Facilities
NRMCA TMMB 100	(1994) Truck Mixer Agitator and Front Discharge Concrete Carrier Standards

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 104	(1980) Method of Calculation of the Fineness Modulus of Aggregate
COE CRD-C 400	(1963) Requirements for Water for Use in Mixing or Curing Concrete
COE CRD-C 521	(1981) Standard Test Method for Frequency and Amplitude of Vibrators for Concrete
COE CRD-C 540	(1971; R 1981) Standard Specification for Nonbituminous Inserts for Contraction Joints in Portland Cement Concrete Airfield Pavements, Sawable Type
COE CRD-C 572	(1974) Corps of Engineers Specifications for Polyvinylchloride Waterstop

1.2 OMITTED

1.3 OMITTED

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office

that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Mixture Proportions; G, RE

The results of trial mixture design studies along with a statement giving the maximum nominal coarse aggregate size and the proportions of ingredients that will be used in the manufacture of each strength or class of concrete, at least 14 days prior to commencing concrete placing operations. Aggregate weights shall be based on the saturated surface dry condition. The statement shall be accompanied by test results from an approved independent commercial testing laboratory, showing that mixture design studies have been made with materials proposed for the project and that the proportions selected will produce concrete of the qualities indicated. No substitutions shall be made in the materials used in the mixture design studies without additional tests to show that the quality of the concrete is satisfactory.

SD-06 Test Reports

Testing and Inspection for Contractor Quality Control

Certified copies of laboratory test reports, including mill tests and all other test data, for portland cement, blended cement, pozzolan, ground granulated blast furnace slag, silica fume, aggregate, admixtures, and curing compound proposed for use on this project.

SD-07 Certificates

Qualifications

Written documentation for Contractor Quality Control personnel.

1.5 QUALIFICATIONS

Contractor Quality Control personnel assigned to concrete construction shall be American Concrete Institute (ACI) Certified Workmen in one of the following grades or shall have written evidence of having completed similar qualification programs:

Concrete Field Testing Technician, Grade I
Concrete Laboratory Testing Technician, Grade I or II
Concrete Construction Inspector, Level II

Concrete Transportation Construction Inspector or Reinforced Concrete Special Inspector, Jointly certified by American Concrete Institute (ACI), Building Official and Code Administrators International (BOCA), International Conference of Building Officials (ICBO), and Southern Building Code Congress International (SBCCI).

The foreman or lead journeyman of the flatwork finishing crew shall have similar qualification for ACI Concrete Flatwork Technician/Finisher or equal, with written documentation.

- 1.6 OMITTED
- 1.7 OMITTED

1.8 GENERAL REQUIREMENTS

1.8.1 Tolerances

Except as otherwise specified herein, tolerances for concrete batching, mixture properties, and construction as well as definition of terms and application practices shall be in accordance with ACI 117/117R. Level and grade tolerance measurements of slabs shall be made as soon as possible after finishing; when forms or shoring are used, the measurements shall be made prior to removal.

1.8.1.1 Floors

For the purpose of this Section the following terminology correlation between ACI 117/117R and this Section shall apply:

Floor Profile Quality Classification From ACI 117/117R -----	This Section -----
Conventional Bullfloated	Same
Conventional Straightedged	Same
Flat	Float Finish or Trowel Finish
Very Flat	Same. Use only with F-system

Levelness tolerance shall not apply where design requires floors to be sloped to drains or sloped for other reasons.

1.8.1.2 Floors by the F-Number System

The flatness and levelness of floors shall be carefully controlled and the tolerances shall be measured by the F-Number system of Paragraph 4.5.6 and 4.5.6.1 of ACI 117/117R. The Contractor shall furnish an approved floor profilograph or other equipment capable of measuring the floor flatness (FF) number and the floor levelness (FL) number in accordance with ASTM E 1155. The Contractor shall perform the tolerance measurements within 72 hours after floor slab construction while being observed by the Contracting Officer. The tolerances of surfaces beyond the limits of ASTM E 1155 (the areas within 24 inches of embedments and construction joints) shall be acceptable to the Contracting Officer. Tolerances of the following areas shall meet the requirements for the listed surfaces as specified in paragraphs 4.5.6 and 4.5.6.1 of ACI 117/117R.

Bullfloated-	Areas Trenches
Float Finish-	Areas Not otherwise noted
Trowel Finish-	Areas Exposed to view in finished work

1.8.2 Strength Requirements and w/c Ratio

1.8.2.1 Strength Requirements

Specified compressive strength (f'c) shall be as follows:

COMPRESSIVE STRENGTH	STRUCTURE OR PORTION OF STRUCTURE
4000 psi at 28 days	All concrete

COMPRESSIVE STRENGTH

STRUCTURE OR PORTION OF STRUCTURE

Concrete made with high-early strength cement shall have a 7-day strength equal to the specified 28-day strength for concrete made with Type I or II portland cement. Compressive strength shall be determined in accordance with ASTM C 39/C 39M. Flexural strength shall be determined in accordance with ASTM C 78.

- a. Evaluation of Concrete Compressive Strength. Compressive strength specimens (6 by 12 inch cylinders) shall be fabricated by the Contractor and laboratory cured in accordance with ASTM C 31/C 31M and tested in accordance with ASTM C 39/C 39M. The strength of the concrete will be considered satisfactory so long as the average of all sets of three consecutive test results equals or exceeds the specified compressive strength f'_c and no individual test result falls below the specified strength f'_c by more than 500 psi. A "test" is defined as the average of two companion cylinders, or if only one cylinder is tested, the results of the single cylinder test. Additional analysis or testing, including taking cores and/or load tests may be required at the Contractor's expense when the strength of the concrete in the structure is considered potentially deficient.
- b. Investigation of Low-Strength Compressive Test Results. When any strength test of standard-cured test cylinders falls below the specified strength requirement by more than 500 psi or if tests of field-cured cylinders indicate deficiencies in protection and curing, steps shall be taken to assure that the load-carrying capacity of the structure is not jeopardized. When the strength of concrete in place is considered potentially deficient, cores shall be obtained and tested in accordance with ASTM C 42/C 42M. At least three representative cores shall be taken from each member or area of concrete in place that is considered potentially deficient. The location of cores will be determined by the Contracting Officer to least impair the strength of the structure. Concrete in the area represented by the core testing will be considered adequate if the average strength of the cores is equal to at least 85 percent of the specified strength requirement and if no single core is less than 75 percent of the specified strength requirement. Non-destructive tests (tests other than test cylinders or cores) shall not be used as a basis for acceptance or rejection. The Contractor shall perform the coring and repair the holes. Cores will be tested by the Government.
- c. Load Tests. If the core tests are inconclusive or impractical to obtain or if structural analysis does not confirm the safety of the structure, load tests may be directed by the Contracting Officer in accordance with the requirements of ACI 318/318R. Concrete work evaluated by structural analysis or by results of a load test as being understrength shall be corrected in a manner satisfactory to the Contracting Officer. All investigations, testing, load tests, and correction of deficiencies shall be performed by and at the expense of the Contractor and must be approved by the Contracting Officer, except that if all concrete is found to be in compliance with the drawings and specifications, the cost of investigations, testing, and load tests will be at the expense of the Government.

1.8.2.2 Water-Cement Ratio

Maximum water-cement ratio (w/c) for normal weight concrete shall be as follows:

WATER-CEMENT RATIO, BY WEIGHT	STRUCTURE OR PORTION OF STRUCTURE
0.45	Slabs cast on grade
0.50	All concrete not otherwise noted

These w/c's may cause higher strengths than that required above for compressive or flexural strength. The maximum w/c required will be the equivalent w/c as determined by conversion from the weight ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace slag (GGBF slag) by the weight equivalency method as described in ACI 211.1.

In the case where silica fume or GGBF slag is used, the weight of the silica fume and GGBF slag shall be included in the equations of ACI 211.1 for the term P which is used to denote the weight of pozzolan.

1.8.3 Air Entrainment

Except as otherwise specified for lightweight concrete, all normal weight concrete shall be air entrained to contain between 4 and 7 percent total air, except that when the nominal maximum size coarse aggregate is 3/4 inch or smaller it shall be between 4.5 and 7.5 percent. Specified air content shall be attained at point of placement into the forms. Air content for normal weight concrete shall be determined in accordance with ASTM C 231.

1.8.4 Slump

Slump of the concrete, as delivered to the point of placement into the forms, shall be within the following limits. Slump shall be determined in accordance with ASTM C 143/C 143M.

Structural Element	Slump	
	Minimum	Maximum
Walls, columns and beams	2 in.	4 in.
Foundation walls, substructure walls, footings, slabs	1 in.	3 in.
Any structural concrete approved for placement by pumping:		
At pump	2 in.	6 in.
At discharge of line	1 in.	4 in.

When use of a plasticizing admixture conforming to ASTM C 1017/C 1017M or when a Type F or G high range water reducing admixture conforming to ASTM C 494/C 494M is permitted to increase the slump of concrete, concrete shall have a slump of 2 to 4 inches before the admixture is added and a maximum slump of 8 inches at the point of delivery after the admixture is added.

1.8.5 Concrete Temperature

The temperature of the concrete as delivered shall not exceed 90 degrees F.

When the ambient temperature during placing is 40 degrees F or less, or is expected to be at any time within 6 hours after placing, the temperature of the concrete as delivered shall be between 55 and 75 degrees F.

1.8.6 Size of Coarse Aggregate

The largest feasible nominal maximum size aggregate (NMSA) specified in paragraph AGGREGATES shall be used in each placement. However, nominal maximum size of aggregate shall not exceed any of the following: three-fourths of the minimum cover for reinforcing bars, three-fourths of the minimum clear spacing between reinforcing bars, one-fifth of the narrowest dimension between sides of forms, or one-third of the thickness of slabs or toppings.

1.8.7 Special Properties and Products

Concrete may contain admixtures other than air entraining agents, such as water reducers, superplasticizers, or set retarding agents to provide special properties to the concrete, if specified or approved. Any of these materials to be used on the project shall be used in the mix design studies.

1.9 MIXTURE PROPORTIONS

Concrete shall be composed of portland cement, other cementitious and pozzolanic materials as specified, aggregates, water and admixtures as specified.

1.9.1 Proportioning Studies for Normal Weight Concrete

Trial design batches, mixture proportioning studies, and testing requirements for various classes and types of concrete specified shall be the responsibility of the Contractor. Except as specified for flexural strength concrete, mixture proportions shall be based on compressive strength as determined by test specimens fabricated in accordance with ASTM C 192/C 192M and tested in accordance with ASTM C 39/C 39M. Samples of all materials used in mixture proportioning studies shall be representative of those proposed for use in the project and shall be accompanied by the manufacturer's or producer's test reports indicating compliance with these specifications. Trial mixtures having proportions, consistencies, and air content suitable for the work shall be made based on methodology described in ACI 211.1, using at least three different water-cement ratios for each type of mixture, which will produce a range of strength encompassing those required for each class and type of concrete required on the project. The maximum water-cement ratios required in subparagraph Water-Cement Ratio will be the equivalent water-cement ratio as determined by conversion from the weight ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace slag (GGBF slag) by the weight equivalency method as described in ACI 211.1. In the case where GGBF slag is used, the weight of the GGBF slag shall be included in the equations in ACI 211.1 for the term P, which is used to denote the weight of pozzolan. If pozzolan is used in the concrete mixture, the minimum pozzolan content shall be 15 percent by weight of the total cementitious material, and the maximum shall be 35 percent. Laboratory trial mixtures shall be designed for maximum permitted slump and air content. Separate sets of trial mixture studies shall be made for each combination of cementitious materials and each combination of admixtures proposed for use. No combination of either shall be used until proven by such studies, except that, if approved in writing and otherwise permitted by these specifications, an accelerator or a retarder may be used without separate trial mixture study. Separate trial

mixture studies shall also be made for concrete for any conveying or placing method proposed which requires special properties and for concrete to be placed in unusually difficult placing locations. The temperature of concrete in each trial batch shall be reported. For each water-cement ratio, at least three test cylinders for each test age shall be made and cured in accordance with ASTM C 192/C 192M. They shall be tested at 7 and 28 days in accordance with ASTM C 39/C 39M. From these test results, a curve shall be plotted showing the relationship between water-cement ratio and strength for each set of trial mix studies. In addition, a curve shall be plotted showing the relationship between 7 day and 28 day strengths. Each mixture shall be designed to promote easy and suitable concrete placement, consolidation and finishing, and to prevent segregation and excessive bleeding.

1.9.2 Omitted

1.9.3 Omitted

1.9.4 Average Compressive Strength Required for Mixtures

The mixture proportions selected during mixture design studies shall produce a required average compressive strength (f'_{cr}) exceeding the specified compressive strength (f'_c) by the amount indicated below. This required average compressive strength, f'_{cr} , will not be a required acceptance criteria during concrete production. However, whenever the daily average compressive strength at 28 days drops below f'_{cr} during concrete production, or daily average 7-day strength drops below a strength correlated with the 28-day f'_{cr} , the mixture shall be adjusted, as approved, to bring the daily average back up to f'_{cr} . During production, the required f'_{cr} shall be adjusted, as appropriate, based on the standard deviation being attained on the job.

1.9.4.1 Computations from Test Records

Where a concrete production facility has test records, a standard deviation shall be established in accordance with the applicable provisions of ACI 214.3R. Test records from which a standard deviation is calculated shall represent materials, quality control procedures, and conditions similar to those expected; shall represent concrete produced to meet a specified strength or strengths (f'_c) within 1,000 psi of that specified for proposed work; and shall consist of at least 30 consecutive tests. A strength test shall be the average of the strengths of two cylinders made from the same sample of concrete and tested at 28 days. Required average compressive strength f'_{cr} used as the basis for selection of concrete proportions shall be the larger of the equations that follow using the standard deviation as determined above:

$$f'_{cr} = f'_c + 1.34S \text{ where units are in psi}$$

$$f'_{cr} = f'_c + 2.33S - 500 \text{ where units are in psi}$$

Where S = standard deviation

Where a concrete production facility does not have test records meeting the requirements above but does have a record based on 15 to 29 consecutive tests, a standard deviation shall be established as the product of the calculated standard deviation and a modification factor from the following table:

NUMBER OF TESTS	MODIFICATION FACTOR FOR STANDARD DEVIATION
15	1.16
20	1.08
25	1.03
30 or more	1.00

1.9.4.2 Computations without Previous Test Records

When a concrete production facility does not have sufficient field strength test records for calculation of the standard deviation, the required average strength f'_{cr} shall be determined as follows:

- a. If the specified compressive strength f'_c is less than 3,000 psi,
 $f'_{cr} = f'_c + 1000$ psi
- b. If the specified compressive strength f'_c is 3,000 to 5,000 psi,
 $f'_{cr} = f'_c + 1,200$ psi
- c. If the specified compressive strength f'_c is over 5,000 psi,
 $f'_{cr} = f'_c + 1,400$ psi

1.10 STORAGE OF MATERIALS

Cement and other cementitious materials shall be stored in weathertight buildings, bins, or silos which will exclude moisture and contaminants and keep each material completely separated. Aggregate stockpiles shall be arranged and used in a manner to avoid excessive segregation and to prevent contamination with other materials or with other sizes of aggregates. Aggregate shall not be stored directly on ground unless a sacrificial layer is left undisturbed. Reinforcing bars and accessories shall be stored above the ground on platforms, skids or other supports. Other materials shall be stored in such a manner as to avoid contamination and deterioration. Admixtures which have been in storage at the project site for longer than 6 months or which have been subjected to freezing shall not be used unless retested and proven to meet the specified requirements. Materials shall be capable of being accurately identified after bundles or containers are opened.

1.11 GOVERNMENT ASSURANCE INSPECTION AND TESTING

Day-to day inspection and testing shall be the responsibility of the Contractor Quality Control (CQC) staff. However, representatives of the Contracting Officer can and will inspect construction as considered appropriate and will monitor operations of the Contractor's CQC staff. Government inspection or testing will not relieve the Contractor of any of his CQC responsibilities.

1.11.1 Materials

The Government will sample and test aggregates, cementitious materials, other materials, and concrete to determine compliance with the specifications as considered appropriate. The Contractor shall provide facilities and labor as may be necessary for procurement of representative

test samples. Samples of aggregates will be obtained at the point of batching in accordance with ASTM D 75. Other materials will be sampled from storage at the jobsite or from other locations as considered appropriate. Samples may be placed in storage for later testing when appropriate.

1.11.2 Fresh Concrete

Fresh concrete will be sampled as delivered in accordance with ASTM C 172 and tested in accordance with these specifications, as considered necessary.

1.11.3 Hardened Concrete

Tests on hardened concrete will be performed by the Government when such tests are considered necessary.

1.11.4 Inspection

Concrete operations may be tested and inspected by the Government as the project progresses. Failure to detect defective work or material will not prevent rejection later when a defect is discovered nor will it obligate the Government for final acceptance.

PART 2 PRODUCTS

2.1 CEMENTITIOUS MATERIALS

Cementitious Materials shall be portland cement, portland-pozzolan cement, portland blast-furnace slag cement, or portland cement in combination with pozzolan or ground granulated blast furnace slag and shall conform to appropriate specifications listed below. Use of cementitious materials in concrete which will have surfaces exposed in the completed structure shall be restricted so there is no change in color, source, or type of cementitious material.

2.1.1 Portland Cement

ASTM C 150, Type I low alkali with a maximum 15 percent amount of tricalcium aluminate, or Type II low alkali including false set requirements.

2.1.2 Omitted

2.1.3 Omitted

2.1.4 Pozzolan (Fly Ash)

ASTM C 618, Class F with the optional requirements for multiple factor, drying shrinkage, and uniformity from Table 2A of ASTM C 618. Requirement for maximum alkalis from Table 1A of ASTM C 618 shall apply. If pozzolan is used, it shall never be less than 15 percent nor more than 35 percent by weight of the total cementitious material. The Contractor shall comply with EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS.

2.1.5 Ground Granulated Blast-Furnace (GGBF) Slag

ASTM C 989, Grade 120.

2.2 AGGREGATES

Aggregates shall conform to the following.

2.2.1 Fine Aggregate

Fine aggregate shall conform to the quality and gradation requirements of ASTM C 33.

2.2.2 Coarse Aggregate

Coarse aggregate shall conform to ASTM C 33, Class 5S, size designation 59.

2.3 CHEMICAL ADMIXTURES

Chemical admixtures, when required or permitted, shall conform to the appropriate specification listed. Admixtures shall be furnished in liquid form and of suitable concentration for easy, accurate control of dispensing.

2.3.1 Air-Entraining Admixture

ASTM C 260 and shall consistently entrain the air content in the specified ranges under field conditions.

2.3.2 Accelerating Admixture

ASTM C 494/C 494M, Type C or E, except that calcium chloride or admixtures containing calcium chloride shall not be used.

2.3.3 Water-Reducing or Retarding Admixture

ASTM C 494/C 494M, Type A, B, or D, except that the 6-month and 1-year compressive and flexural strength tests are waived.

2.3.4 High-Range Water Reducer

ASTM C 494/C 494M, Type F or G, except that the 6-month and 1-year strength requirements are waived. The admixture shall be used only when approved in writing, such approval being contingent upon particular mixture control as described in the Contractor's Quality Control Plan and upon performance of separate mixture design studies.

2.3.5 Omitted

2.3.6 Omitted

2.3.7 Other Chemical Admixtures

Chemical admixtures for use in producing flowing concrete shall comply with ASTM C 1017/C 1017M, Type I or II. These admixtures shall be used only when approved in writing, such approval being contingent upon particular mixture control as described in the Contractor's Quality Control Plan and upon performance of separate mixture design studies.

2.4 CURING MATERIALS

2.4.1 Impervious-Sheet

Impervious-sheet materials shall conform to ASTM C 171, type optional, except, that polyethylene sheet shall not be used.

2.4.2 Membrane-Forming Compound

Membrane-Forming curing compound shall conform to ASTM C 309, Type 1-D or 2, except that only a styrene acrylate or chlorinated rubber compound meeting Class B requirements shall be used for surfaces that are to be painted or are to receive bituminous roofing, or waterproofing, or floors that are to receive adhesive applications of resilient flooring. The curing compound selected shall be compatible with any subsequent paint, roofing, waterproofing, or flooring specified. Nonpigmented compound shall contain a fugitive dye, and shall have the reflective requirements in ASTM C 309 waived.

2.4.3 Burlap and Cotton Mat

Burlap and cotton mat used for curing shall conform to AASHTO M 182.

2.5 WATER

Water for mixing and curing shall be fresh, clean, potable, and free of injurious amounts of oil, acid, salt, or alkali, except that non-potable water may be used if it meets the requirements of COE CRD-C 400.

2.6 NONSHRINK GROUT

Nonshrink grout shall conform to ASTM C 1107, Grade C, and shall be a commercial formulation suitable for the proposed application.

2.7 OMITTED

2.8 LATEX BONDING AGENT

Latex agents for bonding fresh to hardened concrete shall conform to ASTM C 1059.

2.9 EPOXY RESIN

Epoxy resins for use in repairs shall conform to ASTM C 881, Type V, Grade 2. Class as appropriate to the existing ambient and surface temperatures.

2.10 EMBEDDED ITEMS

Embedded items shall be of the size and type indicated or as needed for the application. Dovetail slots shall be galvanized steel. Hangers for suspended ceilings shall be as specified in Section 09510 ACOUSTICAL CEILINGS. Inserts for shelf angles and bolt hangers shall be of malleable iron or cast or wrought steel.

2.11 FLOOR HARDENER

Floor hardener shall be a colorless aqueous solution containing zinc silicofluoride, magnesium silicofluoride, or sodium silicofluoride. These silicofluorides can be used individually or in combination. Proprietary hardeners may be used if approved in writing by the Contracting Officer.

2.12 OMITTED

2.13 VAPOR BARRIER

Vapor barrier shall be polyethylene sheeting with a minimum thickness of 6

mils or other equivalent material having a vapor permeance rating not exceeding 0.5 perms as determined in accordance with ASTM E 96.

2.14 JOINT MATERIALS

2.14.1 Joint Fillers and Sealers

Expansion joint fillers shall be preformed materials conforming to ASTM D 1752. Materials for and sealing of joints shall conform to the requirements of Section 07900A JOINT SEALING.

2.14.2 Contraction Joints in Slabs

Sawable type contraction joint inserts shall conform to COE CRD-C 540. Nonsawable joint inserts shall have sufficient stiffness to permit placement in plastic concrete without undue deviation from a straight line and shall conform to the physical requirements of COE CRD-C 540, with the exception of Section 3.4 "Resistance to Sawing". Plastic inserts shall be polyvinyl chloride conforming to the materials requirements of COE CRD-C 572.

2.15 SYNTHETIC FIBERS FOR REINFORCING

Synthetic fibers shall conform to ASTM C 1116, Type III, Synthetic Fiber, and as follows. Fibers shall be 100 percent virgin polypropylene fibrillated fibers containing no reprocessed olefin materials. Fibers shall have a specific gravity of 0.9, a minimum tensile strength of 70 ksi graded per manufacturer, and specifically manufactured to an optimum gradation for use as concrete secondary reinforcement.

2.16 FLOATING FLOOR SYSTEM MATERIAL

Provide a system in the hydraulic equipment room composed of isolation pads, low density acoustical insulation sheets, forming sheet or panel and isolation joist filler to create a platform and surrounding isolation for a concrete floor slab structurally and acoustically cushioned and isolated from the structural floor slab. The materials shall be components of a coherent system, the product of a single manufacturer, and shall provide an STC in place of not less than 73. The components described herein are based on one manufacturer's system, but any system providing the same acoustical and structural performance shall be acceptable.

2.16.1 Underslab Isolation Material

Underslab isolation material shall consist of high density glass fiber pads, 1 inch thick, bonded to a 1-1/2 inches thick roll of glass fiber acoustic material with an NRC of 0.87. Pads shall be spaced at 12 inches on centers each way. Load carrying capacity of the system shall be 200 psf in open areas with a safety factor of 2.

2.16.2 Forming Board for Concrete

Forming boards for concrete shall be 4-ply exterior plywood, not less than 1/2 inch thick. Board shall be covered with temporary waterproofing membrane during pouring.

2.16.3 Perimeter Isolation Board

Perimeter isolation board shall be 5/8 inch thick resilient board as recommended by the isolation system manufacturer.

PART 3 EXECUTION

3.1 PREPARATION FOR PLACING

Before commencing concrete placement, the following shall be performed. Surfaces to receive concrete shall be clean and free from frost, ice, mud, and water. Forms shall be in place, cleaned, coated, and adequately supported, in accordance with Section 03100A STRUCTURAL CONCRETE FORMWORK. Reinforcing steel shall be in place, cleaned, tied, and adequately supported, in accordance with Section 03200A CONCRETE REINFORCEMENT. Transporting and conveying equipment shall be in-place, ready for use, clean, and free of hardened concrete and foreign material. Equipment for consolidating concrete shall be at the placing site and in proper working order. Equipment and material for curing and for protecting concrete from weather or mechanical damage shall be at the placing site, in proper working condition and in sufficient amount for the entire placement. When hot, windy conditions during concreting appear probable, equipment and material shall be at the placing site to provide windbreaks, shading, fogging, or other action to prevent plastic shrinkage cracking or other damaging drying of the concrete.

3.1.1 Foundations

3.1.1.1 Concrete on Earth Foundations

Earth (subgrade, base, or subbase courses) surfaces upon which concrete is to be placed shall be clean, damp, and free from debris, frost, ice, and standing or running water. Prior to placement of concrete, the foundation shall be well drained and shall be satisfactorily graded and uniformly compacted.

3.1.1.2 Omitted

3.1.1.3 Excavated Surfaces in Lieu of Forms

Concrete for footings and walls may be placed directly against the soil provided the earth or rock has been carefully trimmed, is uniform and stable, and meets the compaction requirements of Section 02315A EXCAVATION, FILLING, AND BACKFILLING FOR BUILDINGS. The concrete shall be placed without becoming contaminated by loose material, and the outline of the concrete shall be within the specified tolerances.

3.1.2 Preparation of Previously Placed Concrete

Concrete surfaces to which other concrete is to be bonded shall be abraded in an approved manner that will expose sound aggregate uniformly without damaging the concrete. Laitance and loose particles shall be removed. Surfaces shall be thoroughly washed and shall be moist but without free water when concrete is placed.

3.1.3 Vapor Barrier

Vapor barrier shall be provided beneath the interior on-grade concrete floor slabs. The greatest widths and lengths practicable shall be used to eliminate joints wherever possible. Joints shall be lapped a minimum of 12 inches. Torn, punctured, or damaged vapor barrier material shall be removed and new vapor barrier shall be provided prior to placing concrete. For minor repairs, patches may be made using laps of at least 12 inches.

Lapped joints shall be sealed and edges patched with pressure-sensitive adhesive or tape not less than 2 inches wide and compatible with the membrane. Vapor barrier shall be placed directly on underlying subgrade, base course, or capillary water barrier, unless it consists of crushed material or large granular material which could puncture the vapor barrier.

In this case, the surface shall be choked with a light layer of sand, as approved, before placing the vapor barrier. A 2 inch layer of compacted, clean concrete sand (fine aggregate) shall be placed on top of the vapor barrier before placing concrete. Concrete placement shall be controlled so as to prevent damage to the vapor barrier, or any covering sand.

3.1.4 Omitted

3.1.5 Embedded Items

Before placement of concrete, care shall be taken to determine that all embedded items are firmly and securely fastened in place as indicated on the drawings, or required. Conduit and other embedded items shall be clean and free of oil and other foreign matter such as loose coatings or rust, paint, and scale. The embedding of wood in concrete will be permitted only when specifically authorized or directed. Voids in sleeves, inserts, and anchor slots shall be filled temporarily with readily removable materials to prevent the entry of concrete into voids. Welding shall not be performed on embedded metals within 1 foot of the surface of the concrete. Tack welding shall not be performed on or to embedded items.

3.2 CONCRETE PRODUCTION

3.2.1 Batching, Mixing, and Transporting Concrete

Concrete shall either be batched and mixed onsite or shall be furnished from a ready-mixed concrete plant. Ready-mixed concrete shall be batched, mixed, and transported in accordance with ASTM C 94/C 94M, except as otherwise specified. Truck mixers, agitators, and nonagitating transporting units shall comply with NRMCA TMMB 100. Ready-mix plant equipment and facilities shall be certified in accordance with NRMCA QC 3. Approved batch tickets shall be furnished for each load of ready-mixed concrete. Site-mixed concrete shall conform to the following subparagraphs.

3.2.1.1 General

The batching plant shall be located off site close to the project. The batching, mixing and placing system shall have a capacity of at least 75 cubic yards per hour. The batching plant shall conform to the requirements of NRMCA CPMB 100 and as specified; however, rating plates attached to batch plant equipment are not required.

3.2.1.2 Batching Equipment

The batching controls shall be semiautomatic or automatic, as defined in NRMCA CPMB 100. A semiautomatic batching system shall be provided with interlocks such that the discharge device cannot be actuated until the indicated material is within the applicable tolerance. The batching system shall be equipped with accurate recorder or recorders that meet the requirements of NRMCA CPMB 100. The weight of water and admixtures shall be recorded if batched by weight. Separate bins or compartments shall be provided for each size group of aggregate and type of cementitious material, to prevent intermingling at any time. Aggregates shall be

weighed either in separate weigh batchers with individual scales or, provided the smallest size is batched first, cumulatively in one weigh batcher on one scale. Aggregate shall not be weighed in the same batcher with cementitious material. If both portland cement and other cementitious material are used, they may be batched cumulatively, provided that the portland cement is batched first. Water may be measured by weight or volume. Water shall not be weighed or measured cumulatively with another ingredient. Filling and discharging valves for the water metering or batching system shall be so interlocked that the discharge valve cannot be opened before the filling valve is fully closed. Piping for water and for admixtures shall be free from leaks and shall be properly valved to prevent backflow or siphoning. Admixtures shall be furnished as a liquid of suitable concentration for easy control of dispensing. An adjustable, accurate, mechanical device for measuring and dispensing each admixture shall be provided. Each admixture dispenser shall be interlocked with the batching and discharging operation of the water so that each admixture is separately batched and individually discharged automatically in a manner to obtain uniform distribution throughout the water as it is added to the batch in the specified mixing period. When use of truck mixers makes this requirement impractical, the admixture dispensers shall be interlocked with the sand batchers. Different admixtures shall not be combined prior to introduction in water and shall not be allowed to intermingle until in contact with the cement. Admixture dispensers shall have suitable devices to detect and indicate flow during dispensing or have a means for visual observation. The plant shall be arranged so as to facilitate the inspection of all operations at all times. Suitable facilities shall be provided for obtaining representative samples of aggregates from each bin or compartment, and for sampling and calibrating the dispensing of cementitious material, water, and admixtures. Filling ports for cementitious materials bins or silos shall be clearly marked with a permanent sign stating the contents.

3.2.1.3 Scales

The weighing equipment shall conform to the applicable requirements of CPMB Concrete Plant Standard, and of NIST HB 44, except that the accuracy shall be plus or minus 0.2 percent of scale capacity. The Contractor shall provide standard test weights and any other auxiliary equipment required for checking the operating performance of each scale or other measuring devices. The tests shall be made at the specified frequency in the presence of a Government inspector. The weighing equipment shall be arranged so that the plant operator can conveniently observe all dials or indicators.

3.2.1.4 Batching Tolerances

(A) Tolerances with Weighing Equipment

MATERIAL	PERCENT OF REQUIRED WEIGHT
Cementitious materials	0 to plus 2
Aggregate	plus or minus 2
Water	plus or minus 1
Chemical admixture	0 to plus 6

(B) Tolerances with Volumetric Equipment

For volumetric batching equipment used for water and admixtures, the following tolerances shall apply to the required volume of material being batched:

MATERIAL	PERCENT OF REQUIRED MATERIAL
Water:	plus or minus 1 percent
Chemical admixtures:	0 to plus 6 percent

3.2.1.5 Moisture Control

The plant shall be capable of ready adjustment to compensate for the varying moisture content of the aggregates and to change the weights of the materials being batched.

3.2.1.6 Concrete Mixers

Mixers shall be stationary mixers or truck mixers. Mixers shall be capable of combining the materials into a uniform mixture and of discharging this mixture without segregation. The mixers shall not be charged in excess of the capacity recommended by the manufacturer. The mixers shall be operated at the drum or mixing blade speed designated by the manufacturer. The mixers shall be maintained in satisfactory operating condition, and the mixer drums shall be kept free of hardened concrete. Should any mixer at any time produce unsatisfactory results, its use shall be promptly discontinued until it is repaired.

3.2.1.7 Stationary Mixers

Concrete plant mixers shall be drum-type mixers of tilting, nontilting, horizontal-shaft, or vertical-shaft type, or shall be pug mill type and shall be provided with an acceptable device to lock the discharge mechanism until the required mixing time has elapsed. The mixing time and uniformity shall conform to all the requirements in ASTM C 94/C 94M applicable to central-mixed concrete.

3.2.1.8 Truck Mixers

Truck mixers, the mixing of concrete therein, and concrete uniformity shall conform to the requirements of ASTM C 94/C 94M. A truck mixer may be used either for complete mixing (transit-mixed) or to finish the partial mixing done in a stationary mixer (shrink-mixed). Each truck shall be equipped with two counters from which it is possible to determine the number of revolutions at mixing speed and the number of revolutions at agitating speed. Or, if approved in lieu of this, the number of revolutions shall be marked on the batch tickets. Water shall not be added at the placing site unless specifically approved; and in no case shall it exceed the specified w/c. Any such water shall be injected at the base of the mixer, not at the discharge end.

3.3 OMITTED

3.4 OMITTED

3.5 FIBER REINFORCED CONCRETE

Fiber reinforced concrete shall conform to ASTM C 1116 and as follows, using the fibers specified in PART 2. A minimum of 1.5 pounds of fibers

per cubic yard of concrete shall be used. Fibers shall be added at the batch plant. The services of a qualified technical representative shall be provided to instruct the concrete supplier in proper batching and mixing of materials to be provided.

3.6 TRANSPORTING CONCRETE TO PROJECT SITE

Concrete shall be transported to the placing site in truck mixers.

3.7 CONVEYING CONCRETE ON SITE

Concrete shall be conveyed from mixer or transporting unit to forms as rapidly as possible and within the time interval specified by methods which will prevent segregation or loss of ingredients using following equipment. Conveying equipment shall be cleaned before each placement.

3.7.1 Buckets

The interior hopper slope shall be not less than 58 degrees from the horizontal, the minimum dimension of the clear gate opening shall be at least 5 times the nominal maximum-size aggregate, and the area of the gate opening shall not be less than 2 square feet. The maximum dimension of the gate opening shall not be greater than twice the minimum dimension. The bucket gates shall be essentially grout tight when closed and may be manually, pneumatically, or hydraulically operated except that buckets larger than 2 cubic yards shall not be manually operated. The design of the bucket shall provide means for positive regulation of the amount and rate of deposit of concrete in each dumping position.

3.7.2 Omitted

3.7.3 Omitted

3.7.4 Chutes

When concrete can be placed directly from a truck mixer, agitator, or nonagitating equipment, the chutes normally attached to this equipment by the manufacturer may be used. A discharge deflector shall be used when required by the Contracting Officer. Separate chutes and other similar equipment will not be permitted for conveying concrete.

3.7.5 Omitted

3.7.6 Concrete Pumps

Concrete may be conveyed by positive displacement pump when approved. The pumping equipment shall be piston or squeeze pressure type; pneumatic placing equipment shall not be used. The pipeline shall be rigid steel pipe or heavy-duty flexible hose. The inside diameter of the pipe shall be at least 3 times the nominal maximum-size coarse aggregate in the concrete mixture to be pumped but not less than 4 inches. Aluminum pipe shall not be used.

3.8 PLACING CONCRETE

Mixed concrete shall be discharged within 1-1/2 hours or before the mixer drum has revolved 300 revolutions, whichever comes first after the introduction of the mixing water to the cement and aggregates. When the concrete temperature exceeds 85 degrees F, the time shall be reduced to 45 minutes. Concrete shall be placed within 15 minutes after it has been

discharged from the transporting unit. Concrete shall be handled from mixer or transporting unit to forms in a continuous manner until the approved unit of operation is completed. Adequate scaffolding, ramps and walkways shall be provided so that personnel and equipment are not supported by in-place reinforcement. Placing will not be permitted when the sun, heat, wind, or limitations of facilities furnished by the Contractor prevent proper consolidation, finishing and curing. Sufficient placing capacity shall be provided so that concrete can be kept free of cold joints.

3.8.1 Depositing Concrete

Concrete shall be deposited as close as possible to its final position in the forms, and there shall be no vertical drop greater than 5 feet except where suitable equipment is provided to prevent segregation and where specifically authorized. Depositing of the concrete shall be so regulated that it will be effectively consolidated in horizontal layers not more than 12 inches thick, except that all slabs shall be placed in a single layer. Concrete to receive other construction shall be screeded to the proper level. Concrete shall be deposited continuously in one layer or in layers so that fresh concrete is deposited on in-place concrete that is still plastic. Fresh concrete shall not be deposited on concrete that has hardened sufficiently to cause formation of seams or planes of weakness within the section. Concrete that has surface dried, partially hardened, or contains foreign material shall not be used. When temporary spreaders are used in the forms, the spreaders shall be removed as their service becomes unnecessary. Concrete shall not be placed in slabs over columns and walls until concrete in columns and walls has been in-place at least two hours or until the concrete begins to lose its plasticity. Concrete for beams, girders, brackets, column capitals, haunches, and drop panels shall be placed at the same time as concrete for adjoining slabs.

3.8.2 Consolidation

Immediately after placing, each layer of concrete shall be consolidated by internal vibrators, except for slabs 4 inches thick or less. The vibrators shall at all times be adequate in effectiveness and number to properly consolidate the concrete; a spare vibrator shall be kept at the jobsite during all concrete placing operations. The vibrators shall have a frequency of not less than 10,000 vibrations per minute, an amplitude of at least 0.025 inch, and the head diameter shall be appropriate for the structural member and the concrete mixture being placed. Vibrators shall be inserted vertically at uniform spacing over the area of placement. The distance between insertions shall be approximately 1-1/2 times the radius of action of the vibrator so that the area being vibrated will overlap the adjacent just-vibrated area by a reasonable amount. The vibrator shall penetrate rapidly to the bottom of the layer and at least 6 inches into the preceding layer if there is such. Vibrator shall be held stationary until the concrete is consolidated and then vertically withdrawn slowly while operating. Form vibrators shall not be used unless specifically approved and unless forms are constructed to withstand their use. Vibrators shall not be used to move concrete within the forms. Slabs 4 inches and less in thickness shall be consolidated by properly designed vibrating screeds or other approved technique. Excessive vibration of lightweight concrete resulting in segregation or flotation of coarse aggregate shall be prevented. Frequency and amplitude of vibrators shall be determined in accordance with COE CRD-C 521. Grate tampers ("jitterbugs") shall not be used.

3.8.3 Cold Weather Requirements

Special protection measures, approved by the Contracting Officer, shall be used if freezing temperatures are anticipated before the expiration of the specified curing period. The ambient temperature of the air where concrete is to be placed and the temperature of surfaces to receive concrete shall be not less than 40 degrees F. The temperature of the concrete when placed shall be not less than 50 degrees F nor more than 75 degrees F. Heating of the mixing water or aggregates will be required to regulate the concrete placing temperature. Materials entering the mixer shall be free from ice, snow, or frozen lumps. Salt, chemicals or other materials shall not be incorporated in the concrete to prevent freezing. Upon written approval, an accelerating admixture conforming to ASTM C 494/C 494M, Type C or E may be used, provided it contains no calcium chloride. Calcium chloride shall not be used.

3.8.4 Hot Weather Requirements

When the ambient temperature during concrete placing is expected to exceed 85 degrees F, the concrete shall be placed and finished with procedures previously submitted and as specified herein. The concrete temperature at time of delivery to the forms shall not exceed the temperature shown in the table below when measured in accordance with ASTM C 1064/C 1064M. Cooling of the mixing water or aggregates or placing concrete in the cooler part of the day may be required to obtain an adequate placing temperature. A retarder may be used, as approved, to facilitate placing and finishing. Steel forms and reinforcements shall be cooled as approved prior to concrete placement when steel temperatures are greater than 120 degrees F. Conveying and placing equipment shall be cooled if necessary to maintain proper concrete-placing temperature.

Maximum Allowable Concrete Placing Temperature

Relative Humidity, Percent, During Time of Concrete Placement	Maximum Allowable Concrete Temperature Degrees
Greater than 60	90 F
40-60	85 F
Less than 40	80 F

3.8.5 Prevention of Plastic Shrinkage Cracking

During hot weather with low humidity, and particularly with appreciable wind, as well as interior placements when space heaters produce low humidity, the Contractor shall be alert to the tendency for plastic shrinkage cracks to develop and shall institute measures to prevent this. Particular care shall be taken if plastic shrinkage cracking is potentially imminent and especially if it has developed during a previous placement. Periods of high potential for plastic shrinkage cracking can be anticipated by use of Fig. 2.1.5 of ACI 305R. In addition the concrete placement shall be further protected by erecting shades and windbreaks and by applying fog sprays of water, sprinkling, ponding or wet covering. Plastic shrinkage cracks that occur shall be filled by injection of epoxy resin as directed, after the concrete hardens. Plastic shrinkage cracks shall never be troweled over or filled with slurry.

3.8.6 Omitted

3.8.7 Omitted

3.8.8 Placing Flowable Concrete

If a plasticizing admixture conforming to ASTM C 1017/C 1017M is used or if a Type F or G high range water reducing admixture is permitted to increase the slump, the concrete shall meet all requirements of paragraph GENERAL REQUIREMENTS in PART 1. Extreme care shall be used in conveying and placing the concrete to avoid segregation. Consolidation and finishing shall meet all requirements of paragraphs Placing Concrete, Finishing Formed Surfaces, and Finishing Unformed Surfaces. No relaxation of requirements to accommodate flowable concrete will be permitted.

3.9 JOINTS

Joints shall be located and constructed as indicated or approved. Joints not indicated on the drawings shall be located and constructed to minimize the impact on the strength of the structure. In general, such joints shall be located near the middle of the spans of supported slabs, beams, and girders unless a beam intersects a girder at this point, in which case the joint in the girder shall be offset a distance equal to twice the width of the beam. Joints in walls and columns shall be at the underside of floors, slabs, beams, or girders and at the tops of footings or floor slabs, unless otherwise approved. Joints shall be perpendicular to the main reinforcement. All reinforcement shall be continued across joints; except that reinforcement or other fixed metal items shall not be continuous through expansion joints, or through construction or contraction joints in slabs on grade. Reinforcement shall be 2 inches clear from each joint. Except where otherwise indicated, construction joints between interior slabs on grade and vertical surfaces shall consist of 30 pound asphalt-saturated felt, extending for the full depth of the slab. The perimeters of the slabs shall be free of fins, rough edges, spalling, or other unsightly appearance. Reservoir for sealant for construction and contraction joints in slabs shall be formed to the dimensions shown on the drawings by removing snap-out joint-forming inserts, by sawing sawable inserts, or by sawing to widen the top portion of sawed joints. Joints to be sealed shall be cleaned and sealed as indicated and in accordance with Section 07900A JOINT SEALING.

3.9.1 Construction Joints

For concrete other than slabs on grade, construction joints shall be located so that the unit of operation does not exceed 30 feet. Concrete shall be placed continuously so that each unit is monolithic in construction. Fresh concrete shall not be placed against adjacent hardened concrete until it is at least 24 hours old. Construction joints shall be located as indicated or approved. Where concrete work is interrupted by weather, end of work shift or other similar type of delay, location and type of construction joint shall be subject to approval of the Contracting Officer. Unless otherwise indicated and except for slabs on grade, reinforcing steel shall extend through construction joints. Construction joints in slabs on grade shall be keyed or doweled as shown. Concrete columns, walls, or piers shall be in place at least 2 hours, or until the concrete begins to lose its plasticity, before placing concrete for beams, girders, or slabs thereon. In walls having door or window openings, lifts shall terminate at the top and bottom of the opening. Other lifts shall terminate at such levels as to conform to structural requirements or architectural details. Where horizontal construction joints in walls or columns are required, a strip of 1 inch-square-edge lumber, bevelled and

oiled to facilitate removal, shall be tacked to the inside of the forms at the construction joint. Concrete shall be placed to a point 1 inch above the underside of the strip. The strip shall be removed 1 hour after the concrete has been placed, and any irregularities in the joint line shall be leveled off with a wood float, and all laitance shall be removed. Prior to placing additional concrete, horizontal construction joints shall be prepared as specified in paragraph Previously Placed Concrete.

3.9.2 Contraction Joints in Slabs on Grade

Contraction joints shall be located and detailed as shown on the drawings. Contraction Joints shall be produced by forming a weakened plane in the concrete slab by use of rigid inserts impressed in the concrete during placing operations use of snap-out plastic joint forming inserts or sawing a continuous slot with a concrete saw. Regardless of method used to produce the weakened plane, it shall be 1/4 the depth of the slab thickness and between 1/8 and 3/16 inch wide. For saw-cut joints, cutting shall be timed properly with the set of the concrete. Cutting shall be started as soon as the concrete has hardened sufficiently to prevent raveling of the edges of the saw cut. Cutting shall be completed before shrinkage stresses become sufficient to produce cracking. Reservoir for joint sealant shall be formed as previously specified.

3.9.3 Expansion Joints

Installation of expansion joints and sealing of these joints shall conform to the requirements of Section 03150A EXPANSION JOINTS AND CONTRACTION JOINTS, and Section 07900A JOINT SEALING.

3.10 FINISHING FORMED SURFACES

Forms, form materials, and form construction are specified in Section 03100A STRUCTURAL CONCRETE FORMWORK. Finishing of formed surfaces shall be as specified herein. Unless another type of architectural or special finish is specified, surfaces shall be left with the texture imparted by the forms except that defective surfaces shall be repaired. Unless painting of surfaces is required, uniform color of the concrete shall be maintained by use of only one mixture without changes in materials or proportions for any structure or portion of structure that requires a Class A or B finish. Except for major defects, as defined hereinafter, surface defects shall be repaired as specified herein within 24 hours after forms are removed. Repairs of the so-called "plaster-type" will not be permitted in any location. Tolerances of formed surfaces shall conform to the requirements of ACI 117/117R. These tolerances apply to the finished concrete surface, not to the forms themselves; forms shall be set true to line and grade. Form tie holes requiring repair and other defects whose depth is at least as great as their surface diameter shall be repaired as specified in paragraph Damp-Pack Mortar Repair. Defects whose surface diameter is greater than their depth shall be repaired as specified in paragraph Repair of Major Defects. Repairs shall be finished flush with adjacent surfaces and with the same surface texture. The cement used for all repairs shall be a blend of job cement with white cement proportioned so that the final color after curing and aging will be the same as the adjacent concrete. Concrete with excessive honeycomb, or other defects which affect the strength of the member, will be rejected. Repairs shall be demonstrated to be acceptable and free from cracks or loose or drummy areas at the completion of the contract and, for Class A and B Finishes, shall be inconspicuous. Repairs not meeting these requirements will be rejected and shall be replaced.

3.10.1 Omitted

3.10.2 Class C Finish

Class C finish is required for all formed surfaces. Fins, ravelings, and loose material shall be removed, and, except as otherwise indicated or as specified in Section 03100A STRUCTURAL CONCRETE FORMWORK, holes left by removal of form ties shall be reamed and filled. Honeycomb and other defects more than 1/2 inch deep or more than 2 inches in diameter shall be repaired. Defects more than 2 inches in diameter shall be cut back to sound concrete, but in all cases at least 1 inch deep.

3.11 REPAIRS

3.11.1 Damp-Pack Mortar Repair

Form tie holes requiring repair and other defects whose depth is at least as great as their surface diameter but not over 4 inches shall be repaired by the damp-pack mortar method. Form tie holes shall be reamed and other similar defects shall be cut out to sound concrete. The void shall then be thoroughly cleaned, thoroughly wetted, brush-coated with a thin coat of neat cement grout and filled with mortar. Mortar shall be a stiff mix of 1 part portland cement to 2 parts fine aggregate passing the No. 16 mesh sieve, and minimum amount of water. Only sufficient water shall be used to produce a mortar which, when used, will stick together on being molded into a ball by a slight pressure of the hands and will not exude water but will leave the hands damp. Mortar shall be mixed and allowed to stand for 30 to 45 minutes before use with remixing performed immediately prior to use. Mortar shall be thoroughly tamped in place in thin layers using a hammer and hardwood block. Holes passing entirely through walls shall be completely filled from the inside face by forcing mortar through to the outside face. All holes shall be packed full. Damp-pack repairs shall be moist cured for at least 48 hours.

3.11.2 Repair of Major Defects

Major defects will be considered to be those more than 1/2 inch in diameter and, for Class C finishes, more than 2 inches in diameter. Also included are any defects of any kind whose depth is over 4 inches or whose surface diameter is greater than their depth. Major defects shall be repaired as specified below.

3.11.2.1 Surface Application of Mortar Repair

Defective concrete shall be removed, and removal shall extend into completely sound concrete. Approved equipment and procedures which will not cause cracking or microcracking of the sound concrete shall be used. If reinforcement is encountered, concrete shall be removed so as to expose the reinforcement for at least 2 inches on all sides. All such defective areas greater than 12 square inches shall be outlined by saw cuts at least 1 inch deep. Defective areas less than 12 square inches shall be outlined by a 1 inch deep cut with a core drill in lieu of sawing. All saw cuts shall be straight lines in a rectangular pattern in line with the formwork panels. After concrete removal, the surface shall be thoroughly cleaned by high pressure washing to remove all loose material. Surfaces shall be kept continually saturated for the first 12 of the 24 hours immediately before placing mortar and shall be damp but not wet at the time of commencing mortar placement. The Contractor, at his option, may use either

hand-placed mortar or mortar placed with a mortar gun. If hand-placed mortar is used, the edges of the cut shall be perpendicular to the surface of the concrete. The prepared area shall be brush-coated with a thin coat of neat cement grout. The repair shall then be made using a stiff mortar, preshrunk by allowing the mixed mortar to stand for 30 to 45 minutes and then remixed, thoroughly tamped into place in thin layers. If hand-placed mortar is used, the Contractor shall test each repair area for drumminess by firm tapping with a hammer and shall inspect for cracks, both in the presence of the Contracting Officer's representative, immediately before completion of the contract, and shall replace any showing drumminess or cracking. If mortar placed with a mortar gun is used, the gun shall be a small compressed air-operated gun to which the mortar is slowly hand fed and which applies the mortar to the surface as a high-pressure stream, as approved. Repairs made using shotcrete equipment will not be accepted. The mortar used shall be the same mortar as specified for damp-pack mortar repair. If gun-placed mortar is used, the edges of the cut shall be beveled toward the center at a slope of 1:1. All surface applied mortar repairs shall be continuously moist cured for at least 7 days. Moist curing shall consist of several layers of saturated burlap applied to the surface immediately after placement is complete and covered with polyethylene sheeting, all held closely in place by a sheet of plywood or similar material rigidly braced against it. Burlap shall be kept continually wet.

3.11.2.2 Repair of Deep and Large Defects

Deep and large defects will be those that are more than 6 inches deep and also have an average diameter at the surface more than 18 inches or that are otherwise so identified by the Project Office. The portion of the structure containing such defects shall be completely removed and replaced.

3.12 FINISHING UNFORMED SURFACES

The finish of all unformed surfaces shall meet the requirements of paragraph Tolerances in PART 1, when tested as specified herein.

3.12.1 General

The ambient temperature of spaces adjacent to unformed surfaces being finished and of the base on which concrete will be placed shall be not less than 50 degrees F. In hot weather all requirements of paragraphs Hot Weather Requirements and Prevention of Plastic Shrinkage Cracking shall be met. Unformed surfaces that are not to be covered by additional concrete or backfill shall have a float finish, with additional finishing as specified below, and shall be true to the elevation shown on the drawings. Surfaces to receive additional concrete or backfill shall be brought to the elevation shown on the drawings, properly consolidated, and left true and regular. Unless otherwise shown on the drawings, exterior surfaces shall be sloped for drainage, as directed. Where drains are provided, interior floors shall be evenly sloped to the drains. Joints shall be carefully made with a jointing or edging tool. The finished surfaces shall be protected from stains or abrasions. Grate tampers or "jitterbugs" shall not be used for any surfaces. The dusting of surfaces with dry cement or other materials or the addition of any water during finishing shall not be permitted. If bleedwater is present prior to finishing, the excess water shall be carefully dragged off or removed by absorption with porous materials such as burlap. During finishing operations, extreme care shall be taken to prevent over finishing or working water into the surface; this can cause "crazing" (surface shrinkage cracks which appear after hardening)

of the surface. Any slabs with surfaces which exhibit significant crazing shall be removed and replaced. During finishing operations, surfaces shall be checked with a 10 foot straightedge, applied in both directions at regular intervals while the concrete is still plastic, to detect high or low areas.

3.12.2 Rough Slab Finish

As a first finishing operation for unformed surfaces and as final finish for slabs to receive mortar setting beds, the surface shall receive a rough slab finish prepared as follows. The concrete shall be uniformly placed across the slab area, consolidated as previously specified, and then screeded with straightedge strikeoffs immediately after consolidation to bring the surface to the required finish level with no coarse aggregate visible. Side forms and screed rails shall be provided, rigidly supported, and set to exact line and grade. Allowable tolerances for finished surfaces apply only to the hardened concrete, not to forms or screed rails. Forms and screed rails shall be set true to line and grade. "Wet screeds" shall not be used.

3.12.3 Floated Finish

Slabs to receive more than a rough slab finish shall next be given a wood float finish. All slabs shall be given a float finish. The screeding shall be followed immediately by darbying or bull floating before bleeding water is present, to bring the surface to a true, even plane. Then, after the concrete has stiffened so that it will withstand a man's weight without imprint of more than 1/4 inch and the water sheen has disappeared, it shall be floated to a true and even plane free of ridges. Floating shall be performed by use of suitable hand floats or power driven equipment. Sufficient pressure shall be used on the floats to bring a film of moisture to the surface. Hand floats shall be made of wood, magnesium, or aluminum. Care shall be taken to prevent over-finishing or incorporating water into the surface.

3.12.4 Troweled Finish

Slabs exposed to view or receiving thin-coat finishes shall be given a trowel finish. After floating is complete and after the surface moisture has disappeared, unformed surfaces shall be steel-troweled to a smooth, even, dense finish, free from blemishes including trowel marks. In lieu of hand finishing, an approved power finishing machine may be used in accordance with the directions of the machine manufacturer. Additional trowelings shall be performed, either by hand or machine until the surface has been troweled 4 times, with waiting period between each. Care shall be taken to prevent blistering and if such occurs, troweling shall immediately be stopped and operations and surfaces corrected. A final hard steel troweling shall be done by hand, with the trowel tipped, and using hard pressure, when the surface is at a point that the trowel will produce a ringing sound. The finished surface shall be thoroughly consolidated and shall be essentially free of trowel marks and be uniform in texture and appearance. The concrete mixture used for troweled finished areas shall be adjusted, if necessary, in order to provide sufficient fines (cementitious material and fine sand) to finish properly.

3.12.5 Omitted

3.12.6 Non-Slip Finish

Non-slip floors shall be constructed in accordance with the following subparagraphs.

3.12.6.1 Broomed

Exterior walking surfaces shall be given a broomed finish. After floating, the surface shall be lightly steel troweled, and then carefully scored by pulling a hair push-type broom across the surface. Brooming shall be transverse to traffic or at right angles to the slope of the slab. After the end of the curing period, the surface shall be vigorously broomed with a coarse fiber broom to remove all loose or semi-detached particles.

3.13 FLOOR HARDENER

Areas as indicated on the drawings as having sealed finish (CS) shall be treated with floor hardener. Floor hardener shall be applied after the concrete has been cured and then air dried for 14 days. Three coats shall be applied, each the day after the preceding coat was applied. For the first application, one pound of the silicofluoride shall be dissolved in one gallon of water. For subsequent applications, the solution shall be two pounds of silicofluoride to each gallon of water. Floor should be mopped with clear water shortly after the preceding application has dried to remove encrusted salts. Proprietary hardeners shall be applied in accordance with the manufacturer's instructions. During application, area should be well ventilated. Precautions shall be taken when applying silicofluorides due to the toxicity of the salts. Any compound that contacts glass or aluminum should be immediately removed with clear water.

3.14 OMITTED

3.15 CURING AND PROTECTION

3.15.1 General

Concrete shall be cured by an approved method for the period of time given below:

All concrete	7 days
--------------	--------

Immediately after placement, concrete shall be protected from premature drying, extremes in temperatures, rapid temperature change, mechanical injury and damage from rain and flowing water for the duration of the curing period. Air and forms in contact with concrete shall be maintained at a temperature above 50 degrees F for the first 3 days and at a temperature above 32 degrees F for the remainder of the specified curing period. Exhaust fumes from combustion heating units shall be vented to the outside of the enclosure, and heaters and ducts shall be placed and directed so as not to cause areas of overheating and drying of concrete surfaces or to create fire hazards. Materials and equipment needed for adequate curing and protection shall be available and at the site prior to placing concrete. No fire or excessive heat, including welding, shall be permitted near or in direct contact with the concrete at any time. Except as otherwise permitted by paragraph Membrane Forming Curing Compounds, moist curing shall be provided for any areas to receive floor hardener, any paint or other applied coating, or to which other concrete is to be bonded.

Concrete containing silica fume shall be initially cured by fog misting during finishing, followed immediately by continuous moist curing. Except for plastic coated burlap, impervious sheeting alone shall not be used for curing.

3.15.2 Moist Curing

Concrete to be moist-cured shall be maintained continuously wet for the entire curing period, commencing immediately after finishing. If water or curing materials used stain or discolor concrete surfaces which are to be permanently exposed, the concrete surfaces shall be cleaned as approved. When wooden forms are left in place during curing, they shall be kept wet at all times. If steel forms are used in hot weather, nonsupporting vertical forms shall be broken loose from the concrete soon after the concrete hardens and curing water continually applied in this void. If the forms are removed before the end of the curing period, curing shall be carried out as on unformed surfaces, using suitable materials. Surfaces shall be cured by ponding, by continuous sprinkling, by continuously saturated burlap or cotton mats, or by continuously saturated plastic coated burlap. Burlap and mats shall be clean and free from any contamination and shall be completely saturated before being placed on the concrete. The Contractor shall have an approved work system to ensure that moist curing is continuous 24 hours per day.

3.15.3 Membrane Forming Curing Compounds

Concrete in areas receiving no applied finish may be cured with a nonpigmented curing compound containing a fugitive dye in lieu of moist curing. Membrane curing shall not be used on surfaces that are to receive any subsequent treatment depending on adhesion or bonding to the concrete, including surfaces to which a smooth finish is to be applied or other concrete to be bonded. However, a styrene acrylate or chlorinated rubber compound meeting ASTM C 309, Class B requirements, may be used for surfaces which are to be painted or are to receive bituminous roofing or waterproofing, or floors that are to receive adhesive applications of resilient flooring. The curing compound selected shall be compatible with any subsequent paint, roofing, waterproofing or flooring specified. Membrane curing compound shall not be used on surfaces that are maintained at curing temperatures with free steam. Curing compound shall be applied to formed surfaces immediately after the forms are removed and prior to any patching or other surface treatment except the cleaning of loose sand, mortar, and debris from the surface. All surfaces shall be thoroughly moistened with water. Curing compound shall be applied to slab surfaces as soon as the bleeding water has disappeared, with the tops of joints being temporarily sealed to prevent entry of the compound and to prevent moisture loss during the curing period. The curing compound shall be applied in a two-coat continuous operation by approved motorized power-spraying equipment operating at a minimum pressure of 75 psi, at a uniform coverage of not more than 400 square feet per gallon for each coat, and the second coat shall be applied perpendicular to the first coat. Concrete surfaces which have been subjected to rainfall within 3 hours after curing compound has been applied shall be resprayed by the method and at the coverage specified. Surfaces on which clear compound is used shall be shaded from direct rays of the sun for the first 3 days. Surfaces coated with curing compound shall be kept free of foot and vehicular traffic, and from other sources of abrasion and contamination during the curing period.

3.15.4 Omitted

3.15.5 Ponding or Immersion

Concrete shall be continually immersed throughout the curing period. Water shall not be more than 20 degrees F less than the temperature of the

concrete.

3.15.6 Cold Weather Curing and Protection

When the daily ambient low temperature is less than 32 degrees F the temperature of the concrete shall be maintained above 40 degrees F for the first seven days after placing. During the period of protection removal, the air temperature adjacent to the concrete surfaces shall be controlled so that concrete near the surface will not be subjected to a temperature differential of more than 25 degrees F as determined by suitable temperature measuring devices furnished by the Contractor, as required, and installed adjacent to the concrete surface and 2 inches inside the surface of the concrete. The installation of the thermometers shall be made by the Contractor as directed.

3.16 SETTING BASE PLATES AND BEARING PLATES

After being properly positioned, column base plates, bearing plates for beams and similar structural members, and machinery and equipment base plates shall be set to the proper line and elevation with damp-pack bedding mortar, except where nonshrink grout is indicated. The thickness of the mortar or grout shall be approximately 1/24 the width of the plate, but not less than 3/4 inch. Concrete and metal surfaces in contact with grout shall be clean and free of oil and grease, and concrete surfaces in contact with grout shall be damp and free of laitance when grout is placed. Nonshrink grout shall be used for structural bearing plates and machine bases.

3.16.1 Damp-Pack Bedding Mortar

Damp-pack bedding mortar shall consist of 1 part cement and 2-1/2 parts fine aggregate having water content such that a mass of mortar tightly squeezed in the hand will retain its shape but will crumble when disturbed.

The space between the top of the concrete and bottom of the bearing plate or base shall be packed with the bedding mortar by tamping or ramming with a bar or rod until it is completely filled.

3.16.2 Nonshrink Grout

Nonshrink grout shall be a ready-mixed material requiring only the addition of water. Water content shall be the minimum that will provide a flowable mixture and completely fill the space to be grouted without segregation, bleeding, or reduction of strength.

3.16.2.1 Mixing and Placing of Nonshrink Grout

Mixing and placing shall be in conformance with the material manufacturer's instructions and as specified therein. Ingredients shall be thoroughly dry-mixed before adding water. After adding water, the batch shall be mixed for 3 minutes. Batches shall be of size to allow continuous placement of freshly mixed grout. Grout not used within 30 minutes after mixing shall be discarded. The space between the top of the concrete or machinery-bearing surface and the plate shall be filled solid with the grout. Forms shall be of wood or other equally suitable material for completely retaining the grout on all sides and on top and shall be removed after the grout has set. The placed grout shall be carefully worked by rodding or other means to eliminate voids; however, overworking and breakdown of the initial set shall be avoided. Grout shall not be retempered or subjected to vibration from any source. Where clearances are

unusually small, placement shall be under pressure with a grout pump. Temperature of the grout, and of surfaces receiving the grout, shall be maintained at 65 to 85 degrees F until after setting.

3.16.2.2 Treatment of Exposed Surfaces

For metal-oxidizing nonshrink grout, exposed surfaces shall be cut back 1 inch and immediately covered with a parge coat of mortar consisting of 1 part portland cement and 2-1/2 parts fine aggregate by weight, with sufficient water to make a plastic mixture. The parge coat shall have a smooth finish. For other mortars or grouts, exposed surfaces shall have a smooth-dense finish and be left untreated. Curing shall comply with paragraph CURING AND PROTECTION.

3.17 TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL

The Contractor shall perform the inspection and tests described below and, based upon the results of these inspections and tests, shall take the action required and shall submit specified reports. When, in the opinion of the Contracting Officer, the concreting operation is out of control, concrete placement shall cease and the operation shall be corrected. The laboratory performing the tests shall be onsite and shall conform with ASTM C 1077. Materials may be subjected to check testing by the Government from samples obtained at the manufacturer, at transfer points, or at the project site. The Government will inspect the laboratory, equipment, and test procedures prior to start of concreting operations for conformance with ASTM C 1077.

3.17.1 Grading and Corrective Action

3.17.1.1 Fine Aggregate

At least once during each shift when the concrete plant is operating, there shall be one sieve analysis and fineness modulus determination in accordance with ASTM C 136 and COE CRD-C 104 for the fine aggregate or for each fine aggregate if it is batched in more than one size or classification. The location at which samples are taken may be selected by the Contractor as the most advantageous for control. However, the Contractor is responsible for delivering fine aggregate to the mixer within specification limits. When the amount passing on any sieve is outside the specification limits, the fine aggregate shall be immediately resampled and retested. If there is another failure on any sieve, the fact shall immediately reported to the Contracting Officer, concreting shall be stopped, and immediate steps taken to correct the grading.

3.17.1.2 Coarse Aggregate

At least once during each shift in which the concrete plant is operating, there shall be a sieve analysis in accordance with ASTM C 136 for each size of coarse aggregate. The location at which samples are taken may be selected by the Contractor as the most advantageous for production control. However, the Contractor shall be responsible for delivering the aggregate to the mixer within specification limits. A test record of samples of aggregate taken at the same locations shall show the results of the current test as well as the average results of the five most recent tests including the current test. The Contractor may adopt limits for control coarser than the specification limits for samples taken other than as delivered to the mixer to allow for degradation during handling. When the amount passing any sieve is outside the specification limits, the coarse aggregate shall

be immediately resampled and retested. If the second sample fails on any sieve, that fact shall be reported to the Contracting Officer. Where two consecutive averages of 5 tests are outside specification limits, the operation shall be considered out of control and shall be reported to the Contracting Officer. Concreting shall be stopped and immediate steps shall be taken to correct the grading.

3.17.2 Quality of Aggregates

Thirty days prior to the start of concrete placement, the Contractor shall perform all tests for aggregate quality required by ASTM C 33. In addition, after the start of concrete placement, the Contractor shall perform tests for aggregate quality at least every three months, and when the source of aggregate or aggregate quality changes. Samples tested after the start of concrete placement shall be taken immediately prior to entering the concrete mixer.

3.17.3 Scales, Batching and Recording

The accuracy of the scales shall be checked by test weights prior to start of concrete operations and at least once every three months. Such tests shall also be made as directed whenever there are variations in properties of the fresh concrete that could result from batching errors. Once a week the accuracy of each batching and recording device shall be checked during a weighing operation by noting and recording the required weight, recorded weight, and the actual weight batched. At the same time, the Contractor shall test and ensure that the devices for dispensing admixtures are operating properly and accurately. When either the weighing accuracy or batching accuracy does not comply with specification requirements, the plant shall not be operated until necessary adjustments or repairs have been made. Discrepancies in recording accuracies shall be corrected immediately.

3.17.4 Batch-Plant Control

The measurement of concrete materials including cementitious materials, each size of aggregate, water, and admixtures shall be continuously controlled. The aggregate weights and amount of added water shall be adjusted as necessary to compensate for free moisture in the aggregates. The amount of air-entraining agent shall be adjusted to control air content within specified limits. A report shall be prepared indicating type and source of cement used, type and source of pozzolan or slag used, amount and source of admixtures used, aggregate source, the required aggregate and water weights per cubic yard, amount of water as free moisture in each size of aggregate, and the batch aggregate and water weights per cubic yard for each class of concrete batched during each day's plant operation.

3.17.5 Concrete Mixture

- a. Air Content Testing. Air content tests shall be made when test specimens are fabricated. In addition, at least two tests for air content shall be made on randomly selected batches of each separate concrete mixture produced during each 8-hour period of concrete production. Additional tests shall be made when excessive variation in workability is reported by the placing foreman or Government inspector. Tests shall be made in accordance with ASTM C 231 for normal weight concrete and ASTM C 173 for lightweight concrete. Test results shall be plotted on control charts which shall at all times be readily available to

the Government and shall be submitted weekly. Copies of the current control charts shall be kept in the field by testing crews and results plotted as tests are made. When a single test result reaches either the upper or lower action limit, a second test shall immediately be made. The results of the two tests shall be averaged and this average used as the air content of the batch to plot on both the air content and the control chart for range, and for determining need for any remedial action. The result of each test, or average as noted in the previous sentence, shall be plotted on a separate control chart for each mixture on which an "average line" is set at the midpoint of the specified air content range from paragraph Air Entrainment. An upper warning limit and a lower warning limit line shall be set 1.0 percentage point above and below the average line, respectively. An upper action limit and a lower action limit line shall be set 1.5 percentage points above and below the average line, respectively. The range between each two consecutive tests shall be plotted on a secondary control chart for range where an upper warning limit is set at 2.0 percentage points and an upper action limit is set at 3.0 percentage points. Samples for air content may be taken at the mixer, however, the Contractor is responsible for delivering the concrete to the placement site at the stipulated air content. If the Contractor's materials or transportation methods cause air content loss between the mixer and the placement, correlation samples shall be taken at the placement site as required by the Contracting Officer, and the air content at the mixer controlled as directed.

- b. Air Content Corrective Action. Whenever points on the control chart for percent air reach either warning limit, an adjustment shall immediately be made in the amount of air-entraining admixture batched. As soon as practical after each adjustment, another test shall be made to verify the result of the adjustment. Whenever a point on the secondary control chart for range reaches the warning limit, the admixture dispenser shall be recalibrated to ensure that it is operating accurately and with good reproducibility. Whenever a point on either control chart reaches an action limit line, the air content shall be considered out of control and the concreting operation shall immediately be halted until the air content is under control. Additional air content tests shall be made when concreting is restarted.
- c. Slump Testing. In addition to slump tests which shall be made when test specimens are fabricated, at least four slump tests shall be made on randomly selected batches in accordance with ASTM C 143/C 143M for each separate concrete mixture produced during each 8-hour or less period of concrete production each day. Also, additional tests shall be made when excessive variation in workability is reported by the placing foreman or Government inspector. Test results shall be plotted on control charts which shall at all times be readily available to the Government and shall be submitted weekly. Copies of the current control charts shall be kept in the field by testing crews and results plotted as tests are made. When a single slump test reaches or goes beyond either the upper or lower action limit, a second test shall immediately be made. The results of the two tests shall be averaged and this average used as the slump of the batch to plot on both the control charts for slump and the chart for range, and for determining need for any remedial action. Limits shall be set

on separate control charts for slump for each type of mixture. The upper warning limit shall be set at 1/2 inch below the maximum allowable slump specified in paragraph Slump in PART 1 for each type of concrete and an upper action limit line and lower action limit line shall be set at the maximum and minimum allowable slumps, respectively, as specified in the same paragraph. The range between each consecutive slump test for each type of mixture shall be plotted on a single control chart for range on which an upper action limit is set at 2 inches. Samples for slump shall be taken at the mixer. However, the Contractor is responsible for delivering the concrete to the placement site at the stipulated slump. If the Contractor's materials or transportation methods cause slump loss between the mixer and the placement, correlation samples shall be taken at the placement site as required by the Contracting Officer, and the slump at the mixer controlled as directed.

- d. Slump Corrective Action. Whenever points on the control charts for slump reach the upper warning limit, an adjustment shall immediately be made in the batch weights of water and fine aggregate. The adjustments are to be made so that the total water content does not exceed that amount allowed by the maximum w/c ratio specified, based on aggregates which are in a saturated surface dry condition. When a single slump reaches the upper or lower action limit, no further concrete shall be delivered to the placing site until proper adjustments have been made. Immediately after each adjustment, another test shall be made to verify the correctness of the adjustment. Whenever two consecutive individual slump tests, made during a period when there was no adjustment of batch weights, produce a point on the control chart for range at or above the upper action limit, the concreting operation shall immediately be halted, and the Contractor shall take appropriate steps to bring the slump under control. Additional slump tests shall be made as directed.
- e. Temperature. The temperature of the concrete shall be measured when compressive strength specimens are fabricated. Measurement shall be in accordance with ASTM C 1064/C 1064M. The temperature shall be reported along with the compressive strength data.
- f. Strength Specimens. At least one set of test specimens shall be made, for compressive or flexural strength as appropriate, on each different concrete mixture placed during the day for each 500 cubic yards or portion thereof of that concrete mixture placed each day. Additional sets of test specimens shall be made, as directed by the Contracting Officer, when the mixture proportions are changed or when low strengths have been detected. A truly random (not haphazard) sampling plan shall be developed by the Contractor and approved by the Contracting Officer prior to the start of construction. The plan shall assure that sampling is done in a completely random and unbiased manner. A set of test specimens for concrete with a 28-day specified strength per paragraph Strength Requirements in PART 1 shall consist of four specimens, two to be tested at 7 days and two at 28 days. Test specimens shall be molded and cured in accordance with ASTM C 31/C 31M and tested in accordance with ASTM C 39/C 39M for test cylinders and ASTM C 78 for test beams. Results of all strength tests shall be reported immediately to the Contracting Officer. Quality control charts shall be kept for individual strength

"tests", ("test" as defined in paragraph Strength Requirements in PART 1) moving average of last 3 "tests" for strength, and moving average for range for the last 3 "tests" for each mixture. The charts shall be similar to those found in ACI 214.3R.

3.17.6 Inspection Before Placing

Foundations, construction joints, forms, and embedded items shall be inspected by the Contractor in sufficient time prior to each concrete placement in order to certify to the Contracting Officer that they are ready to receive concrete. The results of each inspection shall be reported in writing.

3.17.7 Placing

The placing foreman shall supervise placing operations, shall determine that the correct quality of concrete or grout is placed in each location as specified and as directed by the Contracting Officer, and shall be responsible for measuring and recording concrete temperatures and ambient temperature hourly during placing operations, weather conditions, time of placement, volume placed, and method of placement. The placing foreman shall not permit batching and placing to begin until it has been verified that an adequate number of vibrators in working order and with competent operators are available. Placing shall not be continued if any pile of concrete is inadequately consolidated. If any batch of concrete fails to meet the temperature requirements, immediate steps shall be taken to improve temperature controls.

3.17.8 Vibrators

The frequency and amplitude of each vibrator shall be determined in accordance with COE CRD-C 521 prior to initial use and at least once a month when concrete is being placed. Additional tests shall be made as directed when a vibrator does not appear to be adequately consolidating the concrete. The frequency shall be determined while the vibrator is operating in concrete with the tachometer being held against the upper end of the vibrator head while almost submerged and just before the vibrator is withdrawn from the concrete. The amplitude shall be determined with the head vibrating in air. Two measurements shall be taken, one near the tip and another near the upper end of the vibrator head, and these results averaged. The make, model, type, and size of the vibrator and frequency and amplitude results shall be reported in writing. Any vibrator not meeting the requirements of paragraph Consolidation, shall be immediately removed from service and repaired or replaced.

3.17.9 Curing Inspection

- a. Moist Curing Inspections. At least once each shift, and not less than twice per day on both work and non-work days, an inspection shall be made of all areas subject to moist curing. The surface moisture condition shall be noted and recorded.
- b. Moist Curing Corrective Action. When a daily inspection report lists an area of inadequate curing, immediate corrective action shall be taken, and the required curing period for those areas shall be extended by 1 day.
- c. Membrane Curing Inspection. No curing compound shall be applied until the Contractor has verified that the compound is properly

mixed and ready for spraying. At the end of each operation, the Contractor shall estimate the quantity of compound used by measurement of the container and the area of concrete surface covered, shall compute the rate of coverage in square feet per gallon, and shall note whether or not coverage is uniform.

- d. Membrane Curing Corrective Action. When the coverage rate of the curing compound is less than that specified or when the coverage is not uniform, the entire surface shall be sprayed again.

3.17.10 Cold-Weather Protection

At least once each shift and once per day on non-work days, an inspection shall be made of all areas subject to cold-weather protection. Any deficiencies shall be noted, corrected, and reported.

3.17.11 Mixer Uniformity

- a. Stationary Mixers. Prior to the start of concrete placing and once every 6 months when concrete is being placed, or once for every 75,000 cubic yards of concrete placed, whichever results in the shortest time interval, uniformity of concrete mixing shall be determined in accordance with ASTM C 94/C 94M.
- b. Truck Mixers. Prior to the start of concrete placing and at least once every 6 months when concrete is being placed, uniformity of concrete mixing shall be determined in accordance with ASTM C 94/C 94M. The truck mixers shall be selected randomly for testing. When satisfactory performance is found in one truck mixer, the performance of mixers of substantially the same design and condition of the blades may be regarded as satisfactory.
- c. Mixer Uniformity Corrective Action. When a mixer fails to meet mixer uniformity requirements, either the mixing time shall be increased, batching sequence changed, batch size reduced, or adjustments shall be made to the mixer until compliance is achieved.

3.17.12 Reports

All results of tests or inspections conducted shall be reported informally as they are completed and in writing daily. A weekly report shall be prepared for the updating of control charts covering the entire period from the start of the construction season through the current week. During periods of cold-weather protection, reports of pertinent temperatures shall be made daily. These requirements do not relieve the Contractor of the obligation to report certain failures immediately as required in preceding paragraphs. Such reports of failures and the action taken shall be confirmed in writing in the routine reports. The Contracting Officer has the right to examine all contractor quality control records.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 04 - MASONRY

MASONRY

08/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 SAMPLE MASONRY PANELS
 - 1.3.1 Configuration
 - 1.3.2 Composition
 - 1.3.3 Construction Method
 - 1.3.4 Usage
- 1.4 DELIVERY, HANDLING, AND STORAGE
 - 1.4.1 Masonry Units
 - 1.4.2 Reinforcement, Anchors, and Ties
 - 1.4.3 Cementitious Materials, Sand and Aggregates
- 1.5 OMITTED
- 1.6 QUALITY ASSURANCE
 - 1.6.1 Appearance
 - 1.6.2 Testing
 - 1.6.3 Spare Vibrator
 - 1.6.4 Bracing and Scaffolding

PART 2 PRODUCTS

- 2.1 GENERAL REQUIREMENTS
- 2.2 CLAY OR SHALE BRICK
 - 2.2.1 Solid Clay or Shale Brick
 - 2.2.2 Hollow Clay or Shale Brick
- 2.3 CONCRETE BRICK
- 2.4 CONCRETE MASONRY UNITS (CMU)
 - 2.4.1 Aggregates
 - 2.4.2 Kinds and Shapes
 - 2.4.2.1 Omitted
 - 2.4.2.2 Omitted
 - 2.4.3 Fire-Rated CMU
- 2.5 PRECAST CONCRETE ITEMS
 - 2.5.1 Lintels
- 2.6 CAST STONE ITEMS
- 2.7 OMITTED
- 2.8 MASONRY MORTAR
 - 2.8.1 Admixtures for Masonry Mortar
 - 2.8.2 Colored Mortar
 - 2.8.3 Hydrated Lime and Alternates
 - 2.8.4 Cement
 - 2.8.5 Pre-Mixed Mortar
 - 2.8.6 Sand and Water
- 2.9 WATER-REPELLANT ADMIXTURE
- 2.10 GROUT AND READY-MIXED GROUT
 - 2.10.1 Admixtures for Grout
 - 2.10.2 Grout Barriers
- 2.11 ANCHORS, TIES, AND BAR POSITIONERS
 - 2.11.1 Wire Mesh Ties

- 2.11.2 Wall Ties
- 2.11.3 Omitted
- 2.11.4 Adjustable Anchors
- 2.11.5 Bar Positioners
- 2.12 JOINT REINFORCEMENT
- 2.13 REINFORCING STEEL BARS AND RODS
- 2.14 CONTROL JOINT KEYS
- 2.15 INSULATION
 - 2.15.1 Rigid Board-Type Insulation
 - 2.15.1.1 Insulation Thickness and Air Space
 - 2.15.1.2 Aged R-Value
 - 2.15.1.3 Recovered Material
 - 2.15.2 Insulation Adhesive
- 2.16 EXPANSION-JOINT MATERIALS
- 2.17 FLASHING
- 2.18 WEEP HOLE VENTILATORS

PART 3 EXECUTION

- 3.1 PREPARATION
 - 3.1.1 Hot Weather Installation
 - 3.1.2 Cold Weather Installation
 - 3.1.2.1 Protection
 - 3.1.2.2 Completed Masonry and Masonry Not Being Worked On
 - 3.1.3 Stains
 - 3.1.4 Loads
 - 3.1.5 Surfaces
- 3.2 LAYING MASONRY UNITS
 - 3.2.1 Forms and Shores
 - 3.2.2 Reinforced Concrete Masonry Units Walls
 - 3.2.3 Concrete Masonry Units
 - 3.2.4 Clay or Shale Brick Units
 - 3.2.4.1 Wetting of Units
 - 3.2.4.2 Solid Units
 - 3.2.4.3 Hollow Units
 - 3.2.4.4 Brick-Faced Walls
 - 3.2.4.5 Cavity Walls
 - 3.2.4.6 Omitted
 - 3.2.4.7 Omitted
 - 3.2.4.8 Brick Veneer
 - 3.2.5 Tolerances
 - 3.2.6 Cutting and Fitting
 - 3.2.7 Jointing
 - 3.2.7.1 Flush Joints
 - 3.2.7.2 Tooled Joints
 - 3.2.7.3 Door and Window Frame Joints
 - 3.2.8 Joint Widths
 - 3.2.8.1 Concrete Masonry Units
 - 3.2.8.2 Prefaced Concrete Masonry Units
 - 3.2.8.3 Brick
 - 3.2.9 Embedded Items
 - 3.2.10 Unfinished Work
 - 3.2.11 Masonry Wall Intersections
 - 3.2.12 Partitions
- 3.3 ANCHORED VENEER CONSTRUCTION
- 3.4 WEEP HOLES
- 3.5 OMITTED
- 3.6 MORTAR
- 3.7 REINFORCING STEEL

- 3.7.1 Positioning Bars
- 3.7.2 Splices
- 3.8 JOINT REINFORCEMENT INSTALLATION
- 3.9 PLACING GROUT
 - 3.9.1 Vertical Grout Barriers for Fully Grouted Walls
 - 3.9.2 Horizontal Grout Barriers
 - 3.9.3 Grout Holes and Cleanouts
 - 3.9.3.1 Grout Holes
 - 3.9.3.2 Cleanouts for Hollow Unit Masonry Construction
 - 3.9.3.3 Cleanouts for Solid Unit Masonry Construction
 - 3.9.4 Grouting Equipment
 - 3.9.4.1 Grout Pumps
 - 3.9.4.2 Vibrators
 - 3.9.5 Grout Placement
 - 3.9.5.1 Low-Lift Method
- 3.10 BOND BEAMS
- 3.11 CONTROL JOINTS
- 3.12 BRICK EXPANSION JOINTS AND CONCRETE MASONRY VENEER JOINTS
- 3.13 SHELF ANGLES
- 3.14 LINTELS
 - 3.14.1 Masonry Lintels
 - 3.14.2 Precast Concrete and Steel Lintels
- 3.15 SILLS
- 3.16 ANCHORAGE TO STRUCTURAL STEEL
 - 3.16.1 Omitted
 - 3.16.2 Anchorage to Structural Steel
- 3.17 OMITTED
- 3.18 INSULATION
- 3.19 OMITTED
- 3.20 POINTING AND CLEANING
 - 3.20.1 Concrete Masonry Unit Surfaces
 - 3.20.2 Clay or Shale Brick Surfaces
- 3.21 BEARING PLATES
- 3.22 PROTECTION
- 3.23 TEST REPORTS
 - 3.23.1 Field Testing of Mortar
 - 3.23.2 Field Testing of Grout
 - 3.23.3 Efflorescence Test

-- End of Section Table of Contents --

UFGS-04200 (August 2002)

MASONRY
08/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by basic designation only.

ACI INTERNATIONAL (ACI)

ACI 530.1	(1999) Specifications for Masonry Structures and Related Commentaries
ACI 318/318M	(2002) Building Code Requirements for Structural Concrete and Commentary
ACI SP-66	(1994) ACI Detailing Manual

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 82	(2001) Steel Wire, Plain, for Concrete Reinforcement
ASTM A 153/A 153M	(2001a) Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 615/A 615M	(2001b) Deformed and Plain Billet-Steel Bars for Concrete Reinforcement
ASTM A 616/A 616M	(1996a) Rail Steel Deformed and Plain Bars for Concrete Reinforcement
ASTM C 55	(2001a) Concrete Brick
ASTM C 62	(2001) Building Brick (Solid Masonry Units Made from Clay or Shale)
ASTM C 67	(2002) Sampling and Testing Brick and Structural Clay Tile
ASTM C 90	(2002) Loadbearing Concrete Masonry Units
ASTM C 91	(2001) Masonry Cement
ASTM C 94/C 94M	(2000e2) Ready-Mixed Concrete
ASTM C 129	(2001) Nonloadbearing Concrete Masonry Units
ASTM C 140	(2001ae1) Sampling and Testing Concrete Masonry Units and Related Units

ASTM C 144	(1999) Aggregate for Masonry Mortar
ASTM C 150	(2002) Portland Cement
ASTM C 207	(1991; R 1997) Hydrated Lime for Masonry Purposes
ASTM C 216	(2001a) Facing Brick (Solid Masonry Units Made from Clay or Shale)
ASTM C 270	(2001a) Mortar for Unit Masonry
ASTM C 476	(2001) Grout for Masonry
ASTM C 494/C 494M	(1999ae1) Chemical Admixtures for Concrete
ASTM C 578	(2001) Rigid, Cellular Polystyrene Thermal Insulation
ASTM C 641	(1998e1) Staining Materials in Lightweight Concrete Aggregates
ASTM C 652	(2001a) Hollow Brick (Hollow Masonry Units Made From Clay or Shale)
ASTM C 744	(1999) Prefaced Concrete and Calcium Silicate Masonry Units
ASTM C 780	(2000) Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry
ASTM C 1019	(2000b) Sampling and Testing Grout
ASTM C 1072	(2000a) Measurement of Masonry Flexural Bond Strength
ASTM C 1142	(1995; R 2001) Extended Life Mortar for Unit Masonry
ASTM C 1289	(2001) Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
ASTM D 2000	(2001) Rubber Products in Automotive Applications
ASTM D 2240	(2002) Rubber Property - Durometer Hardness
ASTM D 2287	(1996; R 2001) Nonrigid Vinyl Chloride Polymer and Copolymer Molding and Extrusion Compounds
ASTM E 119	(2000a) Fire Tests of Building Construction and Materials
ASTM E 447	(1997) Compressive Strength of Masonry Prisms
ASTM E 514	(1990; R 1996e1) Water Penetration and

Leakage Through Masonry

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Masonry Work

Drawings including plans, elevations, and details of wall reinforcement; details of reinforcing bars at corners and wall intersections; offsets; tops, bottoms, and ends of walls; control and expansion joints; lintels; and wall openings. Bar splice locations shall be shown. Bent bars shall be identified on a bending diagram and shall be referenced and located on the drawings. Wall dimensions, bar clearances, and wall openings greater than one masonry unit in area shall be shown. No approval will be given to the shop drawings until the Contractor certifies that all openings, including those for mechanical and electrical service, are shown. If, during construction, additional masonry openings are required, the approved shop drawings shall be resubmitted with the additional openings shown along with the proposed changes. Location of these additional openings shall be clearly highlighted. The minimum scale for wall elevations shall be 1/4 inch per foot. Reinforcement bending details shall conform to the requirements of ACI SP-66.

SD-03 Product Data

Clay or Shale Brick
Insulation

Manufacturer's descriptive data.

Cold Weather Installation

Cold weather construction procedures.

SD-04 Samples

Clay or Shale Brick

Color samples of three stretcher units and one unit for each type of special shape. Units shall show the full range of color and texture. Submit sample of colored mortar with applicable masonry unit.

Portable Panel

One panel of clay or shale brick, 2 by 2 feet, containing approximately 24 brick facings to establish range of color and

texture.

SD-06 Test Reports

Efflorescence Test
Field Testing of Mortar
Field Testing of Grout
Masonry Cement
Fire-rated CMU

Test reports from an approved independent laboratory. Test reports on a previously tested material shall be certified as the same as that proposed for use in this project.

SD-07 Certificates

Clay or Shale Brick
Concrete Masonry Units (CMU)
Control Joint Keys
Anchors, Ties, and Bar Positioners
Expansion-Joint Materials
Joint Reinforcement
Reinforcing Steel Bars and Rods
Masonry Cement
Mortar Coloring
Insulation
Precast Concrete Items
Admixtures for Masonry Mortar
Admixtures for Grout

Certificates of compliance stating that the materials meet the specified requirements.

Insulation

Certificate attesting that the polyurethane or polyisocyanurate insulation furnished for the project contains recovered material, and showing an estimated percent of such recovered material.

SD-08 Manufacturer's Instructions

Masonry Cement

When masonry cement is used, submit the manufacturer's printed instructions on proportions of water and aggregates and on mixing to obtain the type of mortar required.

1.3 SAMPLE MASONRY PANELS

After material samples are approved and prior to starting masonry work, a portable panel of clay or shale brick and sample masonry panels shall be constructed for each type and color of masonry required. At least 48 hours prior to constructing the sample panel or panels, the Contractor shall submit written notification to the Contracting Officer's Representative. Sample panels shall not be built in, or as part of the structure, but shall be located where directed.

1.3.1 Configuration

Panels shall be L-shaped or otherwise configured to represent all of the wall elements. Panels shall be of the size necessary to demonstrate the acceptable level of workmanship for each type of masonry represented on the project. The minimum size of a straight panel or a leg of an L-shaped panel shall be 8 feet long by 6 feet high.

1.3.2 Composition

Panels shall show full color range, texture, and bond pattern of the masonry work. The Contractor's method for mortar joint tooling; grouting of reinforced vertical cores, collar joints, bond beams, and lintels; positioning, securing, and lapping of reinforcing steel; positioning and lapping of joint reinforcement (including prefabricated corners); and cleaning of masonry work shall be demonstrated during the construction of the panels. Installation or application procedures for anchors, wall ties, CMU control joints, brick expansion joints, insulation, flashing, brick soldier, row lock courses and weep holes shall be shown in the sample panels. The panels shall contain a masonry bonded corner that includes a bond beam corner. Panels that represent reinforced masonry shall contain a 2 by 2 foot opening placed at least 2 feet above the panel base and 2 feet away from all free edges, corners, and control joints. Required reinforcing shall be provided around this opening as well as at wall corners and control joints.

1.3.3 Construction Method

Where anchored veneer walls are required, the Contractor shall demonstrate and receive approval for the method of construction; i.e., either bring up the two wythes together or separately, with the insulation and appropriate ties placed within the specified tolerances across the cavity. Temporary provisions shall be demonstrated to preclude mortar or grout droppings in the cavity and to provide a clear open air space of the dimensions shown on the drawings. Where masonry is to be grouted, the Contractor shall demonstrate and receive approval on the method that will be used to bring up the masonry wythes; support the reinforcing bars; and grout cells, bond beams, lintels, and collar joints using the requirements specified herein. If sealer is specified to be applied to the masonry units, sealer shall be applied to the sample panels. Panels shall be built on a properly designed concrete foundation.

1.3.4 Usage

The completed panels shall be used as the standard of workmanship for the type of masonry represented. Masonry work shall not commence until the sample panel for that type of masonry construction has been completed and approved. Panels shall be protected from the weather and construction operations until the masonry work has been completed and approved. After completion of the work, the sample panels, including all foundation concrete, shall become the property of the Contractor and shall be removed from the construction site.

1.4 DELIVERY, HANDLING, AND STORAGE

Materials shall be delivered, handled, stored, and protected to avoid chipping, breakage, and contact with soil or contaminating material.

1.4.1 Masonry Units

Concrete masonry units shall be covered or protected from inclement

weather. Store Type II, concrete masonry units at the site for a minimum of 28 days for air cured units, 10 days for atmospheric steam or water cured units, and 3 days for units cured with steam at a pressure of 120 to 150 psi and at a temperature of 350 to 365 degrees F for at least 5 hours. Protect moisture controlled units (Type I) from rain and ground water. Prefabricated lintels shall be marked on top sides to show either the lintel schedule number or the number and size of top and bottom bars.

1.4.2 Reinforcement, Anchors, and Ties

Steel reinforcing bars, coated anchors, ties, and joint reinforcement shall be stored above the ground. Steel reinforcing bars and uncoated ties shall be free of loose mill scale and rust.

1.4.3 Cementitious Materials, Sand and Aggregates

Cementitious and other packaged materials shall be delivered in unopened containers, plainly marked and labeled with manufacturers' names and brands. Cementitious material shall be stored in dry, weathertight enclosures or be completely covered. Cement shall be handled in a manner that will prevent the inclusion of foreign materials and damage by water or dampness. Sand and aggregates shall be stored in a manner to prevent contamination or segregation.

1.5 OMITTED

1.6 QUALITY ASSURANCE

1.6.1 Appearance

Bricks shall be manufactured at one time and from the same batch. Blend all brick to produce a uniform appearance when installed. An observable "banding" or "layering" of colors or textures caused by improperly mixed brick is unacceptable.

1.6.2 Testing

Masonry strength shall be determined in accordance with ACI 530.1; submit test reports on three prisms in accordance with ASTM E 447, Method B modified as specified in ACI 530.1. The cost of testing shall be paid by the Contractor.

1.6.3 Spare Vibrator

Maintain at least one spare vibrator on site at all times.

1.6.4 Bracing and Scaffolding

Provide bracing and scaffolding necessary for masonry work. Design bracing to resist wind pressure as required by local code.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS

The source of materials which will affect the appearance of the finished work shall not be changed after the work has started except with Contracting Officer's approval.

2.2 CLAY OR SHALE BRICK

Color range and texture of clay or shale brick shall be as indicated and shall conform to the approved sample. Brick shall conform to ASTM C 62; Grade SW shall be used for brick in contact with earth or grade and for all exterior work and for all nonvertical surfaces. Grade SW or MW shall be used in other brickwork. Average dimensions of brick shall be 3-5/8 inches thick, 2-1/4 inches high, and 8 inches long (standard) or 4 inches thick, 2-2/3 inches high, and 8 inches long (nominal), subject to the tolerances specified in ASTM C 62. Brick shall be tested for efflorescence. Clay or shale brick units shall be delivered factory-blended to provide a uniform appearance and color range in the completed wall.

2.2.1 Solid Clay or Shale Brick

Solid clay or shale brick shall conform to ASTM C 216, Type FBS. Brick size shall be modular and the nominal size of the brick used shall be 3-5/8 inches thick, 2-1/4 inches high, and 8 inches long (nominal) or 4 inches thick, 2-2/3 inches high and 8 inches long (nominal).

2.2.2 Hollow Clay or Shale Brick

Hollow clay or shale brick shall conform to ASTM C 652, Type HBS. Brick size shall be the same as solid clay or shale brick specified above. Where vertical reinforcement is shown in hollow brick, the minimum cell dimension shall be 2-1/2 inches and the units shall be designed to provide precise vertical alignment of the cells.

2.3 CONCRETE BRICK

Concrete brick shall conform to ASTM C 55, Type I, Grade N. Concrete brick may be used where necessary for filling out in concrete masonry unit construction.

2.4 CONCRETE MASONRY UNITS (CMU)

Units shall be of modular dimensions and air, water, or steam cured. ; exposed surfaces of units shall be smooth and of uniform texture.

- a. Hollow Load-Bearing Units: ASTM C 90, Type II, made with lightweight or medium weight or normal weight aggregate. Provide load-bearing units for exterior walls, foundation walls, load-bearing walls, and shear walls.
- b. Hollow Non-Load-Bearing Units: ASTM C 129, Type I or II, made with lightweight or medium weight or normal weight aggregate. Load-bearing units may be provided in lieu of non-load-bearing units.
- c. Solid Load-Bearing Units: ASTM C 90, Type I or II, lightweight or medium weight or normal weight units. Provide solid units as indicated.

2.4.1 Aggregates

Use recycled concrete aggregate to the greatest extent possible. Lightweight

aggregates and blends of lightweight and heavier aggregates in proportions used in producing the units, shall comply with the following requirements when tested for stain-producing iron compounds in accordance with ASTM C 641: by visual classification method, the iron stain deposited on the filter paper shall not exceed the "light stain" classification.

2.4.2 Kinds and Shapes

Units shall be modular in size and shall include closer, jamb, header, lintel, and bond beam units and special shapes and sizes to complete the work as indicated. In exposed interior masonry surfaces, units having a bullnose shall be used for vertical external corners except at door, window, and louver jambs. Radius of the bullnose shall be 1 inch. Units used in exposed masonry surfaces in any one building shall have a uniform fine to medium texture and a uniform color.

2.4.2.1 Omitted

2.4.2.2 Omitted

2.4.3 Fire-Rated CMU

Concrete masonry units used in fire-rated construction shown on the drawings shall be of minimum equivalent thickness for the fire rating indicated and the corresponding type of aggregates indicated in TABLE I. Units containing more than one of the aggregates listed in TABLE I will be rated on the aggregate requiring the greater minimum equivalent thickness to produce the required fire rating. Construction shall conform to ASTM E 119.

TABLE I

FIRE-RATED CONCRETE MASONRY UNITS

See note (a) below

Minimum equivalent thickness
inches for fire rating of:

Aggregate Type	2 hours
Pumice	3.0
Expanded slag	3.3
Expanded clay, shale, or slate	3.7
Limestone, scoria, cinders or unexpanded slag	4.0
Calcareous gravel	4.2
Siliceous gravel	4.5

(a) Minimum equivalent thickness shall equal net volume as determined in conformance with ASTM C 140 divided by the product of the actual length and height of the face shell of the unit in inches. Where walls are to receive plaster or be faced with brick, or

otherwise form an assembly; the thickness of plaster or brick or other material in the assembly will be included in determining the equivalent thickness.

2.5 PRECAST CONCRETE ITEMS

Lintels shall be factory-made units from a plant regularly engaged in producing precast concrete units. Trim and window sills are specified in Section 04435 ARCHITECTURAL CAST STONE. Unless otherwise indicated, concrete shall be 4,000 psi minimum conforming to Section 03300 CAST-IN-PLACE STRUCTURAL CONCRETE using 1/2 inch to No. 4 nominal-size coarse aggregate, and minimum reinforcement shall be the reinforcement required for handling of the units. Clearance of 3/4 inch shall be maintained between reinforcement and faces of units. Unless precast-concrete items have been subjected during manufacture to saturated-steam pressure of at least 120 psi for at least 5 hours, the items, after casting, shall be either damp-cured for 24 hours or steam-cured and shall then be aged under cover for 28 days or longer. Cast-concrete members weighing over 80 pounds shall have built-in loops of galvanized wire or other approved provisions for lifting and anchoring. Units shall have beds and joints at right angles to the face, with sharp true arises and shall be cast with drip grooves on the underside where units overhang walls. Exposed-to-view surfaces shall be free of surface voids, spalls, cracks, and chipped or broken edges. Precast units exposed-to-view shall be of uniform appearance and color. Unless otherwise specified, units shall have a smooth dense finish. Prior to use, each item shall be wetted and inspected for crazing. Items showing evidence of dusting, spalling, crazing, or having surfaces treated with a protective coating will be rejected.

2.5.1 Lintels

Precast lintels, unless otherwise shown, shall be of a thickness equal to the wall and reinforced with two No. 4 bars for the full length. Top of lintels shall be labeled "TOP" or otherwise identified and each lintel shall be clearly marked to show location in the structure. In reinforced masonry, lintels shall conform to ACI 318/318M for flexural and shear strength and shall have at least 8 inches bearing at each end. Concrete shall have a minimum 28 day compressive strength of 4000 psi using 1/2 inch to No. 4 nominal-size coarse aggregate. Reinforcement shall conform to ASTM A 615/A 615M Grade 60. Limit lintel deflection due to dead plus live load to L/600 or 0.3 inches. Provide top and bottom bars for lintels over 36 inches in length.

2.6 CAST STONE ITEMS

Cast stone items shall be as specified in Section 04435 ARCHITECTURAL CAST STONE.

2.7 OMITTED

2.8 MASONRY MORTAR

Type M mortar shall conform to ASTM C 270 and shall be used for foundation walls. Mortar Type S shall conform to the proportion specification of ASTM C 270 except Type S cement-lime mortar proportions shall be 1 part cement, 1/2 part lime and 4-1/2 parts aggregate; Type N cement-lime mortar proportions shall be 1 part cement, 1 part lime and 6 parts aggregate. Type N or S mortar shall be used for non-load-bearing, non-shear-wall interior masonry; and Type S for remaining masonry work; except where

higher compressive strength is indicated on structural drawings. When masonry cement ASTM C 91 is used the maximum air content shall be limited to 12 percent and performance equal to cement-lime mortar shall be verified. Verification of masonry cement performance shall be based on ASTM C 780 and ASTM C 1072. Pointing mortar in showers and kitchens shall contain ammonium stearate, or aluminum tri-stearate, or calcium stearate in an amount equal to 3 percent by weight of cement used. Cement shall have a low alkali content and be of one brand. Aggregates shall be from one source.

2.8.1 Admixtures for Masonry Mortar

In cold weather, a non-chloride based accelerating admixture may be used subject to approval. Accelerating admixture shall be non-corrosive, shall contain less than 0.2 percent chlorides, and shall conform to ASTM C 494/C 494M, Type C.

2.8.2 Colored Mortar

Mortar coloring shall be added to the mortar used for exposed masonry surfaces to produce a uniform color matching existing colored mortar. Quantity of pigment to cementitious content of the masonry cement shall not exceed 5 by weight; carbon black shall not exceed 1 percent by weight. Quantity of pigment to cementitious content of cement-lime mix shall not exceed 10 percent by weight, carbon black no more than 2 percent by weight. Mortar coloring shall be chemically inert, of finely ground limeproof pigment, and furnished in accurately pre-measured and packaged units that can be added to a measured amount of cement.

2.8.3 Hydrated Lime and Alternates

Hydrated lime shall conform to ASTM C 207, Type S. Lime alternates which have a current ICBO, ICBO Building Code, Evaluation Report number whose findings state it may be used as an alternate to lime for Type M, S, N, and O mortars will be deemed acceptable provided the user follows the manufacturer's proportions and mixing instructions as set forth in ICBO report.

2.8.4 Cement

Portland cement shall conform to ASTM C 150, Type I, II, or III, . Masonry cement shall conform to ASTM C 91, Type S. Containers shall bear complete instructions for proportioning and mixing to obtain the required types of mortar.

2.8.5 Pre-Mixed Mortar

Pre-mixed mortar shall conform to ASTM C 1142, Type RS.

2.8.6 Sand and Water

Sand shall conform to ASTM C 144. Water shall be clean, potable, and free from substances which could adversely affect the mortar.

2.9 WATER-REPELLANT ADMIXTURE

Polymeric type formulated to reduce porosity and water transmission. Construct panels of masonry units conforming to ASTM C 744 and mortar which contain the water-repellant admixture. When tested in accordance with ASTM

C 1072, such panels shall have flexural strength not less than that specified or indicated. When tested in accordance with ASTM E 514, panels shall exhibit no water visible on back of test panel and no leaks through the panel after 24 hours, and not more than 25 percent of wall area shall be damp after 72 hours.

2.10 GROUT AND READY-MIXED GROUT

Grout shall conform to ASTM C 476, fine or coarse as appropriate. Cement used in grout shall have a low alkali content. Grout slump shall be between 8 and 10 inches. Minimum grout strength shall be 2000 psi in 28 days, as tested by ASTM C 1019. Grout shall be used subject to the limitations of Table III. Proportions shall not be changed and materials with different physical or chemical characteristics shall not be used in grout for the work unless additional evidence is furnished that the grout meets the specified requirements. Ready-Mixed grout shall conform to ASTM C 94/C 94M.

2.10.1 Admixtures for Grout

In cold weather, a non-chloride based accelerating admixture may be used subject to approval; accelerating admixture shall be non-corrosive, shall contain less than 0.2 percent chlorides, and shall conform to ASTM C 494/C 494M, Type C. In general, air-entrainment, anti-freeze or chloride admixtures shall not be used except as approved by the Contracting Officer.

2.10.2 Grout Barriers

Grout barriers for vertical cores shall consist of fine mesh wire, fiberglass, or expanded metal.

2.11 ANCHORS, TIES, AND BAR POSITIONERS

Anchors and ties shall be fabricated without drips or crimps and shall be zinc-coated in accordance with ASTM A 153/A 153M, Class B-2. Steel wire used for anchors and ties shall be fabricated from steel wire conforming to ASTM A 82. Anchors and ties shall be sized to provide a minimum of 5/8 inch mortar cover from either face.

2.11.1 Wire Mesh Ties

Wire mesh for tying 4 inch thick concrete masonry unit partitions to other intersecting masonry partitions shall be 1/2 inch mesh of minimum 16 gauge steel wire. Minimum lengths shall be not less than 12 inches.

2.11.2 Wall Ties

Wall ties shall be rectangular-shaped or Z-shaped fabricated of 3/16 inch diameter zinc-coated steel wire. Rectangular wall ties shall be no less than 4 inches wide. Wall ties may also be of a continuous type conforming to paragraph JOINT REINFORCEMENT. Adjustable type wall ties, if approved for use, shall consist of two essentially U-shaped elements fabricated of 3/16 inch diameter zinc-coated steel wire. Adjustable ties shall be of the double pintle to eye type and shall allow a maximum of 1/2 inch eccentricity between each element of the tie. Play between pintle and eye opening shall be not more than 1/16 inch. The pintle and eye elements shall be formed so that both can be in the same plane.

2.11.3 Omitted

2.11.4 Adjustable Anchors

Adjustable anchors shall be 3/16 inch diameter steel wire, triangular-shaped. Anchors attached to steel shall be 5/16 inch diameter steel bars placed to provide 1/16 inch play between flexible anchors and structural steel members. Spacers shall be welded to rods and columns. Equivalent welded-on steel anchor rods or shapes standard with the flexible-anchor manufacturer may be furnished when approved. Welds shall be cleaned and given one coat of zinc-rich touch up paint.

2.11.5 Bar Positioners

Bar positioners, used to prevent displacement of reinforcing bars during the course of construction, shall be factory fabricated from 9 gauge steel wire or equivalent, and coated with a hot-dip galvanized finish. Not more than one wire shall cross the cell.

2.12 JOINT REINFORCEMENT

Joint reinforcement shall be factory fabricated from steel wire conforming to ASTM A 82, welded construction. Tack welding will not be acceptable in reinforcement used for wall ties. Wire shall have zinc coating conforming to ASTM A 153/A 153M, Class B-2. All wires shall be a minimum of 9 gauge. Reinforcement shall be ladder type design, having one longitudinal wire in the mortar bed of each face shell for hollow units and one wire for solid units. Joint reinforcement shall be placed a minimum of 5/8 inch cover from either face. The distance between crosswires shall not exceed 16 inches. Joint reinforcement for straight runs shall be furnished in flat sections not less than 10 feet long. Joint reinforcement shall be provided with factory formed corners and intersections. If approved for use, joint reinforcement may be furnished with adjustable wall tie features.

2.13 REINFORCING STEEL BARS AND RODS

Reinforcing steel bars and rods shall conform to ASTM A 615/A 615M, Grade 60 or ASTM A 616/A 616M.

2.14 CONTROL JOINT KEYS

Control joint keys shall be a factory fabricated solid section of natural or synthetic rubber (or combination thereof) conforming to ASTM D 2000 or polyvinyl chloride conforming to ASTM D 2287. The material shall be resistant to oils and solvents. The control joint key shall be provided with a solid shear section not less than 5/8 inch thick and 3/8 inch thick flanges, with a tolerance of plus or minus 1/16 inch. The control joint key shall fit neatly, but without forcing, in masonry unit jamb sash grooves. The control joint key shall be flexible at a temperature of minus 30 degrees F after five hours exposure, and shall have a durometer hardness of not less than 70 when tested in accordance with ASTM D 2240.

2.15 INSULATION

2.15.1 Rigid Board-Type Insulation

Rigid board-type insulation shall be extruded polystyrene, polyurethane, or polyisocyanurate. Polystyrene shall conform to ASTM C 578. Polyisocyanurate shall conform to ASTM C 1289, Type I, Class 1 or 2, faced with aluminum foil on both sides of the foam. The insulation shall be a

standard product and shall be marked with not less than the manufacturer's trademark or name, the specification number, the permeance and R-values.

2.15.1.1 Insulation Thickness and Air Space

The cavity space shall allow for a maximum insulation thickness of 2 inches, and a minimum air space of 3/4 inch.

2.15.1.2 Aged R-Value

The insulation shall provide a minimum aged R-value as indicated for the overall thickness. The aged R-value shall be determined at 75 degrees F in accordance with the appropriate referenced specification. The stated R-value of the insulation shall be certified by an independent testing laboratory or certified by an independent Registered Professional Engineer if tests are conducted in the manufacturer's laboratory.

2.15.1.3 Recovered Material

Contractor shall comply with EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS. The polyurethane or polyisocyanurate foam shall have a minimum material content of 20 percent by weight of the core material.

2.15.2 Insulation Adhesive

Insulation adhesive shall be specifically prepared to adhere the insulation to the masonry and, where applicable, to the thru-wall flashing. The adhesive shall not deleteriously affect the insulation, and shall have a record of satisfactory and proven performance for the conditions under which to be used.

2.16 EXPANSION-JOINT MATERIALS

Backer rod and sealant shall be adequate to accommodate joint compression equal to 50 percent of the width of the joint. The backer rod shall be compressible rod stock of polyethylene foam, polyurethane foam, butyl rubber foam, or other flexible, nonabsorptive material as recommended by the sealant manufacturer. Sealant shall conform to Section 07900A JOINT SEALING.

2.17 FLASHING

Flashing shall be as specified in Section 07600A SHEET METALWORK, GENERAL.

2.18 WEEP HOLE VENTILATORS

Weephole ventilators shall be prefabricated aluminum, plastic or wood blocking sized to form the proper size opening in head joints. Provide aluminum and plastic inserts with grill or screen-type openings designed to allow the passage of moisture from cavities and to prevent the entrance or insects. Ventilators shall be sized to match modular construction with a standard 3/8 inch mortar joint.

PART 3 EXECUTION

3.1 PREPARATION

Prior to start of work, masonry inspector shall verify the applicable

conditions as set forth in ACI 530.1, inspection. The Contracting Officer will serve as inspector or will select a masonry inspector.

3.1.1 Hot Weather Installation

The following precautions shall be taken if masonry is erected when the ambient air temperature is more than 99 degrees F in the shade and the relative humidity is less than 50 percent or the ambient air temperature exceeds 90 degrees F and the wind velocity is more than 8 mph. All masonry materials shall be shaded from direct sunlight; mortar beds shall be spread no more than 4 feet ahead of masonry; masonry units shall be set within one minute of spreading mortar; and after erection, masonry shall be protected from direct exposure to wind and sun for 48 hours.

3.1.2 Cold Weather Installation

Before erecting masonry when ambient temperature or mean daily air temperature falls below 40 degrees F or temperature of masonry units is below 40 degrees F, a written statement of proposed cold weather construction procedures shall be submitted for approval. The following precautions shall be taken during all cold weather erection.

3.1.2.1 Protection

Ice or snow formed on the masonry bed shall be thawed by the application of heat. Heat shall be applied carefully until the top surface of the masonry is dry to the touch. Sections of masonry deemed frozen and damaged shall be removed before continuing construction of those sections.

- a. Air Temperature 40 to 32 Degrees F. Sand or mixing water shall be heated to produce mortar temperatures between 40 and 120 degrees F.
- b. Air Temperature 32 to 25 Degrees F. Sand and mixing water shall be heated to produce mortar temperatures between 40 and 120 degrees F. Temperature of mortar on boards shall be maintained above freezing.
- c. Air Temperature 25 to 20 Degrees F. Sand and mixing water shall be heated to provide mortar temperatures between 40 and 120 degrees F. Temperature of mortar on boards shall be maintained above freezing. Sources of heat shall be used on both sides of walls under construction. Windbreaks shall be employed when wind is in excess of 15 mph.
- d. Air Temperature 20 Degrees F and below. Sand and mixing water shall be heated to provide mortar temperatures between 40 and 120 degrees F. Enclosure and auxiliary heat shall be provided to maintain air temperature above 32 degrees F. Temperature of units when laid shall not be less than 20 degrees F.

3.1.2.2 Completed Masonry and Masonry Not Being Worked On

- a. Mean daily air temperature 40 to 32 degrees F. Masonry shall be protected from rain or snow for 24 hours by covering with weather-resistive membrane.
- b. Mean daily air temperature 32 to 25 degrees F. Masonry shall be completely covered with weather-resistant membrane for 24 hours.

- c. Mean Daily Air Temperature 25 to 20 degrees F. Masonry shall be completely covered with insulating blankets or equally protected for 24 hours.
- d. Mean Daily Temperature 20 degrees F and Below. Masonry temperature shall be maintained above 32 degrees F for 24 hours by enclosure and supplementary heat, by electric heating blankets, infrared heat lamps, or other approved methods.

3.1.3 Stains

Protect exposed surfaces from mortar and other stains. When mortar joints are tooled, remove mortar from exposed surfaces with fiber brushes and wooden paddles. Protect base of walls from splash stains by covering adjacent ground with sand, sawdust, or polyethylene.

3.1.4 Loads

Do not apply uniform loads for at least 12 hours or concentrated loads for at least 72 hours after masonry is constructed. Provide temporary bracing as required.

3.1.5 Surfaces

Surfaces on which masonry is to be placed shall be cleaned of laitance, dust, dirt, oil, organic matter, or other foreign materials and shall be slightly roughened to provide a surface texture with a depth of at least 1/8 inch. Sandblasting shall be used, if necessary, to remove laitance from pores and to expose the aggregate.

3.2 LAYING MASONRY UNITS

Coordinate masonry work with the work of other trades to accommodate built-in items and to avoid cutting and patching. Masonry units shall be laid in the indicated bond pattern. Facing courses shall be level with back-up courses, unless the use of adjustable ties has been approved in which case the tolerances shall be plus or minus 1/2 inch. Each unit shall be adjusted to its final position while mortar is still soft and plastic. Units that have been disturbed after the mortar has stiffened shall be removed, cleaned, and relaid with fresh mortar. Air spaces, cavities, chases, expansion joints, and spaces to be grouted shall be kept free from mortar and other debris. Units used in exposed masonry surfaces shall be selected from those having the least amount of chipped edges or other imperfections detracting from the appearance of the finished work. Vertical joints shall be kept plumb. Units being laid and surfaces to receive units shall be free of water film and frost. Solid units shall be laid in a nonfurrowed full bed of mortar. Mortar for veneer wythes shall be beveled and sloped toward the center of the wythe from the cavity side. Units shall be shoved into place so that the vertical joints are tight. Vertical joints of brick and the vertical face shells of concrete masonry units, except where indicated at control, expansion, and isolation joints, shall be completely filled with mortar. Mortar will be permitted to protrude up to 1/2 inch into the space or cells to be grouted. Means shall be provided to prevent mortar from dropping into the space below. In double wythe construction, the inner wythe may be brought up not more than 16 inches ahead of the outer wythe. Collar joints shall be filled with mortar or grout during the laying of the facing wythe, and filling shall not lag the laying of the facing wythe by more than 8 inches.

3.2.1 Forms and Shores

Provide bracing and scaffolding as required. Design bracing to resist wind pressure as required by local codes. Forms and shores shall be sufficiently rigid to prevent deflections which may result in cracking or other damage to supported masonry and sufficiently tight to prevent leakage of mortar and grout. Supporting forms and shores shall not be removed in less than 10 days.

3.2.2 Reinforced Concrete Masonry Units Walls

Where vertical reinforcement occurs, fill cores solid with grout. Lay units in such a manner as to preserve the unobstructed vertical continuity of cores to be filled. Embed the adjacent webs in mortar to prevent leakage of grout. Remove mortar fins protruding from joints before placing grout. Minimum clear dimensions of vertical cores shall be 2 by 3 inches. Position reinforcing accurately as indicated before placing grout. As masonry work progresses, secure vertical reinforcing in place at vertical intervals not to exceed 160 bar diameters. Use puddling rod or vibrator to consolidate the grout. Minimum clear distance between masonry and vertical reinforcement shall be not less than 1/2 inch. Unless indicated or specified otherwise, form splices by lapping bars not less than 40 bar diameters and wire tying them together.

3.2.3 Concrete Masonry Units

Units in piers, pilasters, columns, starting courses on footings, solid foundation walls, lintels, and beams, and where cells are to be filled with grout shall be full bedded in mortar under both face shells and webs. Other units shall be full bedded under both face shells. Head joints shall be filled solidly with mortar for a distance in from the face of the unit not less than the thickness of the face shell. Foundation walls below grade shall be grouted solid. Jamb units shall be of the shapes and sizes to conform with wall units. Solid units may be incorporated in the masonry work where necessary to fill out at corners, gable slopes, and elsewhere as approved. Double walls shall be stiffened at wall-mounted plumbing fixtures by use of strap anchors, two above each fixture and two below each fixture, located to avoid pipe runs, and extending from center to center of the double wall. Walls and partitions shall be adequately reinforced for support of wall-hung plumbing fixtures when chair carriers are not specified.

3.2.4 Clay or Shale Brick Units

Brick facing shall be laid with the better face exposed. Brick shall be laid in running bond with each course bonded at corners, unless otherwise indicated. Molded brick shall be laid with the frog side down. Brick that is cored, recessed, or has other deformations may be used in sills, treads, soldier courses, except where deformations will be exposed to view.

3.2.4.1 Wetting of Units

Wetting of clay, shale brick, or hollow brick units having an initial rate of absorption of more than 1 gram per minute per square inch of bed surface shall be in conformance with ASTM C 67. The method of wetting shall ensure that each unit is nearly saturated but surface dry when laid. Test clay or shale brick daily on the job, prior to laying, as follows: Using a wax pencil, draw a circle the size of a quarter on five randomly selected bricks. Apply 20 drops of water with a medicine dropper to the surface

within the circle on each brick. If the average time that the water is completely absorbed in the five bricks is less than 1-1/2 minutes, wet bricks represented by the five bricks tested.

3.2.4.2 Solid Units

Bed, head, and collar joints shall be completely filled with mortar.

3.2.4.3 Hollow Units

Hollow units shall be laid as specified for concrete masonry units.

3.2.4.4 Brick-Faced Walls

For brick-faced walls bond the two wythes in every sixth brick course with continuous horizontal joint reinforcement. Provide additional bonding ties spaced not more than 3 feet apart around the perimeter of and within 12 inches of all openings.

3.2.4.5 Cavity Walls

Provide a continuous cavity as indicated. Securely tie the two wythes together with horizontal joint reinforcement. Bevel mortar beds away from cavity to prevent projection into cavity when bricks are shoved in place. Keep cavities clear and clean of mortar droppings. At the bottom of cavity walls, in the course immediately above the through-wall flashing, temporarily omit one brick every 4 feet. With a hose and clean water, wash all mortar droppings and debris out of the cavity through the temporary openings at least twice each day masonry is laid, and more often when required to keep the cavities clean. Fill in the openings with bricks and mortar after the wall is complete and the cavity has been inspected and found clean. Provide weep holes of open head joints spaced 24 inches o.c. wherever the cavity is interrupted.

3.2.4.6 Omitted

3.2.4.7 Omitted

3.2.4.8 Brick Veneer

Brick veneer walls with cold-formed steel framing backup are specified in Section 04810 NONBEARING MASONRY VENEER/STEEL STUD WALLS.

3.2.5 Tolerances

Masonry shall be laid plumb, true to line, with courses level. Bond pattern shall be kept plumb throughout. Corners shall be square unless noted otherwise. Except for walls constructed of prefaced concrete masonry units, masonry shall be laid within the following tolerances (plus or minus unless otherwise noted):

TABLE II

TOLERANCES

Variation from the plumb in the lines
and surfaces of columns, walls and arises

In adjacent masonry units

1/8 inch

TOLERANCES

In 10 feet	1/4 inch
In 20 feet	3/8 inch
In 40 feet or more	1/2 inch

Variations from the plumb for external corners, expansion joints, and other conspicuous lines

In 20 feet	1/4 inch
In 40 feet or more	1/2 inch

Variations from the level for exposed lintels, sills, parapets, horizontal grooves, and other conspicuous lines

In 20 feet	1/4 inch
In 40 feet or more	1/2 inch

Variation from level for bed joints and top surfaces of bearing walls

In 10 feet	1/4 inch
In 40 feet or more	1/2 inch

Variations from horizontal lines

In 10 feet	1/4 inch
In 20 feet	3/8 inch
In 40 feet or more	1/2 inch

Variations in cross sectional dimensions of columns and in thickness of walls

Minus	1/4 inch
Plus	1/2 inch

3.2.6 Cutting and Fitting

Full units of the proper size shall be used wherever possible, in lieu of cut units. Cutting and fitting, including that required to accommodate the work of others, shall be done by masonry mechanics using power masonry saws. Concrete masonry units may be wet or dry cut. Wet cut units, before being placed in the work, shall be dried to the same surface-dry appearance as uncut units being laid in the wall. Cut edges shall be clean, true and sharp. Openings in the masonry shall be made carefully so that wall plates, cover plates or escutcheons required by the installation will completely conceal the openings and will have bottoms parallel with the masonry bed joints. Reinforced masonry lintels shall be provided above openings over 12 inches wide for pipes, ducts, cable trays, and other wall penetrations, unless steel sleeves are used.

3.2.7 Jointing

Joints shall be tooled when the mortar is thumbprint hard. Horizontal joints shall be tooled last. Joints shall be brushed to remove all loose and excess mortar. Mortar joints shall be finished as follows:

3.2.7.1 Flush Joints

Joints in concealed masonry surfaces and joints at electrical outlet boxes in wet areas shall be flush cut. Flush cut joints shall be made by cutting off the mortar flush with the face of the wall. Joints in unparged masonry walls below grade shall be pointed tight. Flush joints for architectural units, such as fluted units, shall completely fill both the head and bed joints.

3.2.7.2 Tooled Joints

Joints in exposed exterior and interior masonry surfaces shall be tooled slightly concave. Joints shall be tooled with a jointer slightly larger than the joint width so that complete contact is made along the edges of the unit. Tooling shall be performed so that the mortar is compressed and the joint surface is sealed. Jointer of sufficient length shall be used to obtain a straight and true mortar joint.

3.2.7.3 Door and Window Frame Joints

On the exposed interior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 3/8 inch. On the exterior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 3/8 inch.

3.2.8 Joint Widths

Joint widths shall be as follows:

3.2.8.1 Concrete Masonry Units

Concrete masonry units shall have 3/8 inch joints, except for prefaced concrete masonry units.

3.2.8.2 Prefaced Concrete Masonry Units

Prefaced concrete masonry units shall have a joint width of 3/8 inch wide on unfaced side and not less than 3/16 inch nor more than 1/4 inch wide on prefaced side.

3.2.8.3 Brick

Brick joint widths shall be the difference between the actual and nominal dimensions of the brick in either height or length. Brick expansion joint widths shall be as shown.

3.2.9 Embedded Items

Spaces around built-in items shall be filled with mortar. Openings around flush-mount electrical outlet boxes in wet locations shall be pointed with mortar. Anchors, ties, wall plugs, accessories, flashing, pipe sleeves and other items required to be built-in shall be embedded as the masonry work progresses. Anchors, ties and joint reinforcement shall be fully embedded in the mortar. Cells receiving anchor bolts and cells of the first course below bearing plates shall be filled with grout.

3.2.10 Unfinished Work

Unfinished work shall be stepped back for joining with new work. Tothing may be resorted to only when specifically approved. Loose mortar shall be removed and the exposed joints shall be thoroughly cleaned before laying new work.

3.2.11 Masonry Wall Intersections

Each course shall be masonry bonded at corners and elsewhere as shown. Masonry walls shall be anchored or tied together at corners and intersections with bond beam reinforcement and prefabricated corner or tee pieces of joint reinforcement as shown.

3.2.12 Partitions

Partitions shall be continuous from floor to underside of roof deck where shown. Openings in firewalls around joists or other structural members shall be filled as indicated or approved. Where suspended ceilings on both sides of partitions are indicated, the partitions other than those shown to be continuous may be stopped approximately 4 inches above the ceiling level. An isolation joint shall be placed in the intersection between partitions and structural or exterior walls as shown. Interior partitions having 4 inch nominal thick units shall be tied to intersecting partitions of 4 inch units, 5 inches into partitions of 6 inch units, and 7 inches into partitions of 8 inch or thicker units. Cells within vertical plane of ties shall be filled solid with grout for full height of partition or solid masonry units may be used. Interior partitions having masonry walls over 4 inches thick shall be tied together with joint reinforcement. Partitions containing joint reinforcement shall be provided with prefabricated pieces at corners and intersections or partitions.

3.3 ANCHORED VENEER CONSTRUCTION

The inner and outer wythes shall be completely separated by a continuous airspace as shown on the drawings. Both the inner and the outer wythes shall be laid up together except when adjustable joint reinforcement assemblies are approved for use. When both wythes are not brought up together, through-wall flashings shall be protected from damage until they are fully enclosed in the wall. The airspace between the wythes shall be kept clear and free of mortar droppings by temporary wood strips laid on the wall ties and carefully lifted out before placing the next row of ties.

A coarse gravel or drainage material shall be placed behind the weep holes in the cavity to a minimum depth of 4 inches of coarse aggregate or 10 inches of drainage material to keep mortar droppings from plugging the weep holes.

3.4 WEEP HOLES

Wherever through-wall flashing occurs, provide weep holes to drain flashing to exterior. Weep holes shall be open head joints. at 24 inches o.c. Weep holes shall be provided not more than 24 inches on centers in mortar joints of the exterior wythe above wall flashing, over foundations, bond beams, and any other horizontal interruptions of the cavity. Weep holes shall be constructed using weep hole ventilators. Other approved methods may be used for providing weep holes. Weep holes shall be kept free of mortar and other obstructions.

3.5 OMITTED

3.6 MORTAR

Mortar shall be mixed in a mechanically operated mortar mixer for at least 3 minutes, but not more than 5 minutes. Measurement of ingredients for mortar shall be by volume. Ingredients not in containers, such as sand, shall be accurately measured by the use of measuring boxes. Water shall be mixed with the dry ingredients in sufficient amount to provide a workable mixture which will adhere to the vertical surfaces of masonry units. Mortar that has stiffened because of loss of water through evaporation shall be retempered by adding water to restore the proper consistency and workability. Mortar that has reached its initial set or that has not been used within 2-1/2 hours after mixing shall be discarded.

3.7 REINFORCING STEEL

Reinforcement shall be cleaned of loose, flaky rust, scale, grease, mortar, grout, or other coating which might destroy or reduce its bond prior to placing grout. Bars with kinks or bends not shown on the drawings shall not be used. Reinforcement shall be placed prior to grouting. Unless otherwise indicated, vertical wall reinforcement shall extend to within 2 inches of tops of walls.

3.7.1 Positioning Bars

Vertical bars shall be accurately placed within the cells at the positions indicated on the drawings. A minimum clearance of 1/2 inch shall be maintained between the bars and masonry units. Minimum clearance between parallel bars shall be one diameter of the reinforcement. Vertical reinforcing may be held in place using bar positioners located near the ends of each bar and at intermediate intervals of not more than 192 diameters of the reinforcement. Column and pilaster ties shall be wired in position around the vertical steel. Ties shall be in contact with the vertical reinforcement and shall not be placed in horizontal bed joints.

3.7.2 Splices

Bars shall be lapped a minimum of 48 diameters of the reinforcement. Welded or mechanical connections shall develop at least 125 percent of the specified yield strength of the reinforcement.

3.8 JOINT REINFORCEMENT INSTALLATION

Joint reinforcement shall be installed at 16 inches on center or as indicated. Reinforcement shall be lapped not less than 6 inches. Prefabricated sections shall be installed at corners and wall intersections. The longitudinal wires of joint reinforcement shall be placed to provide not less than 5/8 inch cover to either face of the unit.

3.9 PLACING GROUT

Cells containing reinforcing bars shall be filled with grout. Hollow masonry units in walls or partitions supporting plumbing, heating, or other mechanical fixtures, voids at door and window jambs, and other indicated spaces shall be filled solid with grout. Cells under lintel bearings on each side of openings shall be filled solid with grout for full height of openings. Walls below grade, lintels, and bond beams shall be filled solid with grout. Units other than open end units may require grouting each

course to preclude voids in the units. Grout not in place within 1-1/2 hours after water is first added to the batch shall be discarded. Sufficient time shall be allowed between grout lifts to preclude displacement or cracking of face shells of masonry units. If blowouts, flowouts, misalignment, or cracking of face shells should occur during construction, the wall shall be torn down and rebuilt.

3.9.1 Vertical Grout Barriers for Fully Grouted Walls

Grout barriers shall be provided not more than 30 feet apart, or as required, to limit the horizontal flow of grout for each pour.

3.9.2 Horizontal Grout Barriers

Grout barriers shall be embedded in mortar below cells of hollow units receiving grout.

3.9.3 Grout Holes and Cleanouts

3.9.3.1 Grout Holes

Grouting holes shall be provided in slabs, spandrel beams, and other in-place overhead construction. Holes shall be located over vertical reinforcing bars or as required to facilitate grout fill in bond beams. Additional openings spaced not more than 16 inches on centers shall be provided where grouting of all hollow unit masonry is indicated. Openings shall not be less than 4 inches in diameter or 3 by 4 inches in horizontal dimensions. Upon completion of grouting operations, grouting holes shall be plugged and finished to match surrounding surfaces.

3.9.3.2 Cleanouts for Hollow Unit Masonry Construction

Cleanout holes shall be provided at the bottom of every pour in cores containing vertical reinforcement when the height of the grout pour exceeds 5 feet. Where all cells are to be grouted, cleanout courses shall be constructed using bond beam units in an inverted position to permit cleaning of all cells. Cleanout holes shall be provided at a maximum spacing of 32 inches where all cells are to be filled with grout. A new series of cleanouts shall be established if grouting operations are stopped for more than 4 hours. Cleanouts shall not be less than 3 by 4 inch openings cut from one face shell. Manufacturer's standard cutout units may be used at the Contractor's option. Cleanout holes shall not be closed until masonry work, reinforcement, and final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, cleanout holes shall be closed in an approved manner to match surrounding masonry.

3.9.3.3 Cleanouts for Solid Unit Masonry Construction

Cleanouts for construction of walls consisting of a grout filled cavity between solid masonry wythes shall be provided at the bottom of every pour by omitting every other masonry unit from one wythe. A new series of cleanouts shall be established if grouting operations are stopped for more than 4 hours. Cleanout holes shall not be plugged until masonry work, reinforcement, and final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, cleanout holes shall be closed in an approved manner to match surrounding masonry.

3.9.4 Grouting Equipment

3.9.4.1 Grout Pumps

Pumping through aluminum tubes will not be permitted. Pumps shall be operated to produce a continuous stream of grout without air pockets, segregation, or contamination. Upon completion of each day's pumping, waste materials and debris shall be removed from the equipment, and disposed of outside the masonry.

3.9.4.2 Vibrators

Internal vibrators shall maintain a speed of not less than 5,000 impulses per minute when submerged in the grout. At least one spare vibrator shall be maintained at the site at all times. Vibrators shall be applied at uniformly spaced points not further apart than the visible effectiveness of the machine. Duration of vibration shall be limited to time necessary to produce satisfactory consolidation without causing segregation.

3.9.5 Grout Placement

Masonry shall be laid to the top of a pour before placing grout. Grout shall not be placed in two-wythe solid unit masonry cavity until mortar joints have set for at least 3 days during hot weather and 5 days during cold damp weather. Grout shall not be placed in hollow unit masonry until mortar joints have set for at least 24 hours. Grout shall be placed using a hand bucket, concrete hopper, or grout pump to completely fill the grout spaces without segregation of the aggregates. Vibrators shall not be inserted into lower pours that are in a semi-solidified state. The height of grout pours and type of grout used shall be limited by the dimensions of grout spaces as indicated in Table III. Low-lift grout methods may be used on pours up to and including 5 feet in height.

3.9.5.1 Low-Lift Method

Grout shall be placed at a rate that will not cause displacement of the masonry due to hydrostatic pressure of the grout. Mortar protruding more than 1/2 inch into the grout space shall be removed before beginning the grouting operation. Grout pours 12 inches or less in height shall be consolidated by mechanical vibration or by puddling. Grout pours over 12 inches in height shall be consolidated by mechanical vibration and reconsolidated by mechanical vibration after initial water loss and settlement has occurred. Vibrators shall not be inserted into lower pours that are in a semi-solidified state. Low-lift grout shall be used subject to the limitations of Table III.

TABLE III

POUR HEIGHT AND TYPE OF GROUT FOR VARIOUS GROUT SPACE DIMENSIONS

Maximum Grout Pour Height (feet) (4)	Grout Type	Grouting Procedure	Minimum Dimensions of the Total Clear Areas Within Grout Spaces and Cells (in.) (1,2)	
			Multiwythe Masonry (3)	Hollow-unit Masonry
1	Fine	Low Lift	3/4	1-1/2 x 2
5	Fine	Low Lift	2	2 x 3

TABLE III

POUR HEIGHT AND TYPE OF GROUT FOR VARIOUS GROUT SPACE DIMENSIONS

Maximum Grout Pour Height (feet) (4)	Grout Type	Grouting Procedure	Minimum Dimensions of the Total Clear Areas Within Grout Spaces and Cells (in.) (1,2)	
			Multiwythe Masonry (3)	Hollow-unit Masonry
1	Coarse	Low Lift	1-1/2	1-1/2 x 3
5	Coarse	Low Lift	2	2-1/2 x 3

Notes:

- (1) The actual grout space or cell dimension must be larger than the sum of the following items:
 - a) The required minimum dimensions of total clear areas given in the table above;
 - b) The width of any mortar projections within the space;
 - c) The horizontal projections of the diameters of the horizontal reinforcing bars within a cross section of the grout space or cell.
- (2) The minimum dimensions of the total clear areas shall be made up of one or more open areas, with at least one area being 3/4 inch or greater in width.
- (3) For grouting spaces between masonry wythes.
- (4) Where only cells of hollow masonry units containing reinforcement are grouted, the maximum height of the pour shall not exceed the distance between horizontal bond beams.

3.10 BOND BEAMS

Bond beams shall be filled with grout and reinforced as indicated on the drawings. Grout barriers shall be installed under bond beam units to retain the grout as required. Reinforcement shall be continuous, including around corners, except through control joints or expansion joints, unless otherwise indicated on the drawings. Where splices are required for continuity, reinforcement shall be lapped 48 bar diameters. A minimum clearance of 1/2 inch shall be maintained between reinforcement and interior faces of units.

3.11 CONTROL JOINTS

Control joints shall be provided as indicated and shall be constructed by using special control-joint units or sash jamb units with control joint key in accordance with the details shown on the drawings. Sash jamb units shall have a 3/4 by 3/4 inch groove near the center at end of each unit. The vertical mortar joint at control joint locations shall be continuous, including through all bond beams. This shall be accomplished by utilizing half blocks in alternating courses on each side of the joint. The control joint key shall be interrupted in courses containing continuous bond beam steel. In single wythe exterior masonry walls, the exterior control joints shall be raked to a depth of 3/4 inch; backer rod and sealant shall be installed in accordance with Section 07900A JOINT SEALING. Exposed interior control joints shall be raked to a depth of 1/4 inch. Concealed

control joints shall be flush cut.

3.12 BRICK EXPANSION JOINTS AND CONCRETE MASONRY VENEER JOINTS

Brick expansion joints and shall be provided and constructed as shown on the drawings. Joints shall be kept free of mortar and other debris.

3.13 SHELF ANGLES

Shelf angles shall be adjusted as required to keep the masonry level and at the proper elevation. Shelf angles shall be galvanized. Shelf angles shall be provided in sections not longer than 10 feet and installed with a 1/4 inch gap between sections. Shelf angles shall be mitered and welded at building corners with each angle not shorter than 4 feet, unless limited by wall configuration.

3.14 LINTELS

3.14.1 Masonry Lintels

Masonry lintels shall be constructed with lintel units filled solid with grout in all courses and reinforced with a minimum of two No. 4 bars in the bottom course unless otherwise indicated on the drawings. Lintel reinforcement shall extend beyond each side of masonry opening 40 bar diameters or 24 inches, whichever is greater. Reinforcing bars shall be supported in place prior to grouting and shall be located 1/2 inch above the bottom inside surface of the lintel unit.

3.14.2 Precast Concrete and Steel Lintels

Precast concrete and steel lintels shall be as shown on the drawings. Lintels shall be set in a full bed of mortar with faces plumb and true. Steel and precast lintels shall have a minimum bearing length of 8 inches unless otherwise indicated on the drawings.

3.15 SILLS

Sills shall be set in a full bed of mortar with faces plumb and true.

3.16 ANCHORAGE TO STRUCTURAL STEEL

3.16.1 Omitted

3.16.2 Anchorage to Structural Steel

Masonry shall be anchored to vertical structural steel framing with adjustable steel wire anchors spaced not over 16 inches on centers vertically, and if applicable, not over 24 inches on centers horizontally.

3.17 OMITTED

3.18 INSULATION

Anchored veneer walls shall be insulated, where shown, by installing board-type insulation on the cavity side of the inner wythe. Board type insulation shall be applied directly to the masonry or thru-wall flashing with adhesive. Insulation shall be neatly fitted between obstructions without impaling of insulation on ties or anchors. The insulation shall be applied in parallel courses with vertical joints breaking midway over

the course below and shall be applied in moderate contact with adjoining units without forcing, and shall be cut to fit neatly against adjoining surfaces.

3.19 OMITTED

3.20 POINTING AND CLEANING

After mortar joints have attained their initial set, but prior to hardening, mortar and grout daubs or splashings shall be completely removed from masonry-unit surfaces that will be exposed or painted. Before completion of the work, defects in joints of masonry to be exposed or painted shall be raked out as necessary, filled with mortar, and tooled to match existing joints. Immediately after grout work is completed, scum and stains which have percolated through the masonry work shall be removed using a high pressure stream of water and a stiff bristled brush. Masonry surfaces shall not be cleaned, other than removing excess surface mortar, until mortar in joints has hardened. Masonry surfaces shall be left clean, free of mortar daubs, dirt, stain, and discoloration, including scum from cleaning operations, and with tight mortar joints throughout. Metal tools and metal brushes shall not be used for cleaning.

3.20.1 Concrete Masonry Unit Surfaces

Exposed concrete masonry unit and concrete brick surfaces shall be dry-brushed at the end of each day's work and after any required pointing, using stiff-fiber bristled brushes.

3.20.2 Clay or Shale Brick Surfaces

Exposed clay or shale brick masonry surfaces shall be cleaned as necessary to obtain surfaces free of stain, dirt, mortar and grout daubs, efflorescence, and discoloration or scum from cleaning operations. After cleaning, the sample panel of similar material shall be examined for discoloration or stain as a result of cleaning. If the sample panel is discolored or stained, the method of cleaning shall be changed to assure that the masonry surfaces in the structure will not be adversely affected. The exposed masonry surfaces shall be water-soaked and then cleaned with a solution proportioned 1/2 cup trisodium phosphate and 1/2 cup laundry detergent to one gallon of water or cleaned with a proprietary masonry cleaning agent specifically recommended for the color and texture by the clay products manufacturer. The solution shall be applied with stiff fiber brushes, followed immediately by thorough rinsing with clean water. Proprietary cleaning agents shall be used in conformance with the cleaning product manufacturer's printed recommendations. Efflorescence shall be removed in conformance with the brick manufacturer's recommendations.

3.21 BEARING PLATES

Bearing plates for beams, joists, joist girders and similar structural members shall be set to the proper line and elevation with damp-pack bedding mortar, except where non-shrink grout is indicated. Bedding mortar and non-shrink grout shall be as specified in Section 03300 CAST-IN-PLACE STRUCTURAL CONCRETE.

3.22 PROTECTION

Facing materials shall be protected against staining. Top of walls shall be covered with nonstaining waterproof covering or membrane when work is

not in progress. Covering of the top of the unfinished walls shall continue until the wall is waterproofed with a complete roof or parapet system. Covering shall extend a minimum of 2 feet down on each side of the wall and shall be held securely in place. Before starting or resuming, top surface of masonry in place shall be cleaned of loose mortar and foreign material.

3.23 TEST REPORTS

3.23.1 Field Testing of Mortar

At least three specimens of mortar shall be taken each day. A layer of mortar 1/2 to 5/8 inch thick shall be spread on the masonry units and allowed to stand for one minute. The specimens shall then be prepared and tested for compressive strength in accordance with ASTM C 780.

3.23.2 Field Testing of Grout

Field sampling and testing of grout shall be in accordance with the applicable provisions of ASTM C 1019. A minimum of three specimens of grout per day shall be sampled and tested. Each specimen shall have a minimum ultimate compressive strength of 2000 psi at 28 days.

3.23.3 Efflorescence Test

Brick which will be exposed to weathering shall be tested for efflorescence. Tests shall be scheduled far enough in advance of starting masonry work to permit retesting if necessary. Sampling and testing shall conform to the applicable provisions of ASTM C 67. Units meeting the definition of "effloresced" will be subject to rejection.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 04 - MASONRY

SECTION 04435

ARCHITECTURAL CAST STONE

09/97

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL REQUIREMENTS
- 1.4 DESIGN
 - 1.4.1 Properties of Mix
 - 1.4.2 Tolerances
 - 1.4.3 Reinforcement
 - 1.4.4 Testing
 - 1.4.5 Standards and Loads
 - 1.4.6 Connections
 - 1.4.7 Calculations
- 1.5 STORAGE AND INSPECTION AT MANUFACTURER'S PLANT
- 1.6 HANDLING AND STORAGE

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Aggregates
 - 2.1.1.1 Fine Aggregate
 - 2.1.1.2 Coarse Aggregate
 - 2.1.2 Reinforcement
 - 2.1.3 Cement
 - 2.1.4 Color
 - 2.1.5 Inserts
 - 2.1.6 Plates, Angles, Anchors and Embedments
 - 2.1.7 Water
 - 2.1.8 Admixtures
 - 2.1.9 Pointing Mortar
 - 2.1.9.1 Nonstaining cement
 - 2.1.9.2 Hydrated Lime
 - 2.1.9.3 Sand
- 2.2 CAST STONE UNITS
 - 2.2.1 Reinforcement
 - 2.2.2 Embedded Accessories
 - 2.2.3 Identification
 - 2.2.4 Finish

PART 3 EXECUTION

- 3.1 SETTING
- 3.2 POINTING
- 3.3 JOINT SEALING
- 3.4 PATCHING AND CLEANING
- 3.5 PROTECTION OF WORK
- 3.6 DEFECTIVE WORK

-- End of Section Table of Contents --

SAVH-04435 (09/97)

SECTION 04435

ARCHITECTURAL CAST STONE
09/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 318 (1992) Building Code Requirements for Reinforced Concrete

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 82 (1990a) Steel Wire, Plain, for Concrete Reinforcement

ASTM A 185 1990a) Steel Welded Wire Fabric, Plain, for Concrete Reinforcement

ASTM A 497 (1990b) Steel Welded Wire Fabric, Deformed, for Concrete Reinforcement

ASTM A 615 (1990) Deformed and Plain Billet-Steel Bars for Concrete Reinforcement

ASTM C 31 (1985) Making and Curing Concrete Test Specimens in the Field

ASTM C 33 (1986) Concrete Aggregates

ASTM C 39 (1986) Compressive Strength of Cylindrical Concrete Specimens

ASTM C 91 (1991) Masonry Cement

ASTM C 97 (1990) Standard Test Methods for Absorption and Bulk Specific Gravity of Dimension Stone

ASTM C 144 (1991) Standard Specification for Aggregate or Masonry Mortar

ASTM C 150 (1989) Portland Cement

ASTM C 207 (1991; R 1992) Hydrated Lime for Masonry Purposes

ASTM C 494 (1986) Chemical Admixtures for Concrete

ASTM C 642	(1990) Standard Test Method for Specific Gravity, Absorption, and Voids in Hardened Concrete
ASTM C 979	(1982; R 1986) Pigments for Integrally Colored Concrete

CAST STONE INSTITUTE (CSI)

CSI 04435	(1990) Standard Specification for Cast Stone
-----------	--

PRECAST PRESTRESSED CONCRETE INSTITUTE (PCI)

PCI Mnl-117	(1977) Manual for Quality Control for Plants and Production of Architectural Precast Concrete Products
PCI Mnl-122	(1989) Architectural Precast Concrete

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Cast Stone

Cast stone manufacturer shall prepare and submit complete properly marked setting drawings, showing details and sizes of stones and reinforcing; arrangement of joints; bonding; inserts; joints; connections to adjoining walls or materials; reinforcing; and method of installation and anchoring. Unless otherwise specified, shop drawings shall provide for the following:

- a. Provide suitable wash on all exterior sills, copings, projecting courses and pieces with exposed top surfaces.
- b. Window sills shall have raised fillets at the back.
- c. All projecting pieces and soffit stones shall have drips under the outer edge.
- d. The shop drawings shall show the setting mark of each stone and its location on the structure. The stone when delivered shall bear the same corresponding setting mark on an unexposed surface.

SD-04 Samples

Cast Stone Units.

Two 12-inch by 12-inch by 2-inch samples of each type of cast stone unit finish required for the project. Samples shall show matrix color, surface color, surface texture, and panel back finish. A full-size mockup, maintained at the cast stone manufacturer's plant until approval by the

Contracting Officer for removal or incorporating in the project. The mockup shall be used to establish quality and acceptance of stone units to be used on the project, and shall consist of three or more units, showing the exterior finish (matrix color, surface color, surface texture), panel back finish, edge treatment, joint treatment, reinforcement, anchorage insert, lifting inserts, and other accessories. Mockup shall also include doors and windows and typical joints, including exterior corner joints and joints between units.

SD-05 Design Data

Calculations

Design calculations, prior to the manufacture of any cast stone units for the project.

Mix Design

A statement giving the maximum nominal fine or coarse aggregate size, the proportions of all ingredients and the type and amount of any admixtures that will be used in the manufacturing process, prior to commencing operations. The statement shall be accompanied by test results certifying that the proportions selected conform to the requirements of CSI 04435.

SD-06 Test Reports

Materials

Certified copies of test reports including all test data and all test results.

SD-07 Certificates

Manufacturer's Qualifications

A statement giving the qualifications of the cast stone manufacturer and of the installers, prior to commencing operations.

1.3 GENERAL REQUIREMENTS

Cast stone units shall be designed and fabricated by an experienced and acceptable cast stone manufacturer. The manufacturer shall have been regularly and continuously engaged in the manufacture of cast stone work similar to that indicated on the drawings for at least 5 years. Cast stone work shall be coordinated with the work of other trades.

1.4 DESIGN

1.4.1 Properties of Mix

Cast stone units shall have a 28-day compressive strength of 5,000 psi. The average water absorption of cast stone shall not exceed 6 percent by dry weight.

1.4.2 Tolerances

Cast stone dimensions shall be the numerically greater of plus or minus 1/8 inch or length/360. Setting tolerances shall be not greater than plus or minus 1/8 inch allowable out of plane from adjacent unit.

1.4.3 Reinforcement

Cast stone shall be reinforced with new billet steel reinforcing bars meeting ASTM A 615, grade 60, when necessary for safe handling, setting and structural stress, and the size of the reinforcing shall be specified. Reinforcement shall be galvanized or epoxy coated when covered with less than 2 inches of material for bars greater than 5/8 inch; 1-1/2 inches for bars 5/8 inch or smaller. The material covering in all cases shall be at least twice the diameter of the bars. Cast stone panels shall be reinforced as may be required for stripping, shipping and handling and to allow for temperature changes and structural stress. They shall be designed to carry the weight of materials above them. There shall be a minimum steel reinforcement equal to 1/4 percent of the sectional area of the panel. When panel is greater than 12 inches in any sectional dimension, the temperature steel shall be placed in both directions. Where applicable, cold-drawn steel wire reinforcement conforming to ASTM A 82, welded wire reinforcement conforming to ASTM A 185 or ASTM A 497, or steel bar or rod mat reinforcement conforming to ASTM A 184 may be used.

1.4.4 Testing

Testing shall be performed in accordance with ASTM C 31, ASTM C 39 and ASTM C 642 except that 2-inch cube specimens shall be used, oven dried in accordance with ASTM C 97. Test results shall be determined by the average of three specimens per test. The results of compression tests shall be divided by a factor of 0.8 when saw-cut or core-drilled specimens are used.

1.4.5 Standards and Loads

Cast stone unit design shall conform to ACI 318 and PCI Mnl-122. Design loads for precast concrete shall be as indicated on the drawings. A differential temperature of 60 degrees F, between interior and exterior faces of the units, shall be considered in the design. Stresses due to restrained volume change caused by shrinkage and temperature differential, handling, transportation and erection shall be accounted for in the design.

1.4.6 Connections

Connection of units to other members, or to other units shall be of the type and configuration indicated. The design and sizing of connections for all design loads shall be by the Contractor.

1.4.7 Calculations

Calculations for design of members and connections not shown shall be made by a currently registered professional engineer in the state of the project who is experienced in the design of precast architectural concrete. Calculation shall include the analysis of member for lifting stresses and the sizing of the lifting inserts.

1.5 STORAGE AND INSPECTION AT MANUFACTURER'S PLANT

Cast stone units temporarily stored at the manufacturer's plant shall be protected from damage in accordance with PCI Mnl-117. Immediately prior to

shipment to the job site, all cast stone units shall be inspected for quality to ensure all cast stone units conform to the requirements specified. Inspection for quality will include but not necessarily be limited to the following elements; color, texture, dimensional tolerances, chipping, cracking, and staining. All defective cast stone units shall be replaced or repaired as approved.

1.6 HANDLING AND STORAGE

Cast stone units shall be delivered to the site with delivery scheduled to avoid excessive build-up of units in storage at the site. Upon delivery to the job site all cast stone units shall be inspected for quality as specified in paragraph STORAGE AND INSPECTION AT MANUFACTURER'S PLANT. If the cast stone units cannot be unloaded and placed directly into the work, they shall be stored onsite, off the ground and protected from weather, marring, or overload. Cast stone units shall be handled in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Aggregates

2.1.1.1 Fine Aggregate

Fine aggregate shall be carefully graded and washed natural sands, or manufactured granite, quartz or limestone sands complying with ASTM C 33, except that gradation may vary to achieve desired finish and texture.

2.1.1.2 Coarse Aggregate

Coarse aggregate shall be carefully graded and washed natural gravels, or crushed, graded stone such as granite, quartz, limestone or other durable stone complying with ASTM C 33, except that gradation may vary to achieve desired finish and texture.

2.1.2 Reinforcement

Cast stone shall be reinforced with new billet steel reinforcing bars in accordance with ASTM A 615, grade 60, when necessary for safe handling, setting and structural stress. The size of the reinforcing shall be specified. If surfaces are to be exposed to the weather, reinforcement shall be galvanized or epoxy coated when covered with less than 2 inches of material for bars larger than 5/8 inch, and 1-1/2 inches for bars 5/8 inch or smaller. The material covering in all cases shall be at least twice the diameter of the bars. Cast stone panels shall be reinforced as may be required for handling, and to allow for temperature changes and structural stress. There shall be a minimum steel reinforcement amounting to 1/4 percent of the sectional area of the panel, and should the panel be greater than 12 inches in any sectional dimension, the temperature steel shall be placed in both directions. Where applicable, cold-drawn steel wire reinforcement in accordance with ASTM A 82, welded wire fabric reinforcement complying with ASTM A 185 or ASTM A 497, or steel bar or rod mat reinforcement meeting ASTM A 184 may be used.

2.1.3 Cement

Cement shall be portland Type I or Type III, white and/or gray conforming to ASTM C 150.

2.1.4 Color

All colors shall be inorganic (natural or synthetic) iron oxide pigments in accordance with ASTM C 979, excluding the use of a cement grade of carbon black pigment, and shall be guaranteed by the pigment manufacturer to be lime-proof. The amount of pigment shall not exceed 10 percent by weight of the cement used. Color shall be white or off-white matching existing cast stone items.

2.1.5 Inserts

Inserts shall be manufacturer's standard, suited for the application.

2.1.6 Plates, Angles, Anchors and Embedments

Steel items, other than stainless, shall be coated with a rust-inhibiting paint or shall be hot-dip galvanized. Steel items, including items embedded in cast stone, shall be either stainless steel or hot dip galvanized steel.

2.1.7 Water

Water shall be potable tap water free from impurities.

2.1.8 Admixtures

Admixtures shall conform to ASTM C 494.

2.1.9 Pointing Mortar

2.1.9.1 Nonstaining cement

ASTM C 91.

2.1.9.2 Hydrated Lime

ASTM C 207.

2.1.9.3 Sand

ASTM C 144.

2.2 CAST STONE UNITS

Cast stone units shall be manufactured and cured in accordance with the applicable provisions of PCI Mnl-117. Units shall be manufactured within the allowable tolerances given in CSI 04435 and PCI Mnl-117.

2.2.1 Reinforcement

Fabrication and placement of reinforcement shall conform to the details shown on the approved detail drawings and PCI Mnl-117.

2.2.2 Embedded Accessories

Anchors, inserts, lifting devices, dowels, and other accessories which are to be embedded in the cast stone units shall be furnished and installed in accordance with the approved detail drawings. Embedded items shall be accurately positioned in their designed location, and shall have sufficient anchorage and embedment to satisfy design requirements.

2.2.3 Identification

Each cast stone unit shall be marked to correspond to the identification marks for each different precast unit shown on the detail drawings.

2.2.4 Finish

Finish for cast stone shall be in accordance with the requirements of CSI 04435.

PART 3 EXECUTION

3.1 SETTING

All cast stone shall be set by experienced masons, accurately and in accordance with the shop and setting drawings. Unless otherwise noted, every stone shall be set in a full bed of mortar with all vertical joints flushed full. All anchors and dowels shall be firmly placed and all anchor holes and dowel holes and similar holes filled completely with mortar or nonshrink grout. All anchors, dowels, and other anchoring devices shall be furnished by the setting contractor as shown on approved shop drawings using, whenever possible, stainless steel-type 302 or 304 standard building stone anchors. When setting with mortar, all stones not thoroughly wet shall be drenched with clear water just prior to setting. After each stone has been set, all joints shall be raked to a depth of 3/4 inch from the face for pointing. The face of each stone shall then be sponged off to remove any splashed mortar or mortar smears. Only the ends of lugged sills and similar stones shall be embedded in mortar. The balance of joint to be left open until pointing of stone work. All cornices, copings, projecting belt courses, steps, platforms and in general, all stone areas either partially or totally horizontal, shall be set with unfilled vertical joints. After setting, insert properly sized back-up material or backer rod to proper depth, prime the ends of the stone, and gun in sealant. All stone shall be protected from splashing mortar or damage by other trades. Any foreign matter splashed on the stone should be removed immediately.

3.2 POINTING

When ready for pointing, the joints shall be dampened and carefully pointed to a slight concave unless otherwise specified. No pointing shall be done in freezing weather nor in locations exposed to hot sun, unless properly protected. Pointing mortar shall be composed of one part nonstaining cement (ASTM C 91), one part hydrate lime (ASTM C 207 - Type S) and four parts of clean, washed sand (ASTM C 144). Coloring pigments shall be added as required so that mortar is the same color as the stone. The Contracting Officer shall approve color of pointing mortar before proceeding with pointing.

3.3 JOINT SEALING

Head joints in copings and similar stones and joints as detailed shall be caulked with a joint sealant used in accordance with the manufacturer's instructions.

3.4 PATCHING AND CLEANING

The repair of chipped or damaged cast stone shall be done only by mechanics skilled in this class of work, with materials furnished by the manufacturer and according to his direction. Before pointing, the face of all cast stone shall be scrubbed with a fibre brush, using soap powder and water, and shall then be thoroughly rinsed with clean running water. Any mortar on the face of the cast stone shall be removed. No acids or prepared cleaners shall be used without the approval of the cast stone manufacturer.

3.5 PROTECTION OF WORK

Cast stone units shall be protected against damage from subsequent operations.

3.6 DEFECTIVE WORK

Cast stone units damaged during erection shall be repaired as soon after occurrence as possible or replaced, as directed, using approved procedures.

All repairs to cast stone units shall match the adjacent surfaces in color and texture and shall be as approved. Unless otherwise approved, repair procedures shall conform to PCI Mnl-117.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 04 - MASONRY

SECTION 04810

NONBEARING MASONRY VENEER/STEEL STUD WALLS

08/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 SAMPLE PANEL
- 1.4 DELIVERY, HANDLING AND STORAGE
- 1.5 EFFLORESCENCE TESTS

PART 2 PRODUCTS

- 2.1 VENEER WYTHE
 - 2.1.1 Clay or Shale Brick>
- 2.2 MORTAR
 - 2.2.1 Masonry Cement
 - 2.2.2 Admixtures
 - 2.2.3 Coloring
- 2.3 JOINT REINFORCEMENT
- 2.4 COLD-FORMED STEEL FRAMING
 - 2.4.1 Steel Studs
 - 2.4.2 Runners, Tracks, Bridging and Accessories
- 2.5 INSULATION
 - 2.5.1 Blanket Insulation
- 2.6 GYPSUM WALLBOARD
- 2.7 EXTERIOR SHEATHING
- 2.8 MOISTURE PROTECTION
 - 2.8.1 Moisture Barrier
 - 2.8.2 Omitted
 - 2.8.3 Staples
- 2.9 VENEER ANCHORS
- 2.10 CONNECTIONS
 - 2.10.1 Framing Screws, Bolts and Anchors
 - 2.10.2 Welding
 - 2.10.3 Veneer Anchor Screws
 - 2.10.4 Gypsum Sheathing Screws
- 2.11 SYNTHETIC RUBBER WASHERS
- 2.12 EXPANSION JOINT MATERIALS
- 2.13 FLASHING
- 2.14 STEEL LINTELS AND SHELF ANGLES
- 2.15 CAULKING AND SEALANTS
- 2.16 CAVITY DRAINAGE MATERIAL

PART 3 EXECUTION

- 3.1 GENERAL INSTALLATION REQUIREMENTS
- 3.2 STEEL STUD WALL FRAMING
- 3.3 STEEL SHELF ANGLES
- 3.4 OMITTED
- 3.5 GYPSUM WALLBOARD

- 3.6 EXTERIOR SHEATHING
- 3.7 MOISTURE PROTECTION
 - 3.7.1 Moisture Barrier
- 3.8 VENEER ANCHORS
- 3.9 FLASHING
- 3.10 MASONRY VENEER
 - 3.10.1 Surface Preparation
 - 3.10.2 Hot Weather Construction
 - 3.10.3 Cold Weather Construction
 - 3.10.4 Tolerances
 - 3.10.5 Mixing of Mortar
 - 3.10.6 Cutting and Fitting
 - 3.10.7 Masonry Units
 - 3.10.8 Mortar Joints
 - 3.10.9 Omitted
 - 3.10.10 Veneer Joints
 - 3.10.11 Weep Holes
 - 3.10.12 Head Joint Vents
 - 3.10.13 Discontinuous Work
 - 3.10.14 Cleaning
- 3.11 BUILDING EXPANSION JOINTS

-- End of Section Table of Contents --

UFGS-04810 (August 2002)

SECTION 04810

NONBEARING MASONRY VENEER/STEEL STUD WALLS

08/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC ASD Manual (1989) Manual of Steel Construction
Allowable Stress Design

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI Cold-Formed Spec (July 2002) Design of Cold-Formed Steel
Structural Members and Commentary

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 123/A 123M (2001a) Zinc (Hot-Dip Galvanized) Coatings
on Iron and Steel Products

ASTM A 153/A 153M (2001a) Zinc Coating (Hot-Dip) on Iron and
Steel Hardware

ASTM A 36/A 36M (2001) Carbon Structural Steel

ASTM A 653/A 653M (2001a) Steel Sheet, Zinc-Coated
(Galvanized) or Zinc-Iron Alloy-Coated
(Galvannealed) by the Hot-Dip Process

ASTM A 82 (2001) Steel Wire, Plain, for Concrete
Reinforcement

ASTM C 1002 (2001) Steel Self-Piercing Tapping Screws
for the Application of Gypsum Panel
Products or Metal Plaster Bases to Wood
Studs or Steel Studs

ASTM C 1072 (2000a) Measurement of Masonry Flexural
Bond Strength

ASTM C 1177/C 1177M (2001) Glass Mat Gypsum Substrate for Use
as Sheathing

ASTM C 216 (2001a) Facing Brick (Solid Masonry Units
Made from Clay or Shale)

ASTM C 270 (2001a) Mortar for Unit Masonry

ASTM C 494/C 494M	(1999ae1) Chemical Admixtures for Concrete
ASTM C 665	(2001e1) Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing
ASTM C 67	(2002) Sampling and Testing Brick and Structural Clay Tile
ASTM C 780	(2000) Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry
ASTM C 79/C 79M	(2001) Treated Core and Nontreated Core Gypsum Sheathing Board
ASTM C 91	(2001) Masonry Cement
ASTM C 955	(2001) Load-Bearing (Transverse and Axial) Steel Studs, Runners (Tracks), and Bracing or Bridging for Screw Application of Gypsum Panel Products and Metal Plaster Bases
ASTM D 1056	(2000) Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D 1330	(2000) Rubber Sheet Gaskets
ASTM D 1667	(1997) Flexible Cellular Materials - Vinyl Chloride Polymers and Copolymers (Closed-Cell Foam)
ASTM D 226	(1997a) Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)	
ASHRAE Hdbk-IP	(2001) Fundamentals Handbook, I-P Edition
AMERICAN WELDING SOCIETY (AWS)	
AWS D1.3	(1998) Structural Welding Code - Sheet Steel

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings

Details of cold-formed steel framing and support around openings, including framing connections, steel lintels, steel shelf angles, attachment to other building elements and bridging. Drawings shall indicate thickness, material, dimensions, protective coatings, and section properties of all steel lintels and shelf angles used in exterior wall framing. Drawings shall also indicate size and type of all fasteners including size and type of all welds.

SD-04 Samples

Expansion Joint Materials
Clay or Shale Brick
Sample Panel

A portable panel, approximately 2 by 2 feet, containing approximately 24 brick facings to establish the range of color and texture. One of each type of masonry veneer anchor used.

SD-06 Test Reports

Masonry Veneer/Steel Stud Wall System; G, RE

Calculations demonstrating the structural adequacy of steel lintels and shelf angles for the calculated gravity loads being supported; this analysis shall be in accordance with AISC ASD Manual. Test results demonstrating that the veneer anchors are structurally adequate to resist the specified loadings shall be submitted for approval. Calculations demonstrating the insulation shown on the drawings provides the specified U-value for heat transmission of the completed exterior wall construction; this analysis shall be in accordance with ASHRAE Hdbk-IP. Manufacturer's descriptive data and installation instructions for the insulation, the vapor barrier and the moisture barrier.

SD-07 Certificates

Clay or Shale Brick
Joint Reinforcement
Expansion Joint Materials
Insulation
Exterior Sheathing
Moisture Barrier
Vapor Retarder
Veneer Anchors
Welding

Certificates stating that the materials and welders meet the requirements specified. Each certificate shall be signed by an authorized certification official and shall include their organization and position and shall identify the products covered under their certifying signature.

1.3 SAMPLE PANEL

After the material samples are approved and prior to starting masonry work, a sample masonry panel shall be built on the project site where directed.

The sample panel shall be not less than 6 feet long by 4 feet high. The panel shall be of typical wall thickness for the construction represented. The panel shall show color range, texture, bond pattern, expansion joints, and cleaning of the masonry as required in the work. The panel shall also show cold-formed steel framing, insulation, gypsum wallboard, gypsum sheathing, moisture barrier, vapor barrier, veneer anchors, joint reinforcement, steel shelf angles, flashing and weep holes. The approved sample panel shall be used as a standard of workmanship required in the actual installation. The sample panel shall be protected from weather and construction operations and shall not be removed until the masonry veneer/steel stud wall work has been completed and accepted.

1.4 DELIVERY, HANDLING AND STORAGE

Materials shall be delivered and handled avoiding chipping, breakage, bending or other damage, and contact with soil or other contaminating materials. The masonry products shall be stored off the ground and protected from inclement weather. Cementitious materials shall be delivered in unopened containers plainly marked and labeled with manufacturer's names and brands. Cementitious materials shall be stored in dry, weather-tight enclosures or covers. Sand and other aggregates shall be stored preventing contamination or segregation and under a weather-tight covering permitting good air circulation. Finish of the framing members shall be maintained at all times, using an approved high zinc dust content galvanizing repair paint whenever necessary to prevent the formation of rust. Insulation, moisture barrier, and gypsum sheathing shall be stored in dry, well ventilated, weather-tight areas protected from sunlight and excessive heat. Air infiltration type vapor barrier shall be stored in accordance with the manufacturer's recommendations.

1.5 EFFLORESCENCE TESTS

Efflorescence tests shall be performed by an approved commercial testing laboratory. Sampling for the tests shall be the responsibility of the Contractor. Brick shall be sampled and tested for efflorescence in accordance with ASTM C 67 and the rating shall be: "not effloresced".

PART 2 PRODUCTS

2.1 VENEER WYTHE

The source of masonry materials which will affect the appearance of the finished work shall not be changed after the work has started except with the Contracting Officer's approval.

2.1.1 Clay or Shale Brick>

Clay or shale brick veneer shall be masonry units conforming to ASTM C 216, Type FBS. Color range and texture shall match existing as indicated and shall conform to the approved sample. Grade SW shall be used for all brickwork. Brick unit sizes shall be modulat and match existing as closely as possible.

2.2 MORTAR

Mortar shall conform to ASTM C 270, Type S. Mortar mix shall be based on proportion specifications. Laboratory testing of mortar shall be in accordance with the preconstruction evaluation of mortar section of ASTM C 780. Cement shall have a low alkali content and be of one brand.

Aggregates shall be from one source.

2.2.1 Masonry Cement

Masonry cement in conformance with ASTM C 91 may be used in the mortar. When using a masonry cement a comparative test shall be performed between a Portland cement-lime mortar and the masonry cement mortar proposed for the project to evaluate the ASTM C 1072 bond and the ASTM C 780 compressive strength of the two mixes. The test shall be conducted with the proposed masonry units for the project. The masonry cement mortar will be acceptable if the bond and compressive strength values are equal to or higher than the portland cement-lime mix. The air-content of the masonry cement shall be limited to 12 percent maximum.

2.2.2 Admixtures

In cold weather, a non-chloride based accelerating admixture may be used subject to approval. Accelerating admixtures shall be non-corrosive, contain less than 0.2 percent chlorides, and conform to ASTM C 494/C 494M, Type C.

2.2.3 Coloring

Mortar coloring shall be added to the mortar used for exposed masonry surfaces to produce a uniform color matching the color indicated on the drawings by reference to a manufacturer's standard color. Mortar coloring shall not exceed 3 percent of the weight of cement for carbon black and ten percent of the weight of cement for all other pigments. Mortar coloring shall be chemically inert, of finely ground limeproof pigment, and furnished in accurately pre-measured and packaged units that can be added to a measured amount of cement.

2.3 JOINT REINFORCEMENT

Joint reinforcement shall be of steel wire conforming to ASTM A 82. Fabrication shall be by welding. Tack welding will not be permitted. Reinforcement shall be zinc-coated after fabrication in accordance with ASTM A 153/A 153M, Class B-2. Joint reinforcement shall consist of at least 1 continuous longitudinal wire in the veneer wythe. Minimum wire cross section shall be 0.017 square inches.

2.4 COLD-FORMED STEEL FRAMING

Cold-formed framing shall consist of steel studs, top and bottom tracks, runners, horizontal bridging, and other cold-formed members and other accessories. All members and components made of sheet steel shall be hot-dip galvanized in accordance with ASTM A 653/A 653M with a minimum coating thickness of G 60. Framing covered herein shall be used only in framing the exterior masonry veneer steel stud wall system as indicated on the detail drawings. Metal framing for interior partitions are specified in Section 09250 GYPSUM BOARD. Metal framing for miscellaneous roof members is specified in Section 05400 COLD-FORMED STEEL FRAMING.

2.4.1 Steel Studs

Studs shall be furnished as shown in the contract drawings.

2.4.2 Runners, Tracks, Bridging and Accessories

Cold-formed steel sheet framing members, components, and accessories, other than the steel studs, shall conform to ASTM C 955 and be of steel conforming to ASTM A 653/A 653M, Grade 33, having a minimum yield strength of 33,000 psi.

2.5 INSULATION

The Contractor shall comply with EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS.

2.5.1 Blanket Insulation

Insulation placed between the steel studs shall be batt or blanket type mineral wool conforming to ASTM C 665, Type II.

2.6 GYPSUM WALLBOARD

Gypsum wallboard that is installed on the interior side of the cold-formed steel framing system shall be as specified in Section 09250 GYPSUM BOARD.

2.7 EXTERIOR SHEATHING

Glass mat gypsum sheathing shall conform to ASTM C 79/C 79M and ASTM C 1177/C 1177M. Glass mat gypsum sheathing shall have a water-resistant core with a water-resistant glass mat embedded onto core and shall have a zero flame, zero smoke developed, and shall have mold and mildew resistant surface.

2.8 MOISTURE PROTECTION

2.8.1 Moisture Barrier

The moisture barrier shall be 15-lb asphalt-saturated felt conforming to ASTM D 226 Type I (No. 15).

2.8.2 Omitted

2.8.3 Staples

Staples for attaching the moisture barrier to the exterior sheathing shall be the type and size best suited to provide a secure connection. Staples shall be made from either galvanized steel or stainless steel wire.

2.9 VENEER ANCHORS

Anchor assemblies for the attachment of the masonry veneer to the cold-formed steel framing, structural steel and/or concrete beam and column members, and concrete floor slabs shall be designed for the design loadings shown. Anchors shall transfer the design loadings from the masonry veneer to the cold-formed steel framing system or other support without exceeding the allowable stresses and deflections in the anchors. Length of anchor wires shall be such that the outermost wires lie between 1-1/4 inch from each face of the masonry veneer. Anchor wires shall not have drips. Wires for veneer anchors shall be rectangular or triangular hoops formed from 3/16 inch diameter steel wire conforming to ASTM A 82. Anchor assemblies including wires and anchor plates shall be hot-dip galvanized conforming to ASTM A 153/A 153M, Class B-2. The veneer anchor shall have a minimum capacity of 200 pounds. The load-displacement capacity of each veneer anchor, both in direct pull-out for tension and compression, shall

be not less than 2000 pounds per inch (or a deflection of 0.05 inches per 100 pounds of load in tension or compression). In the direction perpendicular to the masonry veneer, the anchor assembly shall have a maximum play of 1/16 inch.

2.10 CONNECTIONS

Screws, bolts and anchors shall be hot-dip galvanized in accordance with ASTM A 123/A 123M or ASTM A 153/A 153M as appropriate.

2.10.1 Framing Screws, Bolts and Anchors

Screws, bolts and anchors used in the assembly of the cold-formed steel framing system shall be as required by design of the framing system for the specified loading. Screw, bolt and anchor sizes shall be shown on the detail drawings.

2.10.2 Welding

Welded connections shall be designed and all welding shall be performed in accordance with AWS D1.3, as modified by AISI Cold-Formed Spec. Welders shall be qualified in accordance with AWS D1.3. All welds shall be cleaned and touched-up with zinc-rich paint.

2.10.3 Veneer Anchor Screws

Screws for attachment of the veneer anchors to the cold-formed steel framing members shall be as required by design to provide the needed pullout load capacity but not less than No. 12. Screws shall be shown on the detail drawings. The length of screws shall be such that the screws penetrate the holding member by not less than 5/8 inch.

2.10.4 Gypsum Sheathing Screws

Screws for attachment of gypsum sheathing to cold-formed steel framing shall conform to ASTM C 1002, Type S.

2.11 SYNTHETIC RUBBER WASHERS

Synthetic rubber washers for placement between veneer anchors and the moisture barrier on the outside face of the exterior sheathing shall conform to ASTM D 1330, Grade I.

2.12 EXPANSION JOINT MATERIALS

Expansion joint materials shall be bellows or U-shaped type conforming to Section 07600A SHEET METALWORK, GENERAL. Premolded type shall be closed-cell cellular rubber conforming to ASTM D 1056 or closed-cell vinyl or polyvinyl chloride conforming to ASTM D 1667.

2.13 FLASHING

Copper or stainless steel flashing shall conform to the requirements in Section 07600A SHEET METALWORK, GENERAL. Flashing shall be supplied in a continuous sheet extending from the exterior sheathing across the cavity and through the masonry veneer as shown.

2.14 STEEL LINTELS AND SHELF ANGLES

Steel shapes used for lintels and shelf angles shall conform to ASTM A 36/A 36M. Lintels and shelf angles shall be provided as shown. These steel members shall be hot-dip galvanized in accordance with ASTM A 123/A 123M.

2.15 CAULKING AND SEALANTS

Caulking and sealants shall be as specified in Section 07900A JOINT SEALING.

2.16 CAVITY DRAINAGE MATERIAL

Cavity drainage material (mortar guard) shall be 1-inch-thick, free-draining mesh; made from polyethylene strands and shaped to avoid being clogged by mortar droppings.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Wall sections, types of construction and dimensions shall be as shown. Metal door and window frames and other special framing shall be built and anchored into the wall system as indicated.

3.2 STEEL STUD WALL FRAMING

The top track of the stud wall system shall be slip jointed to accommodate vertical deflections of the supporting members as shown on the drawings. Top and bottom tracks shall be securely anchored to resist track rotation by alternating fastener locations to provide two rows, one row near each track flange as shown on the drawings. Both flanges of all steel studs shall be securely fastened with screws to the flanges of the top and bottom tracks as shown on the drawings. All details for affixing steel studs to runners and all other sheet steel framing members along with all details necessary for anchorage of the steel stud wall system to the building structural systems shall be as shown on the drawings. Horizontal bridging shall be provided as necessary. Studs shall be spaced as required to resist the specified design wind or seismic loadings, but not exceeding 24 inches on center. Coordinate stud spacing with sheathing and anchor requirements. At wall openings for doors, windows and other similar features, the framing system shall provide for the installation and anchorage of the required subframes or finish frames. Steel frames shall be securely attached through built-in anchors to the nearest stud on each side of the opening with self-drilling screws. Double studs shall be provided at both jambs of all door openings. Door frames and other built-in items shall be grouted solid.

3.3 STEEL SHELF ANGLES

Unless otherwise shown, steel shelf angles shall be provided in segments that do not exceed 10 feet in length. At building corners, shelf angle segments shall be mitered and securely attached together by welding with legs no less than 4 feet where possible. Shelf angle segments shall not be connected together but instead shall be installed with 1/4 inch wide gaps between the segments. Fabrication and erection tolerances shall be in accordance with the AISC Code of Standard Practice, as indicated in AISC ASD Manual.

3.4 OMITTED

3.5 GYPSUM WALLBOARD

Gypsum wallboard shall be installed on the interior face of the cold-formed steel framing system. Installation shall be as specified in Section 09250 GYPSUM BOARD except at vertical slip joints, the gypsum wallboard shall be connected to the vertical studs to prevent movement at the slip joint.

3.6 EXTERIOR SHEATHING

Sheathing shall be installed on the exterior face of the cold-formed steel framing system with self-drilling screws. Screws shall be located a minimum of 3/8 inch from the ends and edges of sheathing panels and shall be spaced not more than 8 inches on each supporting member except at vertical slip joints, the sheathing shall be connected to the vertical studs to prevent movement of the slip joint. Edges and ends of gypsum sheathing panels shall be butted snugly with vertical joints staggered to provide full and even support for the moisture barrier. Holes and gaps resulting from abandoned screw installations, from damage to panels, and from cutting and fitting of panels at junctures with doors, windows, foundation walls, floor slabs and other similar locations shall be filled with exterior rubber-base caulk.

3.7 MOISTURE PROTECTION

3.7.1 Moisture Barrier

The asphalt-saturated felt or other approved moisture barrier shall be installed on the outer face of the exterior sheathing. The moisture barrier shall be installed horizontally and shingled with each sheet lapped not less than 6 inches over the sheet below. Vertical end joints shall be lapped not less than 6 inches and shall be staggered. Attachment of the moisture barrier shall be with staples spaced not greater than 16 inches on center or as required by the manufacturer.

3.8 VENEER ANCHORS

Veneer anchors shall be attached with screws through the sheathing and rigid insulation to the steel studs or other support members at the locations shown. When rigid insulation is used, the method of connecting the veneer anchor through the insulation shall be approved by the Contracting Officer. Veneer anchors shall be installed with the outermost wires lying between 5/8 inch from each face of the masonry veneer. Synthetic rubber washers shall be used between the anchor connector plates and the moisture barrier. A clutch torque slip screw gun shall be used on screws attaching veneer anchors to cold-formed steel members. Veneer anchors with corrugated sheet metal or wire mesh members extending across the wall cavity shall not be used. There shall be one veneer anchor for each two square feet of wall and shall be attached to steel studs and other supports with a maximum spacing of 24 inches on center.

3.9 FLASHING

Continuous flashing shall be provided at the bottom of the wall cavity just above grade. Flashing shall also be provided above and below openings at lintels and sills, at shelf angles, and as indicated on the drawings. Flashing shall be as detailed and as specified in Section 07600A SHEET METALWORK, GENERAL. Flashing shall be lapped a minimum of 6 inches at joints and shall be sealed with a mastic as recommended by the flashing manufacturer. Ends over doors, windows and openings shall be turned up and secured. Flashing shall be lapped under the moisture barrier a minimum of

6 inches and securely attached to the gypsum sheathing. Flashing shall extend through the exterior face of the masonry veneer and shall be turned down to form a drip.

3.10 MASONRY VENEER

Exterior masonry wythes shall be constructed to the thickness indicated on the drawings. A cavity consisting of a 2 inch minimum width air space will be provided between the moisture barrier and the masonry veneer. Masonry veneer shall not be installed until the exterior sheathing, moisture barrier, veneer anchors and flashing have been installed on the cold-formed steel framing system. Extreme care shall be taken to avoid damage to the moisture barrier and flashing during construction of the masonry veneer. Any portion of the moisture barrier and flashing that is damaged shall be repaired or replaced prior to completion of the veneer. Masonry bond pattern shall be as indicated on the drawings. Vertical joints on alternating courses shall be aligned and kept vertically plumb. Solid masonry units shall be laid in a non-furrowed full bed of mortar, beveled and sloped toward the center of the wythe on which the mortar is placed. Units shall be shoved into place so that the vertical mortar joints are completely full and tight. Units that have been disturbed after the mortar has stiffened shall be removed, cleaned and relaid. Mortar which protrudes more than 1/2 inch into the cavity space shall be removed. Means shall be provided to ensure that the cavity space is kept clean of mortar droppings and other loose debris. Chases and raked-out joints shall be kept free from mortar and debris. Faces of units used in finished exposed areas shall be free from chipped edges, material texture or color defects or other imperfections distracting from the appearance of the finished work.

3.10.1 Surface Preparation

Surfaces on which masonry is to be laid shall be cleaned of laitance or other foreign material. No units having a film of water shall be laid.

3.10.2 Hot Weather Construction

Temperatures of masonry units and mortar shall not be greater than 120 degrees F when laid. Masonry erected when the ambient air temperature is more than 99 degrees F in the shade and when the relative humidity is less than 50 percent shall be given protection from the direct exposure to wind and sun for 48 hours after the installation.

3.10.3 Cold Weather Construction

Temperatures of masonry units and mortar shall not be less than 40 degrees F when laid. When the ambient air temperature is 32 degrees F or less, masonry veneer under construction shall be protected and maintained at a temperature greater than 32 degrees F for a period of 48 hours after installation. The proposed method of maintaining the temperature within the specified range shall be submitted for approval prior to implementation. No units shall be laid on a surface having a film of frost or water.

3.10.4 Tolerances

Masonry shall be laid plumb, level and true to line within the tolerances specified in TABLE 1. All masonry corners shall be square unless otherwise indicated on the drawings.

TABLE 1

Variation From Plumb

In adjacent units	1/8 inch
In 10 feet	1/4 inch
In 20 feet	3/8 inch
In 40 feet or more	1/2 inch

Variation From Level Or Grades

In 10 feet	1/8 inch
In 20 feet	1/4 inch
In 40 feet or more	1/2 inch

Variation From Linear Building Lines

In 20 feet	1/2 inch
In 40 feet or more	3/4 inch

Variation From Cross Sectional Dimensions Of Walls

Plus	1/2 inch
Minus	1/4 inch

3.10.5 Mixing of Mortar

Mortar shall be mixed in a mechanically operated mortar mixer for at least 3 minutes but not more than 5 minutes. Measurement of ingredients for mortar shall be by volume. Measurement of sand shall be accomplished by the use of a container of known capacity or shovel count based on a container of known capacity. Water shall be mixed with the dry ingredients in sufficient amount to provide a workable mixture which will adhere to the vertical surfaces of the masonry units. Mortar that has stiffened because of loss of water through evaporation shall be retempered by adding water to restore the proper consistency and workability. Mortar that has reached its initial set or that has not been used within 2-1/2 hours shall be discarded.

3.10.6 Cutting and Fitting

Wherever possible, full units shall be used in lieu of cut units. Where cut units are required to accommodate the design, cutting shall be done by masonry mechanics using power masonry saws. Wet-cut units shall be dried to the same surface-dry appearances of uncut units before being placed in the work. Cut edges shall be clean, true and sharp. Openings to accommodate pipes, conduits, and other accessories shall be neatly formed so that framing or escutcheons required will completely conceal the cut edges. Insofar as practicable, all cutting and fitting shall be accomplished while masonry work is being erected.

3.10.7 Masonry Units

When being laid, masonry units shall have suction sufficient to hold the

mortar and to absorb water from the mortar, but shall be damp enough to allow the mortar to remain in a plastic state to permit the unit to be leveled and plumbed immediately after being laid without destroying bond. Masonry units with frogging shall be laid with the frog side down and better or face side exposed to view. Masonry units that are cored, recessed or otherwise deformed may be used in sills or in other areas except where deformations will be exposed to view.

3.10.8 Mortar Joints

Mortar joint widths shall be uniform and such that the specified widths are maintained throughout. Joints shall be of thickness equal to the difference between the actual and nominal dimensions of the masonry units in either height or length but in no case shall the joints be less than 1/4 inch nor more than 1/2 inch wide. Joints shall be tooled slightly concave.

Tooling shall be accomplished when mortar is thumbprint hard and in a manner that will compress and seal the mortar joint and produce joints of straight and true lines free of tool marks.

3.10.9 Omitted

3.10.10 Veneer Joints

Brick expansion joints shall be provided at the locations shown on the drawings. Details of joints shall be as indicated on the drawings. Joints shall be clean and free of mortar and shall contain only backer rod and sealant, installed in accordance with Section 07900A JOINT SEALING. Horizontal reinforcement shall not extend through the joints.

3.10.11 Weep Holes

Weep holes shall be provided at all flashing locations at intervals of 24 inches. Weep holes shall be placed in head joints just above the flashing.

Weep holes shall be formed by leaving head joints open or head joint vents may be used. Weep holes shall be kept free of mortar and other obstructions.

3.10.12 Head Joint Vents

Head joint vents shall be provided near the top of the veneer wythe at the same spacing as the weep holes.

3.10.13 Discontinuous Work

When necessary to temporarily discontinue the work, masonry shall be stepped back for joining when work resumes. Tothing may be used only when specifically approved. Before resuming work, loose mortar shall be removed and the exposed joint shall be thoroughly cleaned. Top of walls subjected to rain or snow shall be covered with nonstaining waterproof covering or membrane when work is not in process. Covering shall extend a minimum of 2 feet down on each side of the wall and shall be held securely in place.

3.10.14 Cleaning

Mortar daubs or splashings shall be completely removed from finished exposed masonry surfaces before they harden or set up. Before completion of the work, defects in mortar joints shall be raked out as necessary, filled with mortar, and tooled to match the adjacent existing mortar in the joints. The proposed cleaning method shall be done on the sample wall

panel and the sample panel shall be examined for discoloration or stain. If the sample panel is discolored or stained, the method of cleaning shall be changed to ensure that the masonry surfaces in the structure will not be adversely affected. Masonry surfaces shall not be cleaned, other than removing excess surface mortar, until mortar in joints has hardened. Cleaning shall be accomplished with the use of stiff bristle fiber brushes, wooden paddles, wooden scrapers, or other suitable nonmetallic tools. The exposed brick surfaces shall be saturated with water and cleaned with a proprietary brick cleaning agent recommended by the clay products manufacturer. The cleaning agent shall not adversely affect the brick masonry surfaces. Proprietary cleaning agents shall be used in conformance with the cleaning product manufacturer's printed recommendations. Efflorescence or other stains shall be removed in conformance with the recommendations of the masonry unit manufacturer. After construction and cleaning, masonry surfaces shall be left clean, free of mortar daubs, stain, and discolorations, including scum from cleaning operations, and will have tight mortar joints throughout. Metallic tools and brushes shall not be used for cleaning.

3.11 BUILDING EXPANSION JOINTS

Expansion joints shall be located where indicated and shall be of the size and details shown.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 05 - METALS

SECTION 05120

STRUCTURAL STEEL

07/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SYSTEM DESCRIPTION
- 1.3 MODIFICATIONS TO REFERENCES
- 1.4 SUBMITTALS
- 1.5 AISC QUALITY CERTIFICATION
- 1.6 SEISMIC PROVISIONS
- 1.7 QUALITY ASSURANCE
 - 1.7.1 Drawing Requirements
 - 1.7.2 Certifications
 - 1.7.2.1 Overhead, Top Running Crane Rail Beam
 - 1.7.2.2 Erection Plan
 - 1.7.2.3 Welding Procedures and Qualifications

PART 2 PRODUCTS

- 2.1 STEEL
 - 2.1.1 Structural Steel
 - 2.1.2 Omitted
 - 2.1.3 Omitted
 - 2.1.4 Omitted
 - 2.1.5 Structural Shapes for Use in Building Framing
 - 2.1.6 Structural Steel Tubing
 - 2.1.7 Steel Pipe
- 2.2 BOLTS, NUTS, AND WASHERS
 - 2.2.1 Structural Steel, Steel Pipe
 - 2.2.1.1 Bolts
 - 2.2.1.2 Nuts
 - 2.2.1.3 Washers
 - 2.2.2 Omitted
 - 2.2.3 Omitted
 - 2.2.4 Foundation Anchorage
 - 2.2.4.1 Bolts
 - 2.2.4.2 Nuts
 - 2.2.4.3 Washers
 - 2.2.5 Load Indicator Washers
- 2.3 STRUCTURAL STEEL ACCESSORIES
 - 2.3.1 Welding Electrodes and Rods
 - 2.3.2 Nonshrink Grout
- 2.4 SHOP PRIMER
- 2.5 OMITTED
- 2.6 OMITTED
- 2.7 FABRICATION
 - 2.7.1 Markings
 - 2.7.2 Shop Primer
 - 2.7.2.1 Cleaning
 - 2.7.2.2 Primer

- 2.7.3 Epoxy Coated Surfaces
- 2.7.4 Surface Finishes

PART 3 EXECUTION

- 3.1 FABRICATION
- 3.2 INSTALLATION
 - 3.2.1 Overhead, Top Running Cranes
- 3.3 ERECTION
 - 3.3.1 STORAGE
- 3.4 CONNECTIONS
 - 3.4.1 Common Grade Bolts
 - 3.4.2 High-Strength Bolts
 - 3.4.2.1 Installation of Load Indicator Washers (LIW)
- 3.5 WELDING
 - 3.5.1 Removal of Temporary Welds, Run-Off Plates, and Backing Strips
- 3.6 SHOP PRIMER REPAIR
 - 3.6.1 Field Priming
- 3.7 OMITTED
- 3.8 FIELD QUALITY CONTROL
 - 3.8.1 Welds
 - 3.8.1.1 Visual Inspection
 - 3.8.1.2 Nondestructive Testing
 - 3.8.2 Load Indicator Washers
 - 3.8.2.1 Load Indicator Washer Compression
 - 3.8.3 Overhead, Top Running Crane Rails and Beams
 - 3.8.4 High-Strength Bolts
 - 3.8.4.1 Testing Bolt, Nut, and Washer Assemblies
 - 3.8.4.2 Inspection
 - 3.8.4.3 Testing
- 3.9 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

-- End of Section Table of Contents --

UFGS-05120 (July 2002)

SECTION 05120

STRUCTURAL STEEL

07/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC FCD	(1995a) Quality Certification Program Description
AISC 810	(1989) Erection Bracing of Low-Rise Structural Steel Frames
AISC 316	(1989) ASD Manual of Steel Construction
AISC 317	(1992; Errata 1994) Connections
AISC 325	LRFD Manual of Steel Construction
AISC 326	(1983) Detailing for Steel Construction
AISC 303	(2000) Steel Buildings and Bridges
AISC 348	(1985) Allowable Stress Design Specification for Structural Joints Using ASTM A325 or A490 Bolts
AISC 348	(1988) Load and Resistance Factor Design Specifications for Structural Joints Using ASTM A325 or A490 Bolts
AISC S340	(1992) Metric Properties of Structural Shapes with Dimensions According to ASTM A6M
AISC 341	(1992) Seismic Provisions for Structural Steel Buildings
AISC 350	(1993) Load and Resistance Factor Design Specification for Structural Steel Buildings

ASME INTERNATIONAL (ASME)

ASME B46.1	(1995) Surface Texture, (Surface Roughness, Waviness, and Lay)
------------	--

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 6/A 6M	(1998a) General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling
ASTM A 36/A 36M	(1997; Rev. A) Carbon Structural Steel
ASTM A 53	(1999; Rev. B) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless
ASTM A 307	(1997) Carbon Steel Bolts and Studs, 60,000 psi Tensile Strength
ASTM A 325M	(1997) High-Strength Bolts for Structural Steel Joints (Metric)
ASTM A 325	(1997) Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM A 490	(1997) Heat-Treated Steel Structural Bolts, 150 ksi Minimum Tensile Strength
ASTM A 500	(1999) Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A 501	(1999) Hot-Formed Welded and Seamless Carbon Steel Structural Tubing
ASTM A 514/A 514M	(1999) High-Yield-Strength, Quenched and Tempered Alloy Steel Plate, Suitable for Welding
ASTM A 563	(1997) Carbon and Alloy Steel Nuts
ASTM A 992/A 992M	(1998e1) Steel for Structural Shapes for Use in Building Framing
ASTM C 827	(1995; R 1997) Change in Height at Early Ages of Cylindrical Specimens from Cementitious Mixtures
ASTM C 1107	(1999) Packaged Dry, Hydraulic-Cement Grout (Nonsrink)
ASTM F 436	(1993) Hardened Steel Washers
ASTM F 844	(1998) Washers, Steel, Plain (Flat), Unhardened for General Use
ASTM F 959	(1999; Rev. A) Compressible-Washer-Type Direct Tension Indicators for Use with Structural Fasteners

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2000) Structural Welding Code - Steel
	CRANE MANUFACTURERS ASSOCIATION OF AMERICA (CMAA)
CMAA 70	(2000) Electric Overhead Traveling Cranes
	STEEL STRUCTURES PAINTING COUNCIL (SSPC)
SSPC SP 3	(1995) Power Tool Cleaning
SSPC SP 6	(1994) Commercial Blast Cleaning
SSPC Paint 25	(1991) Red Iron Oxide, Zinc Oxide, Raw Linseed Oil and Alkyd Primer (Without Lead and Chromate Pigments)
SSPC PA 1	(1991) Shop, Field, and Maintenance Painting
SSPC PS 13.01	(1991) Epoxy-Polyamide Painting System

1.2 SYSTEM DESCRIPTION

Provide the structural steel system, including shop primer, complete and ready for use. Structural steel systems including design, materials, installation, workmanship, fabrication, assembly, erection, inspection, quality control, and testing shall be provided in accordance with AISC 325 except as modified in this contract.

1.3 MODIFICATIONS TO REFERENCES

In AISC 325, AISC 350, AISC 303, AISC 348, and AISC S340, except as modified in this section, shall be considered a part of AISC M018L and AISC M019L and is referred to in this section as AISC 325.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Erection drawings, including description of temporary supports; G, AE

Fabrication drawings, including description of connections; G, AE

SD-03 Product Data

Shop primer

Load indicator washers

Include test report for Class B primer.

SD-06 Test Reports

Class B coating

Bolts, nuts, and washers

Supply the certified manufacturer's mill reports which clearly show the applicable ASTM mechanical and chemical requirements together with the actual test results for the supplied fasteners.

SD-07 Certificates

Steel

Bolts, nuts, and washers

Shop primer

Welding electrodes and rods

Nonshrink grout

AISC Quality Certification

Overhead, top running crane rail beam

Welding procedures and qualifications

1.5 AISC QUALITY CERTIFICATION

Work shall be fabricated in an AISC certified Category Sbd fabrication plant.

1.6 SEISMIC PROVISIONS

In addition to AISC 325, the structural steel system shall be provided in accordance with AISC 341.

1.7 QUALITY ASSURANCE

1.7.1 Drawing Requirements

Submit fabrication drawings for approval prior to fabrication. Prepare in accordance with AISC 326, AISC 316 and AISC 317. Drawings shall not be reproductions of contract drawings. Include complete information for the fabrication and erection of the structure's components, including the location, type, and size of bolts, welds, member sizes and lengths, connection details, blocks, copes, and cuts. Use AWS standard welding symbols. Shoring and temporary bracing shall be designed and sealed by a registered professional engineer and submitted for record purposes, with calculations, as part of the drawings.

1.7.2 Certifications

1.7.2.1 Overhead, Top Running Crane Rail Beam

Submit written field survey results for overhead, top running crane rail beam verifying tolerance requirements, area out of tolerance and proposed corrective measures.

1.7.2.2 Erection Plan

Submit for record purposes. Indicate the sequence of erection, temporary shoring and bracing, and a detailed sequence of welding, including each welding procedure required.

1.7.2.3 Welding Procedures and Qualifications

Prior to welding, submit certification for each welder stating the type of welding and positions qualified for, the code and procedure qualified under, date qualified, and the firm and individual certifying the qualification tests. If the qualification date of the welding operator is more than one-year old, the welding operator's qualification certificate shall be accompanied by a current certificate by the welder attesting to the fact that he has been engaged in welding since the date of certification, with no break in welding service greater than 6 months.

PART 2 PRODUCTS

2.1 STEEL

2.1.1 Structural Steel

ASTM A 36/A 36M.

2.1.2 Omitted

2.1.3 Omitted

2.1.4 Omitted

2.1.5 Structural Shapes for Use in Building Framing

Wide flange shapes, ASTM A 992/A 992M, 50 ksi grade.

2.1.6 Structural Steel Tubing

ASTM A 500, Grade B; ASTM A 501.

2.1.7 Steel Pipe

ASTM A 53, Type E or S, Grade B, weight class STD (Standard).

2.2 BOLTS, NUTS, AND WASHERS

Provide the following unless indicated otherwise.

2.2.1 Structural Steel, Steel Pipe

2.2.1.1 Bolts

ASTM A 307, Grade A; ASTM A 325, Type 1. The bolt heads and the nuts of the supplied fasteners must be marked with the manufacturer's identification mark, the strength grade and type specified by ASTM specifications.

2.2.1.2 Nuts

ASTM A 563, Grade and Style for applicable ASTM bolt standard recommended.

2.2.1.3 Washers

ASTM F 844 washers for ASTM A 307 bolts, and ASTM F 436 washers for ASTM A 325 bolts.

2.2.2 Omitted

2.2.3 Omitted

2.2.4 Foundation Anchorage

2.2.4.1 Bolts

ASTM A 307.

2.2.4.2 Nuts

ASTM A 563, Grade A, hex style.

2.2.4.3 Washers

ASTM F 844.

2.2.5 Load Indicator Washers

ASTM F 959.

2.3 STRUCTURAL STEEL ACCESSORIES

2.3.1 Welding Electrodes and Rods

AWS D1.1/D1.1M.

2.3.2 Nonshrink Grout

ASTM C 1107, with no ASTM C 827 shrinkage. Grout shall be nonmetallic.

2.4 SHOP PRIMER

SSPC Paint 25, (alkyd primer) or SSPC PS 13.01 epoxy-polyamide, green primer (Form 150) type 1, except provide a Class B coating in accordance with AISC 316 and AISC 317 for slip critical joints. Primer shall conform to Federal, State, and local VOC regulations. If flash rusting occurs, re-clean the surface prior to application of primer.

2.5 OMITTED

2.6 OMITTED

2.7 FABRICATION

2.7.1 Markings

Prior to erection, members shall be identified by a painted erection mark. Connecting parts assembled in the shop for reaming holes in field connections shall be match marked with scratch and notch marks. Do not locate erection markings on areas to be welded. Do not locate match markings in areas that will decrease member strength or cause stress

concentrations.

2.7.2 Shop Primer

Shop prime structural steel, except as modified herein, in accordance with SSPC PA 1. Do not prime steel surfaces embedded in concrete, galvanized surfaces, surfaces designed as part of a composite steel concrete section, or surfaces within 0.5 inch of the toe of the welds prior to welding (except surfaces on which metal decking is to be welded). Slip critical surfaces shall be primed with a Class B coating. Prior to assembly, prime surfaces which will be concealed or inaccessible after assembly. Do not apply primer in foggy or rainy weather; when the ambient temperature is below 45 degrees F or over 95 degrees F; or when the primer may be exposed to temperatures below 40 degrees F within 48 hours after application, unless approved otherwise by the Contracting Officer.

2.7.2.1 Cleaning

SSPC SP 6, except steel exposed in spaces above ceilings, attic spaces, furred spaces, and chases that will be hidden to view in finished construction may be cleaned to SSPC SP 3 when recommended by the shop primer manufacturer. Maintain steel surfaces free from rust, dirt, oil, grease, and other contaminants through final assembly.

2.7.2.2 Primer

Apply primer to a minimum dry film thickness of 2.0 mil except provide the Class B coating for slip critical joints in accordance with the coating manufacturer's recommendations. Repair damaged primed surfaces with an additional coat of primer.

2.7.3 Epoxy Coated Surfaces

Surfaces to receive coatings shall be cleaned and prepared in accordance with the manufacturer's recommendations, and as specified in Section 09900, "Paints and Coatings".

2.7.4 Surface Finishes

ASME B46.1 maximum surface roughness of 125 for pin, pinholes, and sliding bearings, unless indicated otherwise.

PART 3 EXECUTION

3.1 FABRICATION

Fabrication shall be in accordance with the applicable provisions of AISC 316. Fabrication and assembly shall be done in the shop to the greatest extent possible. The fabricating plant shall be certified under the AISC FCD for Category Sbd structural steelwork. Compression joints depending on contact bearing shall have a surface roughness not in excess of 500 micro inches as determined by ASME B46.1, and ends shall be square within the tolerances for milled ends specified in ASTM A 6/A 6M. Structural steelwork, except surfaces of steel to be encased in concrete, surfaces to be field welded, surfaces to be fireproofed, and contact surfaces of friction-type high-strength bolted connections shall be prepared for painting in accordance with endorsement "P" of AISC FCD and primed with the

specified paint.

3.2 INSTALLATION

3.2.1 Overhead, Top Running Cranes

Runway rails and beams shall be provided in accordance with AISC 325 and CMAA 70, except that in case of conflict, the requirements of CMAA 70 shall govern. In addition, provide a maximum vertical difference of 0.03 inch in the elevation between adjacent runway rail tops and adjacent runway beam tops at joints. Provide adjustable runway support connections to allow placement of the crane rails and beams to the tolerances specified. Stagger runway rail joints a minimum of one foot, except that the stagger shall not be the same as the crane wheel spacing.

3.3 ERECTION

- a: Erection of structural steel, except as indicated in item b. below, shall be in accordance with the applicable provisions of AISC 325 and endorsement F of AISC FCD. Erection plan shall be reviewed, stamped and sealed by a licensed structural engineer.
- b. For low-rise structural steel buildings (60 feet tall or less and a maximum of 2 stories), the erection plan shall conform to AISC 303 and the structure shall be erected in accordance with AISC 810.

Provide for drainage in structural steel. After final positioning of steel members, provide full bearing under base plates and bearing plates using nonshrink grout. Place nonshrink grout in accordance with the manufacturer's instructions.

3.3.1 STORAGE

Material shall be stored out of contact with the ground in such manner and location as will minimize deterioration.

3.4 CONNECTIONS

Except as modified in this section, connections not detailed shall be designed in accordance with AISC 350. Build connections into existing work. Do not tighten anchor bolts set in concrete with impact torque wrenches. Punch, subpunch and ream, or drill bolt and pin holes. Bolts, nuts, and washers shall be clean of dirt and rust, and lubricated immediately prior to installation.

3.4.1 Common Grade Bolts

ASTM A 307 bolts shall be tightened to a "snug tight" fit. "Snug tight" is the tightness that exists when plies in a joint are in firm contact. If firm contact of joint plies cannot be obtained with a few impacts of an impact wrench, or the full effort of a man using a spud wrench, contact the Contracting Officer for further instructions.

3.4.2 High-Strength Bolts

ASTM A 325 bolts shall be fully tensioned to 70 percent of their minimum tensile strength. Provide load indicator washers in all ASTM A 325M bolted connections, except provide only load indicator washers for slip critical connections. Direct tension indicator tightening, shall be the

only acceptable tightening methods. Use only direct tension indicator tightening for slip critical connections. Bolts shall be installed in connection holes and initially brought to a snug tight fit. After the initial tightening procedure, bolts shall then be fully tensioned, progressing from the most rigid part of a connection to the free edges.

3.4.2.1 Installation of Load Indicator Washers (LIW)

ASTM F 959. Where possible, the LIW shall be installed under the bolt head and the nut shall be tightened. If the LIW is installed adjacent to the turned element, provide a flat ASTM F 436 washer between the LIW and nut when the nut is turned for tightening, and between the LIW and bolt head when the bolt head is turned for tightening. In addition to the LIW, provide flat ASTM F 436 washers under both the bolt head and nut when ASTM A 490 bolts are used.

3.5 WELDING

AWS D1.1/D1.1M, except use only shielded metal arc welding and low hydrogen electrodes for ASTM A 514/A 514M steel. Do not stress relieve ASTM A 514/A 514M steel by heat treatment. Grind exposed welds smooth as indicated. Provide AWS D1.1/D1.1M qualified welders, welding operators, and tackers.

The contractor shall develop and submit the Welding Procedure Specifications (WPS) for all welding, including welding done using prequalified procedures. Prequalified procedures may be submitted for information only; however, procedures that are not prequalified shall be submitted for approval.

3.5.1 Removal of Temporary Welds, Run-Off Plates, and Backing Strips

Remove only from finished areas.

3.6 SHOP PRIMER REPAIR

Repair shop primer in accordance with the paint manufacturer's recommendation for surfaces damaged by handling, transporting, cutting, welding, or bolting.

3.6.1 Field Priming

Field priming of steel exposed to the weather, or located in building areas without HVAC for control of relative humidity. After erection, the field bolt heads and nuts, field welds, and any abrasions in the shop coat shall be cleaned and primed with paint of the same quality as that used for the shop coat.

3.7 OMITTED

3.8 FIELD QUALITY CONTROL

Perform field tests, and provide labor, equipment, and incidentals required for testing, except that electric power for field tests will be furnished as set forth in Division 1. The Contracting Officer shall be notified in writing of defective welds, bolts, nuts, and washers within 7 working days of the date of weld inspection.

3.8.1 Welds

3.8.1.1 Visual Inspection

AWS D1.1/D1.1M. Furnish the services of AWS-certified welding inspectors for fabrication and erection inspection and testing and verification inspections. Welding inspectors shall visually inspect and mark welds, including fillet weld end returns.

3.8.1.2 Nondestructive Testing

AWS D1.1/D1.1M. Test locations shall be selected by the Contracting Officer. If more than 20 percent of welds made by a welder contain defects identified by testing, then all welds made by that welder shall be tested by radiographic or ultrasonic testing, as approved by the Contracting Officer. When all welds made by an individual welder are required to be tested, magnetic particle testing shall be used only in areas inaccessible to either radiographic or ultrasonic testing. Retest defective areas after repair.

- a. Testing frequency: Provide the following types and number of tests:

<u>Test Type</u>	<u>Number of Tests</u>
Ultrasonic	25
Dye Penetrant	25

3.8.2 Load Indicator Washers

3.8.2.1 Load Indicator Washer Compression

Load indicator washers shall be tested in place to verify that they have been compressed sufficiently to provide the 0.015 inch gap when the load indicator washer is placed under the bolt head and the nut is tightened, and to provide the 0.005 inch gap when the load indicator washer is placed under the turned element, as required by ASTM F 959.

3.8.3 Overhead, Top Running Crane Rails and Beams

Runway rails and beams shall be surveyed (horizontally and vertically) after installation to verify compliance with the tolerance requirements of CMAA 70 and the additional tolerance requirements specified in this section. After each survey, submit a written report to the Contracting Officer with the following information: field survey results, tolerance requirements, areas out of tolerance, and proposed corrective measures. Proposed corrective measures shall be approved by the Contracting Officer. Following completion of corrective measures, areas that were previously out of tolerance shall be re-surveyed and another written report shall be furnished to the Contracting Officer. Field surveys shall be performed and sealed by a registered land surveyor.

3.8.4 High-Strength Bolts

3.8.4.1 Testing Bolt, Nut, and Washer Assemblies

Test a minimum of 3 bolt, nut, and washer assemblies from each mill certificate batch in a tension measuring device at the job site prior to the beginning of bolting start-up. Demonstrate that the bolts and nuts, when used together, can develop tension not less than the provisions specified in AISC 348, Table 4, depending on bolt size and grade. The bolt

tension shall be developed by tightening the nut. A representative of the manufacturer or supplier shall be present to ensure that the fasteners are properly used, and to demonstrate that the fastener assemblies supplied satisfy the specified requirements.

3.8.4.2 Inspection

Inspection procedures shall be in accordance with AISC 348, Section 9. Confirm and report to the Contracting Officer that the materials meet the project specification and that they are properly stored. Confirm that the faying surfaces have been properly prepared before the connections are assembled. Observe the specified job site testing and calibration, and confirm that the procedure to be used provides the required tension. Monitor the work to ensure the testing procedures are routinely followed on joints that are specified to be fully tensioned.

3.8.4.3 Testing

The Government has the option to perform nondestructive tests on 5 percent of the installed bolts to verify compliance with pre-load bolt tension requirements. The nondestructive testing will be done in-place using an ultrasonic measuring device or any other device capable of determining in-place pre-load bolt tension. The test locations shall be selected by the Contracting Officer. If more than 10 percent of the bolts tested contain defects identified by testing, then all bolts used from the batch from which the tested bolts were taken, shall be tested. Retest new bolts after installation.

3.9 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

Special inspections and testing for seismic-resisting systems and components shall be done in accordance with Section 01452A SPECIAL INSPECTION FOR SEISMIC-RESISTING SYSTEMS.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 05 - METALS

SECTION 05210A

STEEL JOISTS

01/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL REQUIREMENTS
- 1.4 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 OPEN WEB STEEL JOISTS
- 2.2 OMITTED
- 2.3 JOIST GIRDERS
- 2.4 ACCESSORIES AND FITTINGS
- 2.5 SHOP PAINTING

PART 3 EXECUTION

- 3.1 ERECTION
- 3.2 BEARING PLATES

-- End of Section Table of Contents --

UFGS-05210A (December 2002)

SECTION 05210A

STEEL JOISTS

01/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

STEEL JOIST INSTITUTE (SJI)

SJI Specs & Tables (August 2002) Standard Specifications and Load Tables for Steel Joists and Joist Girders

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Steel Joists; G, AE

Detail drawings shall include fabrication and erection details, specifications for shop painting, and identification markings of joists and joist girders.

SD-07 Certificates

Steel Joists

Certificates stating that the steel joists and joist girders have been designed and manufactured in accordance with SJI Specs & Tables. Complete engineering design computations may be submitted in lieu of the certification.

1.3 GENERAL REQUIREMENTS

Steel joists and joist girders are designated on the drawings in accordance with the standard designations of the Steel Joist Institute. Joists of other standard designations or joists with properties other than those shown may be substituted for the joists designated provided the structural properties are equal to or greater than those of the joists shown and provided all other specified requirements are met.

1.4 DELIVERY AND STORAGE

Materials shall be delivered to the site in undamaged condition and stored off the ground in a well drained location, protected from damage, and easily accessible for inspection and handling.

PART 2 PRODUCTS

2.1 OPEN WEB STEEL JOISTS

Open web steel joists shall conform to SJI Specs & Tables, K-Series. Joists shall be designed to support the loads given in the standard load tables of SJI Specs & Tables.

2.2 OMITTED

2.3 JOIST GIRDERS

Joist girders shall conform to SJI Specs & Tables.

2.4 ACCESSORIES AND FITTINGS

Accessories and fittings, including end supports, joist substitutes, and bridging, shall be in accordance with the standard specifications under which the members were designed.

2.5 SHOP PAINTING

Joists, joist girders and accessories shall be shop painted with a rust-inhibiting primer paint. For joists and joist girders which will be finish painted under Section 09900 PAINTING, GENERAL, the primer paint shall be limited to a primer which is compatible with the specified finish paint.

PART 3 EXECUTION

3.1 ERECTION

Installation of joists and joist girders shall be in accordance with the standard specification under which the member was produced. Joists and joist girders shall be handled in a manner to avoid damage. Damaged joists and joist girders shall be removed from the site, except when field repair is approved and such repairs are satisfactorily made in accordance with the manufacturer's recommendations. Joists and joist girders shall be accurately set, and end anchorage shall be in accordance with the standard specification under which the joists and joist girders were produced. For spans over 40 ft through 60 ft one row of bridging nearest midspan shall be bolted diagonal bridging; for spans over 60 ft bolted diagonal bridging shall be used instead of welded horizontal bridging. Joist bridging and anchoring shall be secured in place prior to the application of any construction loads. Any temporary loads shall be distributed so that the carrying capacity of any joist is not exceeded. Loads shall not be applied to bridging during construction or in the completed work. Abraded, corroded, and field welded areas shall be cleaned and touched up with the same type of paint used in the shop painting.

3.2 BEARING PLATES

Bearing plates shall be provided with full bearing after the supporting members have been plumbed and properly positioned, but prior to placing

superimposed loads. The area under the plate shall be damp-packed solidly with bedding mortar, except where nonshrink grout is indicated on the drawings. Bedding mortar and grout shall be as recommended by joist manufacturer.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 05 - METALS

SECTION 05300A

STEEL DECKING

01/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 DECK UNITS
 - 2.1.1 Roof Deck
- 2.2 TOUCH-UP PAINT
- 2.3 ADJUSTING PLATES
- 2.4 CLOSURE PLATES
 - 2.4.1 Closure Plates for Roof Deck
 - 2.4.2 Omitted
 - 2.4.2.1 Sheet Metal
- 2.5 ACCESSORIES

PART 3 EXECUTION

- 3.1 ERECTION
- 3.2 OMITTED
- 3.3 ATTACHMENTS
- 3.4 HOLES AND OPENINGS

-- End of Section Table of Contents --

UFGS-05300A (January 2002)

SECTION 05300A

STEEL DECKING

01/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI SG-973 (1996) Cold-Formed Steel Design Manual

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 611 (1997) Structural Steel (SS), Sheet, Carbon, Cold-Rolled

ASTM A 780 (2000) Repair of Damaged and Uncoated Areas of Hot-Dipped Galvanized Coatings

ASTM A 792/A 792M (1999) Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process

AMERICAN WELDING SOCIETY (AWS)

AWS D1.3 (1998) Structural Welding Code - Sheet Steel

STEEL DECK INSTITUTE (SDI)

SDI DDM01 (1991) Diaphragm Design Manual

SDI 30 (1995) Design Manual for Composite Decks, Form Decks, Roof Decks, and Cellular Metal Floor Deck with Electrical Distribution

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC Paint 20 (1991) Zinc-Rich Primers (Type I - "Inorganic" and Type II - "Organic")

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Deck Units
Accessories
Attachments
Holes and Openings

Drawings shall include type, configuration, structural properties, location, and necessary details of deck units, accessories, and supporting members; size and location of holes to be cut and reinforcement to be provided; location and sequence of welded or fastener connections; and the manufacturer's erection instructions.

SD-03 Product Data

Deck Units

Design computations for the structural properties of the deck units or SDI certification that the units are designed in accordance with SDI specifications.

Attachments

Prior to welding operations, copies of qualified procedures and lists of names and identification symbols of qualified welders and welding operators.

SD-07 Certificates

Deck Units
Attachments

Manufacturer's certificates attesting that the decking material meets the specified requirements. Manufacturer's certificate attesting that the operators are authorized to use the low-velocity piston tool.

1.3 DELIVERY, STORAGE, AND HANDLING

Deck units shall be delivered to the site in a dry and undamaged condition, stored off the ground with one end elevated, and stored under a weathertight covering permitting good air circulation. Finish of deck units shall be maintained at all times by using touch-up paint whenever necessary to prevent the formation of rust.

PART 2 PRODUCTS

2.1 DECK UNITS

Deck units shall conform to SDI 30. Panels of maximum possible lengths shall be used to minimize end laps. Deck units shall be fabricated in lengths to span 3 or more supports with flush, telescoped, or nested 2 inch laps at ends, and interlocking, or nested side laps, unless otherwise indicated. Deck with cross-sectional configuration differing from the units indicated may be used, provided that the properties of the proposed units, determined in accordance with AISI SG-973, are equal to or greater than the properties of the units indicated and that the material will fit the space provided without requiring revisions to adjacent materials or systems.

2.1.1 Roof Deck

Steel deck used in conjunction with insulation and metal roofing shall conform to ASTM A 792/A 792M, ASTM A 611 or ASTM A 792/A 792M. Roof deck units shall be fabricated of 16 gage design thickness or thicker steel and shall be galvanized.

2.2 TOUCH-UP PAINT

Touch-up paint for zinc-coated units shall be an approved galvanizing repair paint with a high-zinc dust content. Welds shall be touched-up with paint conforming to SSPC Paint 20 in accordance with ASTM A 780. Finish of deck units and accessories shall be maintained by using touch-up paint whenever necessary to prevent the formation of rust.

2.3 ADJUSTING PLATES

Adjusting plates or segments of deck units shall be provided in locations too narrow to accommodate full-size units. As far as practical, the plates shall be the same thickness and configuration as the deck units.

2.4 CLOSURE PLATES

2.4.1 Closure Plates for Roof Deck

Voids above interior walls shall be closed with sheet metal where shown. Open deck cells at parapets, end walls, eaves, and openings through roofs shall be closed with sheet metal. Sheet metal shall be same thickness as deck units.

2.4.2 Omitted

2.4.2.1 Sheet Metal

Where deck is cut for passage of pipes, ducts, columns, etc., and deck is to remain exposed, provide a neatly cut sheet metal collar to cover edges of deck. Do not cut deck until after installation of supplemental supports.

2.5 ACCESSORIES

The manufacturer's standard accessories shall be furnished as necessary to complete the deck installation. Metal accessories shall be of the same material as the deck and have minimum design thickness as follows: saddles, 0.0474 inch; welding washers, 0.0598 inch; cant strip, 0.0295 inch; other metal accessories, 0.0358 inch; unless otherwise indicated. Accessories shall include but not be limited to saddles, welding washers, cant strips, butt cover plates, underlapping sleeves, and ridge and valley plates.

PART 3 EXECUTION

3.1 ERECTION

Erection of deck and accessories shall be in accordance with SDI 30 and the approved detail drawings. Damaged deck and accessories including material which is permanently stained or contaminated, with burned holes or deformed shall not be installed. The deck units shall be placed on secure supports, properly adjusted, and aligned at right angles to supports before being permanently secured in place. The deck shall not be used for storage or as

a working platform until the units have been secured in position. Loads shall be distributed by appropriate means to prevent damage during construction and to the completed assembly. The maximum uniform distributed storage load shall not exceed the design live load. There shall be no loads suspended directly from the steel deck.

3.2 OMITTED

3.3 ATTACHMENTS

All fasteners shall be installed in accordance with the manufacturer's recommended procedure, except as otherwise specified. The deck units shall be welded with nominal 5/8 inch diameter puddle welds or fastened with screws, powder-actuated fasteners or pneumatically driven fasteners to supports as indicated on the design drawings and in accordance with requirements of SDI 30. All welding of steel deck shall be in accordance with AWS D1.3 using methods and electrodes as recommended by the manufacturer of the steel deck being used. Welds shall be made only by operators previously qualified by tests prescribed in AWS D1.3 to perform the type of work required. Welding washers shall be used at the connections of the deck to supports. Welding washers shall not be used at sidelaps. Holes and similar defects will not be acceptable. Deck ends shall be lapped 2 inches. All partial or segments of deck units shall be attached to structural supports in accordance with Section 2.5 of SDI DDM01.

Powder-actuated fasteners shall be driven with a low-velocity piston tool by an operator authorized by the manufacturer of the piston tool. Pneumatically driven fasteners shall be driven with a low-velocity fastening tool and shall comply with the manufacturer's recommendations.

3.4 HOLES AND OPENINGS

All holes and openings required shall be coordinated with the drawings, specifications, and other trades. Holes and openings shall be drilled or cut, reinforced and framed as indicated on the drawings or described in the specifications and as required for rigidity and load capacity. Holes and openings less than 6 inches across require no reinforcement. Holes and openings 6 to 12 inches across shall be reinforced by 0.0474 inch thick steel sheet at least 12 inches wider and longer than the opening and be fastened to the steel deck at each corner of the sheet and at a maximum of 6 inches on center. Holes and openings larger than 12 inches shall be reinforced by steel angles installed perpendicular to the steel joists and supported by the adjacent steel joists. Steel angles shall be installed perpendicular to the deck ribs and shall be fastened to the angles perpendicular to the steel joists. Openings must not interfere with seismic members such as chords and drag struts.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 05 - METALS

SECTION 05400A

COLD-FORMED STEEL FRAMING

01/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, HANDLING AND STORAGE

PART 2 PRODUCTS

- 2.1 STEEL STUDS, TRACKS, BRACING, BRIDGING, AND ACCESSORIES
- 2.2 MARKINGS
- 2.3 CONNECTIONS

PART 3 EXECUTION

- 3.1 Delivery, Handling and Storage
- 3.2 CONNECTIONS
 - 3.2.1 Welds
 - 3.2.2 Screws
 - 3.2.3 Anchors
- 3.3 INSTALLATION
 - 3.3.1 General Requirements
 - 3.3.2 Non-Load Bearing Walls (Curtain walls)
 - 3.3.3 Load Bearing Walls
 - 3.3.3.1 Axial Load
 - 3.3.3.2 Lateral Load (Shear Wall Panels)
 - 3.3.4 Omitted
 - 3.3.5 Trusses
- 3.4 TOLERANCES
- 3.5 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

-- End of Section Table of Contents --

UFGS-05400A (January 2002)

SECTION 05400A

COLD-FORMED STEEL FRAMING

01/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI SG-671 (1996) Specification & Commentary for the Design of Cold-Formed Steel Structural Members (Part V of the Cold-Formed Steel Design Manual)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 123/A 123M (2001) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A 153/A 153M (2001) Zinc Coating (Hot-Dip) on Iron and Steel Hardware

ASTM A 653/A 653M (2000) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM B 633 (1985; R 1998) Electrodeposited Coatings of Zinc on Iron and Steel

ASTM C 1007 (2000) Installation of Load Bearing (Transverse and Axial) Steel Studs and Related Accessories

ASTM C 955 (2000a) Load-Bearing (Transverse and Axial) Steel Studs, Runners (Tracks), and Bracing or Bridging for Screw Application of Gypsum Panel Products and Metal Plaster Bases

AMERICAN WELDING SOCIETY (AWS)

AWS D1.3 (1998) Structural Welding Code - Sheet Steel

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J78 (1998) Steel Self Drilling Tapping Screws

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Framing Components; G, AE

- a. Cross sections, plans, and/or elevations showing component types and locations for each framing application; including shop coatings and material thicknesses for each framing component.
- b. Connection details showing fastener type, quantity, location, and other information to assure proper installation.
- c. Drawings depicting panel configuration, dimensions, components, locations, and construction sequence if the Contractor elects to install prefabricated/prefinished frames.

1.3 DELIVERY, HANDLING AND STORAGE

Materials shall be delivered and handled preventing bending or other damage, and avoiding contact with soil or other contaminating materials. Finish of the framing members shall be maintained at all times, using an approved high zinc dust content, galvanizing repair paint whenever necessary to prevent the formation of rust.

PART 2 PRODUCTS

2.1 STEEL STUDS, TRACKS, BRACING, BRIDGING, AND ACCESSORIES

Framing components shall comply with ASTM C 955 and the following:

- a. Material shall be corrosion-resistant steel complying with ASTM A 653/A 653M, Grade 33 or higher, having a minimum yield of 33,000 psi and a G 60 minimum zinc coating.
- b. Minimum uncoated steel thickness (design thickness times 0.95):
 - (1). Studs and Tracks: 0.0329 inch.
 - (2). Bracing and bridging: Thickness as shown on the drawings.
 - (3). Accessories: Standard thickness as provided by the manufacturer.
- c. Stud and Track web depth: 6 inches except as indicated otherwise.
- d. Stud flange width: 1-3/8 inches.
- e. Stud effective section properties as shown on the drawings:

2.2 MARKINGS

Studs and track shall have product markings on the web of the section. The markings shall be repeated throughout the length of the member at a maximum

spacing of 4 feet on center and shall be legible and easily read. The product marking shall include the following:

- a. Manufacturer's identification.
- b. Minimum delivered uncoated steel thickness.
- c. Protective coating designator.
- d. Minimum yield strength.

2.3 CONNECTIONS

Screws for steel-to-steel connections shall be self-drilling tapping in compliance with SAE J78 of the type, size, and location as shown on the drawings. Electroplated screws shall have a Type II coating in accordance with ASTM B 633. Screws, bolts, and anchors shall be hot-dipped galvanized in accordance with ASTM A 123/A 123M or ASTM A 153/A 153M as appropriate. Screws bolts, and anchors shall be hot dipped galvanized in accordance with ASTM A 123/A 123Mor ASTM A 153/A 153M as appropriate.

PART 3 EXECUTION

3.1 Delivery, Handling and Storage

a. Materials shall be delivered and handled in a manner to avoid bending or other damage and to avoid contact with the soil or other contaminating materials.

b. Finish of the framing members shall be maintained at all times, using an approved high zinc dust content galvanizing repair paint whenever necessary to prevent the formation of rust.

3.2 CONNECTIONS

3.2.1 Welds

All welding shall be performed in accordance with AWS D1.3, as modified by AISI SG-671. All welders, welding operations, and welding procedures shall be qualified according to AWS D1.3. All welds shall be cleaned and coated with rust inhibitive galvanizing paint.

3.2.2 Screws

Screws shall be of the self-drilling self-tappingtype, size, and location shown on the drawings. Screw penetration through joined materials shall not be less than three exposed threads. Minimum spacings and edge distances for screws shall be as specified in AISI SG-671. Screws covered by sheathing materials shall have low profile heads.

3.2.3 Anchors

Anchors shall be of the type, size, and location shown on the drawings.

3.3 INSTALLATION

3.3.1 General Requirements

- a. Prefabricated frames shall be square, with components attached to

prevent racking during fabrication, transportation, and lifting. Design and construction of frames shall include provisions for lifting.

- b. Cutting of steel framing shall be by saw, shear, or plasma cutting equipment. Oxyacetylene torch cutting is not permitted.
- c. Temporary bracing shall be provided and remain in place until work is permanently stabilized.
- d. Abutting lengths of track shall be butt-welded, spliced, or each length securely anchored to a common structural element. Track shall be securely anchored to the supporting structure as shown on the drawings.
- e. Splicing of framing components, other than track and tension members, is not permitted.
- f. Wire tying of framing members is not permitted.

3.3.2 Non-Load Bearing Walls (Curtain walls)

- a. Studs shall be spaced as shown on the drawings.
- b. Studs shall be plumbed, aligned, and secured to the continuous runner tracks at each end, unless the stud end terminates at a deflection track.
- c. Tracks shall be securely anchored to the supporting structure as shown on the drawings.
- d. Bridging spaced as shown on the drawings shall be installed prior to the installation of facing materials.
- e. Framed wall openings shall include headers and supporting components as shown on the drawings. Headers shall be installed in all openings that are larger than the stud spacing in a wall.
- f. At wall openings for doors, windows and other similar features, the framing system shall provide for the installation and anchorage of the required subframes or finish frames. Steel frames shall be securely attached through built-in anchors to the nearest stud on each side of the opening with self-drilling screws. Double studs shall be provided at both jambs of all door openings.
- g. Installation of sheathing, wallboards, or any other collateral material shall be performed in accordance with the product manufacturer's specifications.
- h. Components (Deflection Track and/or Slide Clips) shall be provided at locations shown on the drawings to accommodate potential movements of Primary Frames.

3.3.3 Load Bearing Walls

3.3.3.1 Axial Load

Installation shall comply with ASTM C 1007 and the following:

- a. Studs shall be spaced at 16 inches on center or as shown on the drawings.
- b. Studs shall be installed seated squarely against the web of the top and bottom track to assure transfer of axial load. Studs shall be plumbed, aligned, and secured to the continuous runner tracks at each end before the installation of components which induce axial load.
- c. Studs, other than at framed openings, shall align vertically to allow for full transfer of the loads to the foundation. Vertical alignment shall be maintained at floor/wall intersections. Where vertical alignment is not possible, a continuous load distribution member at the top track shall be provided as shown on the drawings.
- d. Foundation bearing bottom track shall rest on a continuous, uniform, and level bearing surface.
- e. Tracks shall be securely anchored to the supporting structure as shown on the drawings.
- f. Bridging spaced as shown on the drawings shall be installed prior to loading and the installation of facing materials.
- g. Framed wall openings shall include headers and supporting components as shown on the drawings. Headers shall be installed in all openings which are larger than the stud spacing in a wall.
- h. At wall openings for doors, windows and other similar features, the framing system shall provide for the installation and anchorage of the required subframes or finish frames. Steel frames shall be securely attached through built-in anchors to the nearest stud on each side of the opening with self-drilling screws. Double studs shall be provided at both jambs of all door openings.
- i. Installation of sheathing, wallboards, or any other collateral material shall be performed in accordance with the product manufacturer's specifications.

3.3.3.2 Lateral Load (Shear Wall Panels)

Shear wall panels shall be installed at the locations shown; stud spacing and arrangement shall be as shown; diagonal bracing shall be placed across studs, pulled tight, and attached to each stud within the shear panel as shown on the drawings.

3.3.4 Omitted

3.3.5 Trusses

- a. Trusses shall be spaced as shown on the drawings.
- b. Trusses shall be bridged and braced as shown on the drawings before the installation of collateral materials.
- c. Temporary bracing shall be provided and remain in place until work

is permanently stabilized.

3.4 TOLERANCES

Vertical alignment (plumbness) of studs shall be within 1/960th of the span. Horizontal alignment (levelness) of walls shall be within 1/960th of their respective lengths. Spacing of studs shall not be more than plus 1/8 inch from the designed spacing providing the the cumulative error does not exceed the requirements of the finishing material.

3.5 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

Special inspections and testing for seismic-resisting systems and components shall be done in accordance with Section 01452A SPECIAL INSPECTION FOR SEISMIC-RESISTING SYSTEMS.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 05 - METALS

SECTION 05500A

MISCELLANEOUS METAL

01/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL REQUIREMENTS
 - 1.3.1 Performance Requirements
- 1.4 DISSIMILAR MATERIALS
- 1.5 WORKMANSHIP
- 1.6 ANCHORAGE
- 1.7 ALUMINUM FINISHES
- 1.8 SHOP PAINTING

PART 2 PRODUCTS

- 2.1 OMITTED
- 2.2 OMITTED
- 2.3 OMITTED
- 2.4 OMITTED
- 2.5 OMITTED
- 2.6 OMITTED
- 2.7 OMITTED
- 2.8 OMITTED
- 2.9 EXPANSION JOINT COVERS
- 2.10 OMITTED
- 2.11 OMITTED
- 2.12 FLOOR PLATES
- 2.13 OMITTED
- 2.14 HANDRAILS
 - 2.14.1 Steel Handrails, Including Carbon Steel Inserts
- 2.15 OMITTED
- 2.16 OMITTED
- 2.17 OMITTED
- 2.18 OMITTED
- 2.19 MISCELLANEOUS
- 2.20 OMITTED
- 2.21 OMITTED
- 2.22 OMITTED
- 2.23 SAFETY CHAINS
- 2.24 OMITTED
- 2.25 OMITTED
- 2.26 STEEL STAIRS AND MEZZANINE
- 2.27 SAFETY TREADS
- 2.28 TRENCH COVERS, FRAMES, AND LINERS
- 2.29 OMITTED
- 2.30 OMITTED
- 2.31 OMITTED
- 2.32 OMITTED
- 2.33 OMITTED

2.34 FIRE EXTINGUISHER CABINETS

PART 3 EXECUTION

- 3.1 GENERAL INSTALLATION REQUIREMENTS
- 3.2 OMITTED
- 3.3 OMITTED
- 3.4 OMITTED
- 3.5 OMITTED
- 3.6 OMITTED
- 3.7 ATTACHMENT OF HANDRAILS
 - 3.7.1 Installation of Steel Handrails
- 3.8 OMITTED
- 3.9 OMITTED
- 3.10 OMITTED
- 3.11 OMITTED
- 3.12 MOUNTING OF SAFETY CHAINS
- 3.13 OMITTED
- 3.14 OMITTED
- 3.15 TRENCH FRAMES AND COVERS
- 3.16 OMITTED
- 3.17 OMITTED
- 3.18 OMITTED
- 3.19 OMITTED
- 3.20 INSTALLATION OF FIRE EXTINGUISHER CABINETS

-- End of Section Table of Contents --

UFGS-05500A (January 2002)

SECTION 05500A

MISCELLANEOUS METAL

01/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF-45 (1997) Designation System for Aluminum Finishes

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 123/A 123M (2001) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A 36/A 36M (2000a) Carbon Structural Steel

ASTM A 467/A 467M (1998) Machine and Coil Chain

ASTM A 500 (1999) Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes

ASTM A 53/A 53M (2001) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A 653/A 653M (2000) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM A 924/A 924M (1999) General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process

ASTM E 814 (2000) Fire Tests of Through-Penetration Fire Stops

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1 (2000) Structural Welding Code - Steel

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10 (1998; Errata 10-98-1) Portable Fire Extinguishers

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-344

(Rev B) Lacquer, Clear Gloss, Exterior,
Interior

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Miscellaneous Metal Items

Detail drawings indicating material thickness, type, grade, and class; dimensions; and construction details. Drawings shall include catalog cuts, erection details, manufacturer's descriptive data and installation instructions, and templates. Detail drawings for the following items: stairs and platforms, trench covers, frames and liners, railings, and miscellaneous items

SD-04 Samples

Miscellaneous Metal Items

Samples of the following items: safety treads, floor plate. Samples shall be full size, taken from manufacturer's stock, and shall be complete as required for installation in the structure. Samples may be installed in the work, provided each sample is clearly identified and its location recorded.

1.3 GENERAL REQUIREMENTS

The Contractor shall verify all measurements and shall take all field measurements necessary before fabrication. Welding to or on structural steel shall be in accordance with AWS D1.1. Items specified to be galvanized, when practicable and not indicated otherwise, shall be hot-dip galvanized after fabrication. Galvanizing shall be in accordance with ASTM A 123/A 123M, ASTM A 653/A 653M, or ASTM A 924/A 924M, as applicable. Exposed fastenings shall be compatible materials, shall generally match in color and finish, and shall harmonize with the material to which fastenings are applied. Materials and parts necessary to complete each item, even though such work is not definitely shown or specified, shall be included. Poor matching of holes for fasteners shall be cause for rejection. Fastenings shall be concealed where practicable. Thickness of metal and details of assembly and supports shall provide strength and stiffness. Joints exposed to the weather shall be formed to exclude water.

1.3.1 Performance Requirements

Steel stairs, landings and mezzanine shall be capable of withstanding a uniform load of 100 pounds force per square foot, a concentrated load of 300 pounds force applied in an area of 4 square inches, with a maximum deflection of 1/240 of span or 1/4 inch, whichever is less. Railings and handrails shall withstand a uniform load of 50 pounds force per lineal foot applied in any direction and a concentrated load of 200 pounds force applied in any direction. Framing of stairs and platforms shall withstand

the additional loads applied to handrails and railings.

1.4 DISSIMILAR MATERIALS

Where dissimilar metals are in contact, or where aluminum is in contact with concrete, mortar, masonry, wet or pressure-treated wood, or absorptive materials subject to wetting, the surfaces shall be protected with a coat of bituminous paint or asphalt varnish.

1.5 WORKMANSHIP

Miscellaneous metalwork shall be well formed to shape and size, with sharp lines and angles and true curves. Drilling and punching shall produce clean true lines and surfaces. Welding shall be continuous along the entire area of contact except where tack welding is permitted. Exposed connections of work in place shall not be tack welded. Exposed welds shall be ground smooth. Exposed surfaces of work in place shall have a smooth finish, and unless otherwise approved, exposed riveting shall be flush. Where tight fits are required, joints shall be milled. Corner joints shall be coped or mitered, well formed, and in true alignment. Work shall be accurately set to established lines and elevations and securely fastened in place. Installation shall be in accordance with manufacturer's installation instructions and approved drawings, cuts, and details.

1.6 ANCHORAGE

Anchorage shall be provided where necessary for fastening miscellaneous metal items securely in place. Anchorage not otherwise specified or indicated shall include slotted inserts made to engage with the anchors, expansion shields, and power-driven fasteners when approved for concrete; toggle bolts and through bolts for masonry; machine and carriage bolts for steel; and lag bolts and screws for wood.

1.7 ALUMINUM FINISHES

Unless otherwise specified, aluminum items shall have standard mill finish. The thickness of the coating shall be not less than that specified for protective and decorative type finishes for items used in interior locations or architectural Class I type finish for items used in exterior locations in AA DAF-45. Items to be anodized shall receive a polished satin finish. Aluminum surfaces to be in contact with plaster or concrete during construction shall be protected with a field coat conforming to CID A-A-344.

1.8 SHOP PAINTING

Surfaces of ferrous metal except galvanized surfaces, shall be cleaned and shop coated with the manufacturer's standard protective coating unless otherwise specified. Surfaces of items to be embedded in concrete shall not be painted. Items to be finish painted shall be prepared according to manufacturer's recommendations or as specified.

PART 2 PRODUCTS

- 2.1 OMITTED
- 2.2 OMITTED
- 2.3 OMITTED
- 2.4 OMITTED
- 2.5 OMITTED

- 2.6 OMITTED
- 2.7 OMITTED
- 2.8 OMITTED

2.9 EXPANSION JOINT COVERS

Expansion joint covers shall be constructed of extruded aluminum with anodized satin finish for walls and ceilings and with standard mill finish for floor covers and exterior covers. Plates, backup angles, expansion filler strip and anchors shall be designed as indicated. Expansion joint system shall provide a one inch movement.

- 2.10 OMITTED
- 2.11 OMITTED

2.12 FLOOR PLATES

Floor plates for mezzanine floor shall be 1/4 inch thick, raised tread stainless steel.

- 2.13 OMITTED

2.14 HANDRAILS

Handrails shall be designed to resist a concentrated load of 200 pounds in any direction at any point of the top of the rail or 50 pounds per foot applied horizontally to top of the rail, whichever is more severe.

2.14.1 Steel Handrails, Including Carbon Steel Inserts

Steel handrails shall be steel pipe conforming to ASTM A 53/A 53M or structural tubing conforming to ASTM A 500, Grade A or B of equivalent strength. Steel railings shall be 1-1/2 inch nominal size. Railings shall be shop painted. Pipe collars shall be stainless steel.

- a. Joint posts, rail, and corners shall be fabricated by one of the following methods:

- (1) Flush type rail fittings of commercial standard, welded and ground smooth with railing splice locks secured with 3/8 inch hexagonal recessed-head setscrews.

- (2) Mitered and welded joints by fitting post to top rail and intermediate rail to post, mitering corners, groove welding joints, and grinding smooth. Railing splices shall be butted and reinforced by a tight fitting interior sleeve not less than 6 inches long.

- (3) Railings may be bent at corners in lieu of jointing, provided bends are made in suitable jigs and the pipe is not crushed.

- b. Brackets shall be provided as indicated.

- 2.15 OMITTED
- 2.16 OMITTED
- 2.17 OMITTED
- 2.18 OMITTED

2.19 MISCELLANEOUS

Miscellaneous plates and shapes for items that do not form a part of the structural steel framework, such as lintels, sill angles, miscellaneous mountings, and frames, shall be provided to complete the work.

2.20 OMITTED

2.21 OMITTED

2.22 OMITTED

2.23 SAFETY CHAINS

Safety chains shall be galvanized welded steel, proof coil chain tested in accordance with ASTM A 467/A 467M, Class CS. Safety chains shall be straight link style, 3/16 inch diameter, minimum 12 links per foot and with bolt type snap hooks on each end. Eye bolts for attachment of chains shall be galvanized 3/8 inch bolt with 3/4 inch eye, anchored as indicated. Two chains shall be furnished for each guarded opening.

2.24 OMITTED

2.25 OMITTED

2.26 STEEL STAIRS AND MEZZANINE

Steel stairs shall be complete with structural or formed channel stringers, steel plate treads and risers, landings, mezzanine framing and floor, columns, handrails, and necessary bolts and other fastenings as indicated. Structural steel shall conform to ASTM A 36/A 36M. Stairs and accessories shall be shop painted.

2.27 SAFETY TREADS

Cast gray iron, Class 20, with an integral abrasive finish consisting of aluminum oxide, silicon carbide, or a combination of both. Fabricate units in sizes and configurations indicated and in lengths necessary to accurately fit openings or conditions. Treads shall be cross-hatched units, full depth of tread with 3/4-by-3/4-inch nosing, for application over bent plate treads.

2.28 TRENCH COVERS, FRAMES, AND LINERS

Trench covers shall be designed to meet. Trench frames and anchors shall be all welded aluminum construction designed to match cover. Covers shall be secured to frame and have flush drop handles formed of 1/4 inch round stock, and shall be raised-tread, or aluminum floor plate. Trench liners shall be aluminum with integral frame for cover.

2.29 OMITTED

2.30 OMITTED

2.31 OMITTED

2.32 OMITTED

2.33 OMITTED

2.34 FIRE EXTINGUISHER CABINETS

Cabinets to be located in fire-rated walls shall be fire-rated type, fabricated in accordance with ASTM E 814, and shall be listed by an approved testing agency for 1- and 2-hour combustible and non-combustible wall systems. The testing agency's seal shall be affixed to each fire-rated cabinet. All cabinets shall be of the semi-recessed type suitable for 10 pound extinguishers. Box and trim shall be of heavy gage

rolled steel. Door shall be a rigid frame with full length piano type hinge and double strength (DSA) glass panel. Door and panel shall have the manufacturer's standard white baked enamel finish inside and out.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

All items shall be installed at the locations shown and according to the manufacturer's recommendations. Items listed below require additional procedures as specified.

- 3.2 OMITTED
- 3.3 OMITTED
- 3.4 OMITTED
- 3.5 OMITTED
- 3.6 OMITTED

3.7 ATTACHMENT OF HANDRAILS

Brackets shall be installed where indicated. Splices, where required, shall be made at expansion joints.

3.7.1 Installation of Steel Handrails

Installation shall be by means of base plates bolted or welded to stringers or structural steel framework. Rail ends shall be secured by steel pipe flanges anchored by expansion shields and bolts. or through-bolted to a back plate or by 1/4 inch lag bolts to studs or solid backing.

- 3.8 OMITTED
- 3.9 OMITTED
- 3.10 OMITTED
- 3.11 OMITTED

3.12 MOUNTING OF SAFETY CHAINS

Safety chains shall be mounted at heights indicated.

- 3.13 OMITTED
- 3.14 OMITTED

3.15 TRENCH FRAMES AND COVERS

Trench frames and covers shall finish flush with the floor.

- 3.16 OMITTED
- 3.17 OMITTED
- 3.18 OMITTED
- 3.19 OMITTED

3.20 INSTALLATION OF FIRE EXTINGUISHER CABINETS

Metal fire extinguisher cabinets shall be furnished and installed in accordance with NFPA 10 where shown on the drawings or specified.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 06 - WOODS & PLASTICS

SECTION 06100A

ROUGH CARPENTRY

02/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 LUMBER AND SHEATHING
 - 2.1.1 Grading and Marking
 - 2.1.1.1 Lumber Products
 - 2.1.1.2 Omitted
 - 2.1.1.3 Plywood and Other Sheathing Products
 - 2.1.2 Sizes
 - 2.1.3 Treatment
 - 2.1.3.1 Lumber and Timbers
 - 2.1.3.2 Plywood
 - 2.1.4 Moisture Content
 - 2.1.5 Fire-Retardant Treatment
 - 2.1.6 Omitted
 - 2.1.7 Sheathing
 - 2.1.7.1 Omitted
 - 2.1.7.2 Omitted
 - 2.1.7.3 Plywood
 - 2.1.8 Omitted
 - 2.1.9 Omitted
 - 2.1.10 Omitted
 - 2.1.11 Omitted
 - 2.1.12 Miscellaneous Wood Members
 - 2.1.12.1 Nonstress Graded Members
 - 2.1.12.2 Omitted
 - 2.1.12.3 Omitted
 - 2.1.12.4 Blocking
 - 2.1.12.5 Rough Bucks and Frames
- 2.2 ACCESSORIES AND NAILS
 - 2.2.1 Anchor Bolts
 - 2.2.2 Bolts: Lag, Toggle, and Miscellaneous Bolts and Screws
 - 2.2.3 Clip Angles
 - 2.2.4 Expansion Shields
 - 2.2.5 Joist Hangers
 - 2.2.6 Omitted
 - 2.2.7 Nails and Staples
- 2.3 INSULATION
 - 2.3.1 Batt or Blanket
 - 2.3.1.1 Glass Fiber Batts and Rolls
 - 2.3.1.2 Mineral Fiber Batt
 - 2.3.2 Omitted
 - 2.3.3 Omitted

- 2.3.4 Rigid Insulation
 - 2.3.4.1 Omitted
 - 2.3.4.2 Polyurethane or Polyisocyanurate Board

PART 3 EXECUTION

- 3.1 OMITTED
- 3.2 INSTALLATION OF SHEATHING
 - 3.2.1 Omitted
 - 3.2.2 Omitted
 - 3.2.3 Plywood
- 3.3 OMITTED
- 3.4 OMITTED
- 3.5 OMITTED
- 3.6 INSTALLATION OF MISCELLANEOUS WOOD MEMBERS
 - 3.6.1 Omitted
 - 3.6.2 Omitted
 - 3.6.3 Blocking
 - 3.6.4 Nailers and Nailing Strips
 - 3.6.5 Wood Grounds
 - 3.6.6 Furring Strips
 - 3.6.7 Rough Bucks and Frames
- 3.7 OMITTED
- 3.8 INSTALLATION OF INSULATION
- 3.9 TABLES

-- End of Section Table of Contents --

UFGS-06100A (February 2002)

SECTION 06100A

ROUGH CARPENTRY

02/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN FOREST & PAPER ASSOCIATION (AF&PA)

- AF&PA T101 (1991; Supple 1993; Addenda Apr 1997; Supple T02) National Design Specification for Wood Construction
- AF&PA T11 (1988) Manual for Wood Frame Construction
**

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)

- AITC 111 (1979) Recommended Practice for Protection of Structural Glued Laminated Timber During Transit, Storage and Erection

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

- ASTM A 307 (2000) Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
- ASTM C 1289 (1998) Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
- ASTM C 518 (1998) Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus
- ASTM C 591 (1994) Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
- ASTM C 665 (1998) Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing
- ASTM D 2898 (1994; R 1999) Accelerated Weathering of Fire-Retardant-Treated Wood for Fire Testing
- ASTM F 547 (1977; R 1995) Definitions of Terms Relating to Nails for Use with Wood and Wood-Based Materials

AMERICAN WOOD-PRESERVERS' ASSOCIATION (AWPA)

AWPA C2 (2000) Lumber, Timber, Bridge Ties and Mine Ties - Preservative Treatment by Pressure Processes

AWPA C20 (1999) Structural Lumber Fire-Retardant Pressure Treatment

AWPA C27 (1999) Plywood - Fire-Retardant Pressure Treatment

AWPA C9 (1997) Plywood - Preservative Treatment by Pressure Processes

AWPA M4 (1999) Standard for the Care of Preservative-Treated Wood Products

AWPA P5 (2000) Standards for Waterborne Preservatives

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA EWS R540C (1996) Builder Tips Proper Storage and Handling of Glulam Beams

APA PRP-108 (1980; Rev Jan 1996) Performance Standards and Policies for Structural-Use Panels

FACTORY MUTUAL ENGINEERING AND RESEARCH (FM)

FM LPD 1-49 (1995) Loss Prevention Data Sheet - Perimeter Flashing

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules (1997) Standard Grading Rules for Northeastern Lumber

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)

SCMA Spec (1986; Supple No. 1, Aug 1993) Standard Specifications for Grades of Southern Cypress

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB Rules (1994; Supple 8 thru 11) Standard Grading Rules for Southern Pine Lumber

U.S. DEPARTMENT OF COMMERCE (DOC)

PS-1 (1995) Construction and Industrial Plywood

PS-2 (1993) Wood-Base Structural-Use Panels

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17 (1996; Supp. VII & VIII) Standard Grading

and Dressing Rules for Douglas Fir,
Western Hemlock, Western Red Cedar, White
Fir, Sitka Spruce Lumber

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA Grading Rules

(1999) Western Lumber Grading Rules 95

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-07 Certificates

Grading and Marking

Manufacturer's certificates (approved by an American Lumber Standards approved agency) attesting that lumber and material not normally grade marked meet the specified requirements. Certificate of Inspection for grade marked material by an American Lumber Standards Committee (ALSC) recognized inspection agency prior to shipment.

Insulation

Certificate attesting that the cellulose, perlite, glass and mineral fiber, glass mat gypsum roof board, polyurethane, or polyisocyanurate insulation furnished for the project contains recovered material, and showing an estimated percent of such recovered material.

1.3 DELIVERY AND STORAGE

Materials shall be delivered to the site in undamaged condition, stored off ground in fully covered, well ventilated areas, and protected from extreme changes in temperature and humidity. Laminated timber shall be handled and stored in accordance with AITC 111 or APA EWS R540C.

PART 2 PRODUCTS

2.1 LUMBER AND SHEATHING

2.1.1 Grading and Marking

2.1.1.1 Lumber Products

Solid sawn and finger-jointed lumber shall bear an authorized gradestamp or grademark recognized by ALSC, or an ALSC recognized certification stamp, mark, or hammerbrand. Surfaces that are to be exposed to view shall not bear grademarks, stamps, or any type of identifying mark. Hammer marking will be permitted on timbers when all surfaces will be exposed to view.

2.1.1.2 Omitted

2.1.1.3 Plywood and Other Sheathing Products

Materials shall bear the grademark or other identifying marks indicating grades of material and rules or standards under which produced, including requirements for qualifications and authority of the inspection organization. Except for plywood and wood structural panels, bundle marking will be permitted in lieu of marking each individual piece. Surfaces that are to be exposed to view shall not bear grademarks or other types of identifying marks.

2.1.2 Sizes

Lumber and material sizes shall conform to requirements of the rules or standards under which produced. Unless otherwise specified, lumber shall be surfaced on four sides. Unless otherwise specified, sizes indicated are nominal sizes, and actual sizes shall be within manufacturing tolerances allowed by the standard under which the product is produced.

2.1.3 Treatment

Exposed areas of treated wood that are cut or drilled after treatment shall receive a field treatment in accordance with AWPA M4. Items of all-heart material of cedar, cypress, or redwood will not require preservative treatment, except when in direct contact with soil. Except as specified for all-heart material of the previously mentioned species, the following items shall be treated:

- a. Wood members in contact with or within 18 inches of soil.
- b. Wood members in contact with water.
- c. Wood members exposed to the weather and those used in roofing systems or as nailing strips or nailers over fiberboard or gypsum-board wall sheathing as a base for wood siding.

2.1.3.1 Lumber and Timbers

Lumber and timbers shall be treated in accordance with AWPA C2 with waterborne preservatives listed in AWPA P5 to a retention level as follows:

- a. 0.25 pcf intended for above ground use.

2.1.3.2 Plywood

Plywood shall be treated in accordance with AWPA C9 with waterborne preservatives listed in AWPA P5 to a retention level as follows:

- a. 0.25 pcf intended for above ground use.

2.1.4 Moisture Content

At the time lumber and other materials are delivered and when installed in the work their moisture content shall be as follows:

- a. Treated and Untreated Lumber: 4 inches or less, nominal thickness, 19 percent maximum. 5 inches or more, nominal thickness, 23 percent maximum in a 3 inch perimeter of the timber cross-section.
- b. Materials Other Than Lumber: In accordance with standard under which product is produced.

2.1.5 Fire-Retardant Treatment

Fire-retardant treated wood shall be pressure treated in accordance with AWPA C20 for lumber and AWPA C27 for plywood. Material use shall be defined in AWPA C20 and AWPA C27 for Interior Type A and Exterior Type. Treatment and performance inspection shall be by an independent and qualified testing agency that establishes performance ratings. Each piece or bundle of treated material shall bear identification of the testing agency to indicate performance in accordance with such rating. Treated materials to be exposed to rain wetting shall be subjected to an accelerated weathering technique in accordance with ASTM D 2898 prior to being tested for compliance with AWPA C20 or AWPA C27. Items to be treated are indicated on drawings.

2.1.6 Omitted

2.1.7 Sheathing

Sheathing shall be plywood for roof sheathing.

2.1.7.1 Omitted

2.1.7.2 Omitted

2.1.7.3 Plywood

Plywood shall conform to PS-1, APA PRP-108 or PS-2, Grade C-D with exterior glue. Sheathing for roof shall have a span rating of 16/0 or greater for supports 16 inches on center and a span rating of 24/0 or greater for supports 24 inches on center and indicated thickness.

2.1.8 Omitted

2.1.9 Omitted

2.1.10 Omitted

2.1.11 Omitted

2.1.12 Miscellaneous Wood Members

2.1.12.1 Nonstress Graded Members

Members shall include bridging, corner bracing, furring, grounds, and nailing strips. Members shall be in accordance with TABLE I for the species used. Sizes shall be as follows unless otherwise shown:

Member	Size (inch)
Furring	1 x 3 .
Grounds	Plaster thickness by 1-1/2.
Nailing strips	As indicated. Where not indicated, 1 x 3 or 1 x 4 when used as interior finish, otherwise 2 inch stock.

2.1.12.2 Omitted

2.1.12.3 Omitted

2.1.12.4 Blocking

Blocking shall be standard or number 2 grade.

2.1.12.5 Rough Bucks and Frames

Rough bucks and frames shall be straight standard or number 2 grade.

2.2 ACCESSORIES AND NAILS

Markings shall identify both the strength grade and the manufacturer. Accessories and nails shall conform to the following:

2.2.1 Anchor Bolts

ASTM A 307, size as indicated, complete with nuts and washers.

2.2.2 Bolts: Lag, Toggle, and Miscellaneous Bolts and Screws

Type, size, and finish best suited for intended use. Finish options include zinc compounds, cadmium, and aluminum paint impregnated finishes.

2.2.3 Clip Angles

Steel, 3/16 inch thick, size best suited for intended use; or zinc-coated steel or iron commercial clips designed for connecting wood members.

2.2.4 Expansion Shields

Type and size best suited for intended use.

2.2.5 Joist Hangers

Steel or iron, zinc-coated, size to fit members where used, sufficient strength to develop the full strength of supported member, complete with any special nails required.

2.2.6 Omitted

2.2.7 Nails and Staples

ASTM F 547, size and type best suited for purpose; staples shall be as recommended by the manufacturer of the materials to be joined. For sheathing, length of nails shall be sufficient to extend 1 inch into supports. In general, 8-penny or larger nails shall be used for nailing through 1 inch thick lumber and for toe nailing 2 inch thick lumber; 16-penny or larger nails shall be used for nailing through 2 inch thick lumber. Nails used with treated lumber and sheathing shall be galvanized. Nailing shall be in accordance with the recommended nailing schedule contained in AF&PA T11. Where detailed nailing requirements are not specified, nail size and spacing shall be sufficient to develop an adequate strength for the connection. The connection's strength shall be verified against the nail capacity tables in AF&PA T101. Reasonable judgement backed by experience shall ensure that the designed connection will not cause the wood to split. If a load situation exceeds a reasonable limit for nails, a specialized connector shall be used.

2.3 INSULATION

Thermal resistance of insulation shall be not less than the R-values shown.

R-values shall be determined at 75 degrees F in accordance with ASTM C 518.

Contractor shall comply with EPA requirements in conformance with Section 01670 RECYCLED / RECOVERED MATERIALS. Insulation shall be the standard product of a manufacturer and factory marked or identified with manufacturer's name or trademark and R-value. Identification shall be on individual pieces or individual packages. Materials containing more than one percent asbestos will not be allowed.

2.3.1 Batt or Blanket

2.3.1.1 Glass Fiber Batts and Rolls

Glass fiber batts and rolls shall conform to ASTM C 665, Type I unfaced insulation. Width and length shall suit construction conditions.

2.3.1.2 Mineral Fiber Batt

Mineral fiber batt shall conform to ASTM C 665, Type I unfaced insulation.

2.3.2 Omitted

2.3.3 Omitted

2.3.4 Rigid Insulation

2.3.4.1 Omitted

2.3.4.2 Polyurethane or Polyisocyanurate Board

Polyurethane or polyisocyanurate board shall have a minimum recovered material content of 20 percent by weight of core material in the polyurethane or polyisocyanurate portion. Unfaced preformed polyurethane shall conform to ASTM C 591. Faced polyisocyanurate shall conform to ASTM C 1289.

PART 3 EXECUTION

3.1 OMITTED

3.2 INSTALLATION OF SHEATHING

3.2.1 Omitted

3.2.2 Omitted

3.2.3 Plywood

Sheathing shall be applied with edges 1/8 inch apart at side and end joints, and screwed at supported edges at 6 inches on center and at intermediate supports 12 inches on center unless otherwise shown. Attachment of edges shall be 3/8 inch from the edges. Roof sheathing shall be applied with long dimension at right angles to supports, end joints made over supports, and end joints staggered.

3.3 OMITTED

3.4 OMITTED

3.5 OMITTED

3.6 INSTALLATION OF MISCELLANEOUS WOOD MEMBERS

3.6.1 Omitted

3.6.2 Omitted

3.6.3 Blocking

Blocking shall be provided as necessary for application of sheathing, concealed gutter, and other materials or building items. Blocking shall be cut to fit between framing members and rigidly attached thereto.

3.6.4 Nailers and Nailing Strips

Nailers and nailing strips shall be provided as necessary for the attachment of finish materials. Nailers used in conjunction with roof deck installation shall be installed flush with the roof deck system. Stacked nailers shall be assembled with spikes or nails spaced not more than 18 inches on center and staggered. Beginning and ending nails shall not be more than 6 inches for nailer end. Ends of stacked nailers shall be offset approximately 12 inches in long runs and alternated at corners. Anchors shall extend through the entire thickness of the nailer. Strips shall be run in lengths as long as practicable, butt jointed, cut into wood framing members when necessary, and rigidly secured in place. Nailers and nailer installation for Factory Mutual wind uplift rated roof systems specified in other Sections of these specifications shall conform to the recommendations contained in FM LPD 1-49.

3.6.5 Wood Grounds

Wood grounds shall be provided as necessary for attachment of trim, finish, and other work to plaster. Grounds shall be run in lengths as long as practicable, butt jointed, and rigidly secured in place.

3.6.6 Furring Strips

Furring strips shall be provided at the locations shown. Furring strips shall be installed at 16 inches on center unless otherwise shown, run in lengths as long as practicable, butt jointed and rigidly secured in place.

3.6.7 Rough Bucks and Frames

Rough bucks shall be set straight, true, and plumb, and secured with anchors near top and bottom of each wood member and at intermediate intervals of not more than 3 feet. Anchors for concrete shall be expansion bolts, and anchors for masonry shall be 3/16 x 1-1/4 inch steel straps extending not less than 8 inches into the masonry and turned down 2 inches into the masonry.

3.7 OMITTED

3.8 INSTALLATION OF INSULATION

Insulation shall be installed after construction has advanced to a point that the installed insulation will not be damaged by remaining work. For thermal insulation the actual installed thickness shall provide the R-values shown. For acoustical insulation the installed thickness shall be as shown. Insulation shall be installed on the weather side of such items as electrical boxes and water lines. Unless otherwise specified, installation shall be in accordance with the manufacturer's recommendation.

3.9 TABLES

TABLE I. SPECIES AND GRADE

Grading Rules	Species	Roof Sheathing, Furring			
		Const Standard	No. 2 Comm	No. 2 Board Comm	No. 3 Comm
NELMA Grading Rules					
	Northern White Cedar				X
	Eastern White Pine	X			
	Northern Pine	X			
	Balsam Fir				X
	Eastern Hemlock- Tamarack				X
SCMA Spec					
	Cypress			X	
SPIB Rules					
	Southern Pine		X		
WCLIB 17					
	Douglas Fir-Larch	X			
	Hem-Fir	X			
	Sitka Spruce	X			
	Mountain Hemlock	X			
	Western Cedar	X			
WWPA Grading Rules					
	Douglas Fir-Larch	X			
	Hem-Fir	X			
	Idaho White Pine	X			
	Lodgepole Pine			X	
	Ponderosa Pine			X	
	Sugar Pine			X	
	Englemann Spruce			X	
	Douglas Fir South			X	
	Mountain Hemlock			X	
	Subalpine Fir			X	
	Western Cedar			X	

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 06 - WOODS & PLASTICS

SECTION 06200A

FINISH CARPENTRY

11/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 WOOD ITEMS AND TRIM
 - 2.1.1 Grading and Marking
 - 2.1.2 Sizes and Patterns
 - 2.1.3 Moisture Content
 - 2.1.4 Preservative Treatment
 - 2.1.4.1 Plywood
 - 2.1.4.2 Omitted
 - 2.1.5 Omitted
 - 2.1.6 Omitted
 - 2.1.7 Omitted
 - 2.1.8 Omitted
 - 2.1.9 Trim
 - 2.1.9.1 Wood
 - 2.1.10 Moldings
 - 2.1.11 Omitted
 - 2.1.12 Woodwork Items
 - 2.1.12.1 Omitted
 - 2.1.12.2 Omitted
 - 2.1.12.3 Window Stools
- 2.2 NAILS
- 2.3 PLASTIC LAMINATE
 - 2.3.1 Window Stool Finish

PART 3 EXECUTION

- 3.1 OMITTED
- 3.2 OMITTED
- 3.3 OMITTED
- 3.4 MOLDING AND INTERIOR TRIM
- 3.5 OMITTED
- 3.6 OMITTED
- 3.7 OMITTED
- 3.8 TABLES

-- End of Section Table of Contents --

UFGS-06200A (November 2001)

SECTION 06200A

FINISH CARPENTRY

11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM F 547 (1977; R 1995) Definitions of Terms
Relating to Nails for Use with Wood and
Wood-Based Materials

AMERICAN WOOD-PRESERVERS' ASSOCIATION (AWPA)

AWPA C9 (1997) Plywood - Preservative Treatment by
Pressure Processes

AWPA P5 (2000) Standards for Waterborne
Preservatives

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA LD 3 (1995) High-Pressure Decorative Laminates

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules (1997) Standard Grading Rules for
Northeastern Lumber

REDWOOD INSPECTION SERVICE (RIS)

RIS GCRL (1987) Grades of California Redwood Lumber

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)

SCMA Spec (1986; Supple No. 1, Aug 1993) Standard
Specifications for Grades of Southern
Cypress

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB Rules (1994; Supple 8 thru 11) Standard Grading
Rules for Southern Pine Lumber

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17 (1996; Supples VII(A-E), VIII(A-C))
Grading Rules for West Coast Lumber

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA Grading Rules

(1999) Western Lumber Grading Rules 95

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Finish Carpentry

Drawings showing fabricated items and special mill and woodwork items. Drawings shall indicate materials and details of construction, methods of fastening, erection, and installation.

SD-04 Samples

Plastic Laminate

Samples shall be of sufficient size to show patterns, color ranges, and types, as applicable, of the material proposed to be used.

1.3 DELIVERY AND STORAGE

Materials shall be delivered to the site in undamaged condition, stored off ground in fully covered, well-ventilated areas, and protected from extreme changes in temperature and humidity.

PART 2 PRODUCTS

2.1 WOOD ITEMS AND TRIM

The Contractor shall furnish products which optimize design by reducing the amount of wood used (engineered wood), by using recycled wood products and preservatives without arsenic or chromium when the products and methods are competitive in price or directed by the Contracting Officer. The Contractor shall comply with EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS.

2.1.1 Grading and Marking

Materials shall bear the grademark, stamp or other identifying marks indicating grades of material and rules or standards under which produced. Such identifying marks on a material shall be in accordance with the rule or standard under which the material is produced, including requirements for qualifications and authority of the inspection organization, usage of authorized identification, and information included in the identification. The inspection agency for lumber shall be certified by the Board of Review, American Lumber Standards Committee, to grade the species used. Except for plywood, wood structural panels, and lumber, bundle marking will be permitted in lieu of marking each individual piece. Surfaces that are to

be architecturally exposed to view shall not bear grademarks, stamps, or other types of identifying marks.

2.1.2 Sizes and Patterns

Lumber sizes and patterns shall conform to rules or standards under which produced. Unless otherwise specified, lumber shall be surfaced on four sides. Sizes and patterns for materials other than lumber shall conform to requirements of the rules or standards under which produced. Size references, unless otherwise specified, are nominal sizes, and actual sizes shall be within manufacturing tolerances allowed by the standard under which the product is produced.

2.1.3 Moisture Content

The maximum moisture content of untreated trim and wood siding shall be 15 percent at the time of delivery to the jobsite and when installed. Moisture content of all other material shall be in accordance with the standard under which the product is produced.

2.1.4 Preservative Treatment

2.1.4.1 Plywood

Plywood shall be treated in accordance with AWPA C9 with waterborne preservatives listed in AWPA P5 to a retention level as follows:

- a. 0.25 pcf intended for above ground use.

2.1.4.2 Omitted

2.1.5 Omitted

2.1.6 Omitted

2.1.7 Omitted

2.1.8 Omitted

2.1.9 Trim

2.1.9.1 Wood

Trim shall be select grade red oak. Sizes shall be as indicated.

2.1.10 Moldings

Moldings shall be of the pattern indicated and shall be of a grade compatible with the finish specified.

2.1.11 Omitted

2.1.12 Woodwork Items

2.1.12.1 Omitted

2.1.12.2 Omitted

2.1.12.3 Window Stools

plywood, interior type, Grade A-B, 3/4 inch thick, any species group, clad with plastic laminate.

2.2 NAILS

Nails shall be the size and type best suited for the purpose and shall conform to ASTM F 547. Nails shall be hot-dip galvanized or aluminum when used on exterior work. For siding, length of nails shall be sufficient to extend 1-1/2 inches into supports, including wood sheathing over framing. Screws for use where nailing is impractical shall be size best suited for purpose.

2.3 PLASTIC LAMINATE

NEMA LD 3.

2.3.1 Window Stool Finish

Grade GP 50, satin finish. Color and pattern shall be as indicated.

PART 3 EXECUTION

3.1 OMITTED

3.2 OMITTED

3.3 OMITTED

3.4 MOLDING AND INTERIOR TRIM

Molding and interior trim shall be installed straight, plumb, level and with closely fitted joints. Exposed surfaces shall be machine sanded at the mill. Molded work shall be coped at returns and interior angles and mitered at external corners. Intersections of flatwork shall be shouldered to ease any inherent changes in plane. Window and door trim shall be provided in single lengths. Blind nailing shall be used to the extent practicable, and face nailing shall be set and stopped with a nonstaining putty to match the finish applied. Screws shall be used for attachment to metal; setting and stopping of screws shall be of the same quality as required where nails are used.

3.5 OMITTED

3.6 OMITTED

3.7 OMITTED

3.8 TABLES

TABLE I. SPECIES AND GRADE TABLES

Grading Rules	Species	Choice	Clear	C Select	C & Better
NELMA Grading Rules					
	Eastern Cedar				X
	Eastern Hemlock		X		
	Tamarack				X
	Eastern W. Pine				X
	Northern Pine				X
	Eastern Spruce			X	
	Balsam Fir		X		
RIS GCRL	Redwood		X		
SCMA Spec	Cypress			X	
SPIB Rules	Southern Pine				X
WCLIB 17	Douglas Fir				X

TABLE I. SPECIES AND GRADE TABLES

Grading Rules	Species	Choice	Clear	C Select	C & Better
WWPA Grading Rules	Larch				X
	Hemlock Fir				X
	Mountain Hemlock				X
	Sitka Spruce				X
	Douglas Fir				X
	Larch				X
	Hemlock Fir			X	
	Mountain Hemlock				X
	Western Larch			X	
	Idaho White Pine	X			
	Lodgepole Pine			X	
	Ponderosa Pine			X	
	Sugar Pine			X	
	Englemann Spruce			X	
Douglas Fir South			X		
Subalpine Fir			X		

NOTE 1: Western Cedar under WCLIB 17 shall be Grade B; and under WWPA Grading Rules, Western Cedar shall be Grade B bevel for siding and Grade A for trim.

NOTE 2: Except as specified in NOTE 3 below, siding and exterior trim shall be any of the species listed above. Interior trim shall be any one of the species listed above and the highest grade of the species for stain or natural finish and one grade below highest grade of species for paint finish.

NOTE 3: Southern Yellow Pine, Douglas Fir, Larch, Western Larch, and Tamarack shall not be used where painting is required and may be used on exterior work only when approved and stained with a preservative type stain.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL & MOISTURE PROTECTION

SECTION 07110A

BITUMINOUS DAMPPROOFING

09/98

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALIFICATIONS
- 1.4 DELIVERY, STORAGE AND HANDLING

PART 2 PRODUCTS

- 2.1 EMULSION-BASED ASPHALT DAMPPROOFING
 - 2.1.1 Fibrated Emulsion-Based Asphalt

PART 3 EXECUTION

- 3.1 SURFACE PREPARATION
 - 3.1.1 Protection of Surrounding Areas
 - 3.1.2 Omitted
 - 3.1.3 Omitted
 - 3.1.4 Metal Surfaces
- 3.2 APPLICATION OF BITUMINOUS DAMPPROOFING
 - 3.2.1 Emulsion-Based Asphalt
- 3.3 CLEAN-UP
- 3.4 PROTECTION

-- End of Section Table of Contents --

UFGS-07110A (September 1998)

SECTION 07110A

BITUMINOUS DAMPPROOFING

09/98

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 1227 (1995) Emulsified Asphalt Used as a Protective Coating for Roofing

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-07 Certificates

Materials

Certificates attesting that the materials meet the requirements specified.

1.3 QUALIFICATIONS

Work shall be performed by skilled laborers thoroughly experienced in the type of bituminous dampproofing work specified to meet the requirements of the contract.

1.4 DELIVERY, STORAGE AND HANDLING

Dampproofing materials shall be delivered to the project site in the original sealed containers bearing the name of manufacturer, contents and brand name, and stored in a weathertight enclosure to prevent moisture damage and absorption. Dampproofing materials shall be protected from freezing. Asphalt shall be stored off the ground on pallets, and covered on top and all sides with breathable-type canvas tarpaulins. Plastic sheets cause condensation buildup; and therefore, shall not be used to cover dampproofing materials. Care shall be taken during storage to avoid separation or settlement of the emulsion components. Damaged or deteriorated materials shall be removed from the project site.

PART 2 PRODUCTS

2.1 EMULSION-BASED ASPHALT DAMPPROOFING

2.1.1 Fibrated Emulsion-Based Asphalt

Fibrated emulsion-based asphalt dampproofing shall be cold-applied type conforming to ASTM D 1227 Type IV, asbestos-free, manufactured of refined asphalt, emulsifiers and selected clay, fibrated with mineral fibers. For spray or brush application, emulsion shall contain a minimum of 59 percent solids by weight, 56 percent solids by volume.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Surfaces scheduled for bituminous dampproofing shall be prepared in accordance with dampproofing manufacturer's recommendations. Surface preparation shall be approved prior to dampproofing application.

3.1.1 Protection of Surrounding Areas

Before starting the dampproofing work, the surrounding areas and surfaces shall be protected from spillage and migration of asphalt onto other work. Drains and conductors shall be protected from clogging with asphalt.

3.1.2 Omitted

3.1.3 Omitted

3.1.4 Metal Surfaces

Metal surfaces shall be dry and be free of rust, scale, loose paint, oil, grease, dirt, frost and debris.

3.2 APPLICATION OF BITUMINOUS DAMPPROOFING

3.2.1 Emulsion-Based Asphalt

Emulsion-based asphalt dampproofing work shall not be performed in temperatures below 40 degrees F. Emulsions shall have a smooth and uniform consistency at time of application. Dampproofing materials shall be applied in accordance with manufacturer's published instructions to produce a smooth uniform dry film of not less than 12 mils thick without voids or defects. Dull or porous spots shall be recoated. Dampproofing materials shall seal tightly around pipes and other items projecting through dampproofing. Rates of application shall be as follows:

a. Primer: 1/2 gallon per 100 square feet, cold-applied.

b. Non-fibrated Dampproofing: 2 gallons per 100 square feet, cold-applied with spray, brush or trowel.

3.3 CLEAN-UP

Surfaces of other work which are stained with dampproofing materials shall be cleaned with a cleaner recommended by dampproofing manufacturer.

3.4 PROTECTION

The completed dampproofing work shall be protected from damage during and

after construction.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL & MOISTURE PROTECTION

SECTION 07416A

STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM

11/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 GENERAL REQUIREMENTS
 - 1.2.1 Structural Standing Seam Metal Roof (SSSMR) System
 - 1.2.2 Manufacturer
 - 1.2.3 Installer
- 1.3 DESIGN REQUIREMENTS
 - 1.3.1 Design Criteria
 - 1.3.2 Dead Loads
 - 1.3.3 Live Loads
 - 1.3.3.1 Concentrated Loads
 - 1.3.3.2 Uniform Loads
 - 1.3.4 Roof Snow Loads
 - 1.3.5 Wind Loads
 - 1.3.6 Thermal Loads
 - 1.3.7 Framing Members Supporting the SSSMR System
 - 1.3.8 Roof Panels Design
 - 1.3.9 Accessories and Their Fasteners
- 1.4 PERFORMANCE REQUIREMENTS
- 1.5 SUBMITTALS
- 1.6 DELIVERY AND STORAGE
- 1.7 WARRANTIES
 - 1.7.1 Contractor's Weathertightness Warranty
 - 1.7.2 Manufacturer's Material Warranties.
- 1.8 COORDINATION MEETING

PART 2 PRODUCTS

- 2.1 ROOF PANELS
 - 2.1.1 Steel Panels
 - 2.1.2 Aluminum Panels
- 2.2 CONCEALED ANCHOR CLIPS
- 2.3 ACCESSORIES
- 2.4 FASTENERS
 - 2.4.1 Screws
 - 2.4.2 Bolts
 - 2.4.3 Structural Blind Fasteners
- 2.5 OMITTED
- 2.5 FACTORY COLOR FINISH
 - 2.5.1 Salt Spray Test
 - 2.5.2 Formability Test
 - 2.5.3 Accelerated Weathering, Chalking Resistance and Color Change
 - 2.5.4 Humidity Test
 - 2.5.5 Impact Resistance
 - 2.5.6 Abrasion Resistance Test
 - 2.5.7 Omitted
 - 2.5.8 Pollution Resistance

- 2.6 INSULATION
 - 2.6.1 Polyisocyanurate Rigid Board Insulation for Use Above a Roof Deck
 - 2.6.2 Omitted
 - 2.6.3 Glass Mat Gypsum Roof Board
- 2.7 OMITTED
- 2.8 SEALANT
- 2.9 GASKETS AND INSULATING COMPOUNDS
- 2.10 UNDERLAYMENT
 - 2.10.1 Self-Adhering Membrane
 - 2.10.2 Slip Sheet for Use With Underlayment
- 2.11 EPDM RUBBER BOOTS

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Field Forming of Panels for Unique Area
 - 3.1.2 Omitted
 - 3.1.3 Roof Panel Installation
 - 3.1.4 Concealed Anchor Clips
- 3.2 INSULATION INSTALLATION
 - 3.2.1 Board Insulation
- 3.3 OMITTED
- 3.4 UNDERLAYMENT INSTALLATION
 - 3.4.1 Self-Adhering Sheet Underlayment
- 3.5 OMITTED
- 3.6 CLEANING AND TOUCH-UP

-- End of Section Table of Contents --

UFGS-07416A (November 2001)

SECTION 07416A

STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM
11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ALUMINUM ASSOCIATION (AA)

AA Design Manual (2000) Aluminum Design Manual:
Specification & Guidelines for Aluminum
Structures

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI Cold-Formed Mnl (1996) Cold-Formed Steel Design Manual

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 463/A 463M (2000) Steel Sheet, Aluminum-Coated, by
the Hot-Dip Process

ASTM A 653/A 653M (2000) Steel Sheet, Zinc-Coated
(Galvanized) or Zinc-Iron Alloy-Coated
(Galvannealed) by the Hot-Dip Process

ASTM A 792/A 792M (1999) Steel Sheet, 55% Aluminum-Zinc
Alloy-Coated by the Hot-Dip Process

ASTM B 209 (2000) Aluminum and Aluminum-Alloy Sheet
and Plate

ASTM C 1177/C 1177M (1999) Glass Mat Gypsum Substrate for Use
as Sheathing

ASTM C 1289 (1998) Faced Rigid Cellular
Polyisocyanurate Thermal Insulation Board

ASTM C 518 (1998) Steady-State Heat Flux Measurements
and Thermal Transmission Properties by
Means of the Heat Flow Meter Apparatus

ASTM D 1308 (1987; R 1998) Effect of Household
Chemicals on Clear and Pigmented Organic
Finishes

ASTM D 1654 (1992) Evaluation of Painted or Coated
Specimens Subjected to Corrosive

Environments

ASTM D 2244	(1995) Calculation of Color Differences from Instrumentally Measured Color Coordinates
ASTM D 2247	(1999) Testing Water Resistance of Coatings in 100% Relative Humidity
ASTM D 2794	(1993; R 1999e1) Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)
ASTM D 3359	(1997) Measuring Adhesion by Tape Test
ASTM D 4214	(1998) Evaluating Degree of Chalking of Exterior Paint Films
ASTM D 522	(1993a) Mandrel Bend Test of Attached Organic Coatings
ASTM D 5894	(1996) Standard Practice for Cyclic Salt Fog/UV Exposure of Painted Metal, (Alternating Exposures in a Fog/Dry Cabinet and a UV/Condensation Cabinet)
ASTM D 610	(1995) Evaluating Degree of Rusting on Painted Steel Surfaces
ASTM D 714	(1987; R 1994e1) Evaluating Degree of Blistering of Paints
ASTM D 968	(1993) Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM E 1592	(1998) Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference
ASTM D 1970	(2001) Self-Adhering Polymer Modified Bituminous Sheet Materials Used as Steep Roofing Underlayment for Ice Dam Protection
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials
ASTM G 154	(2000ae1) Standard Practice for Operating Fluorescent Light Apparatus for UV Exposure of Nonmetallic Materials
AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)	
ASCE 7	(1998) Minimum Design Loads for Buildings and Other Structures

1.2 GENERAL REQUIREMENTS

The Contractor shall furnish a commercially available roofing system which satisfies all requirements contained herein and has been verified by load testing and independent design analyses to meet the specified design requirements.

1.2.1 Structural Standing Seam Metal Roof (SSSMR) System

The SSSMR system covered under this specification shall include the entire roofing system; the standing seam metal roof panels, fasteners, connectors, roof securement components, and assemblies tested and approved in accordance with ASTM E 1592. In addition, the system shall consist of panel finishes, slip sheet, insulation, underlayment and slip sheet, all accessories, components, and trim and all connections with roof panels. This includes roof penetration items such as vents, curbs, interior or exterior gutters and downspouts; eaves, ridge, hip, valley, rake, wall, or other roof system flashings installed and any other components specified within this contract to provide a weathertight roof system.

1.2.2 Manufacturer

The SSSMR system shall be the product of a manufacturer who has been in the practice of manufacturing and designing SSSMR systems for a period of not less than 3 years and has been involved in at least five projects similar in size and complexity to this project.

1.2.3 Installer

The installer shall be certified by the SSSMR system manufacturer to have experience in installing at least three projects that are of comparable size, scope and complexity as this project for the particular roof system furnished. The installer may be either employed by the manufacturer or be an independent installer.

1.3 DESIGN REQUIREMENTS

The design of the SSSMR system shall be provided by the Contractor as a complete system. Members and connections not indicated on the drawings shall be designed by the Contractor. Roof panels, components, transitions, accessories, and assemblies shall be supplied by the same roofing system manufacturer.

1.3.1 Design Criteria

Design criteria shall be in accordance with ASCE 7.

1.3.2 Dead Loads

The dead load shall be the weight of the SSSMR system. Collateral loads such as sprinklers, mechanical and electrical systems, and ceilings shall not be attached to the panels.

1.3.3 Live Loads

1.3.3.1 Concentrated Loads

The panels and anchor clips shall be capable of supporting a 300 pound concentrated load. The concentrated load shall be applied at the panel midspan and will be resisted by a single standing seam metal roof panel assumed to be acting as a beam. The undeformed shape of the panel shall be

used to determine the section properties.

1.3.3.2 Uniform Loads

The panels and concealed anchor clips shall be capable of supporting a minimum uniform live load of 20 psf.

1.3.4 Roof Snow Loads

The design roof snow loads shall be as shown on the contract drawings.

1.3.5 Wind Loads

The design wind uplift pressure for the roof system shall be as shown on the contract drawings. The design uplift force for each connection assembly shall be that pressure given for the area under consideration, multiplied by the tributary load area of the connection assembly. The safety factor listed below shall be applied to the design force and compared against the ultimate capacity. Prying shall be considered when figuring fastener design loads.

- a. Single fastener in each connection.....3.0
- b. Two or more fasteners in each connection...2.25

1.3.6 Thermal Loads

Roof panels shall be free to move in response to the expansion and contraction forces resulting from a total temperature range of 104 degrees F during the life of the structure.

1.3.7 Framing Members Supporting the SSSMR System

Any additions/revisions to framing members supporting the SSSMR system to accommodate the manufacturer/fabricator's design shall be the Contractor's responsibility and shall be submitted for review and approval. New or revised framing members and their connections shall be designed in accordance with AISI Cold-Formed Mnl. Maximum deflection under applied live load, snow, or wind load shall not exceed 1/180 of the span length.

1.3.8 Roof Panels Design

Steel panels shall be designed in accordance with AISI Cold-Formed Mnl. Aluminum panels shall be designed in accordance with AA Design Manual. The structural section properties used in the design of the panels shall be determined using the unloaded shape of the roof panels. The calculated panel deflection from concentrated loads shall not exceed 1/180 of the span length. The calculated panel deflection under applied live load, snow, or wind load shall not exceed 1/180 times the span length. Deflections shall be based on panels being continuous across three or more supports. Deflection shall be calculated and measured along the major ribs of the panels.

1.3.9 Accessories and Their Fasteners

Accessories and their fasteners shall be capable of resisting the specified design wind uplift forces and shall allow for thermal movement of the roof panel system. Exposed fasteners shall not restrict free movement of the roof panel system resulting from thermal forces. There shall be a minimum

of two fasteners per clip. Single fasteners with a minimum diameter of 3/8 inch will be allowed when the supporting structural members are prepunched or predrilled.

1.4 PERFORMANCE REQUIREMENTS

The SSSMR shall be tested for wind uplift resistance in accordance with ASTM E 1592; SSSMR systems previously tested and approved by the Corps of Engineers' STANDARD TEST METHOD FOR STRUCTURAL PERFORMANCE OF SSMRS BY UNIFORM STATIC AIR PRESSURE DIFFERENCE may be acceptable. Two tests shall be performed. Test 1 shall simulate the edge condition with one end having crosswise restraint and other end free of crosswise restraint. The maximum span length for the edge condition shall be 30 inches. Test 2 shall simulate the interior condition with both ends free of crosswise restraint.

The maximum span length for the interior condition shall be 5.0 feet. External reinforcement, such as clamps on the ribs, shall not be installed to improve uplift resistance. Bolts through seams shall not be installed.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Drawings

Structural Standing Seam Metal Roof System; G, AE.

Metal roofing drawings and specifications and erection drawings; shop coating and finishing specifications; and other data as necessary to clearly describe design, materials, sizes, layouts, standing seam configuration, construction details, provisions for thermal movement, line of panel fixity, fastener sizes and spacings, sealants and erection procedures. Drawings shall reflect the intent of the architectural detailing using the manufacturer's proprietary products and fabricated items as required. The SSSMR system shop drawings shall be provided by the metal roofing manufacturer.

SD-03 Product Data

Design Analysis; G, AE.

Design analysis signed by a Registered Professional Engineer employed by the SSSMR manufacturer. The design analysis shall include a list of the design loads, and complete calculations for the support system (when provided by the Contractor), roofing system and its components; valley designs, gutter/downspout calculations, screw pullout test results, and shall indicate how expected thermal movements are accommodated.

Qualifications.

Qualifications of the manufacturer and installer.

SD-06 Test Reports

Test Report for Uplift Resistance of the SSSMR; G, AE.

The report shall include the following information:

- a. Details of the SSSMR system showing the roof panel cross-section with dimensions and thickness.
- b. Details of the anchor clip, dimensions, and thickness.
- c. Type of fasteners, size, and the number required for each connection.
- d. Purlin size and spacing used in the test.
- e. Description of the seaming operation including equipment used.
- f. Maximum allowable uplift pressures. These pressures are determined from the ultimate load divided by a factor of safety equal to 1.65.
- g. Any additional information required to identify the SSSMR system tested.
- h. Signature and seal of an independent registered engineer who witnessed the test.

SD-07 Certificates

Structural Standing Seam Metal Roof System.

- a. Certification that the actual thickness of uncoated sheets used in SSSMRS components including roofing panels, and concealed anchor clips complies with specified requirements.
- b. Certification that materials used in the installation are mill certified.
- c. Previous certification of SSSMR system tested under the Corps of Engineers' Standard Test Method in lieu of ASTM E 1592 testing.
- d. Certification that the sheets to be furnished are produced under a continuing quality control program and that a representative sample consisting of not less than three pieces has been tested and has met the quality standards specified for factory color finish.
- e. Certification of installer. Installer certification shall be furnished.
- f. Warranty certificate. At the completion of the project the Contractor shall furnish signed copies of the 5-year Warranty for Structural Standing Seam Metal Roof (SSSMR) System, a sample copy of which is attached to this section, and the 20-year Manufacturer's Material Warranties, and the manufacturer's 20-year system weathertightness warranty.

Insulation.

Certificate attesting that the polyurethane or polyisocyanurate insulation furnished for the project contains recovered material, and showing an estimated percent of such recovered material.

1.6 DELIVERY AND STORAGE

Materials shall be delivered to the site in a dry and undamaged condition and stored out of contact with the ground. Materials shall be covered with weathertight coverings and kept dry. Storage conditions shall provide good air circulation and protection from surface staining.

1.7 WARRANTIES

The SSSMR system shall be warranted as outlined below. Any emergency temporary repairs conducted by the owner shall not negate the warranties.

1.7.1 Contractor's Weathertightness Warranty

The SSSMR system shall be warranted by the Contractor on a no penal sum basis for a period of five years against material and workmanship deficiencies; system deterioration caused by exposure to the elements and/or inadequate resistance to specified service design loads, water leaks, and wind uplift damage. The SSSMR system covered under this warranty shall include the entire roofing system including, but not limited to, the standing seam metal roof panels, fasteners, connectors, roof securement components, and assemblies tested and approved in accordance with ASTM E 1592. In addition, the system shall consist of panel finishes, slip sheet, insulation, underlayment, all accessories, components, and trim and all connections with roof panels. This includes roof penetration items such as vents, curbs, and skylights; interior or exterior gutters and downspouts; eaves, ridge, hip, valley, rake, wall, or other roof system flashings installed and any other components specified within this contract to provide a weathertight roof system; and items specified in other sections of these specifications that are part of the SSSMR system. All material and workmanship deficiencies, system deterioration caused by exposure to the elements and/or inadequate resistance to specified design loads, water leaks and wind uplift damage shall be repaired as approved by the Contracting Officer. See the attached Contractor's required warranty for issue resolution of warrantable defects. This warranty shall warrant and cover the entire cost of repair or replacement, including all material, labor, and related markups. The Contractor shall supplement this warranty with written warranties from the installer and system manufacturer, which shall be submitted along with Contractor's warranty; however, the Contractor shall be ultimately responsible for this warranty. The Contractor's written warranty shall be as outlined in attached WARRANTY FOR STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM, and shall start upon final acceptance of the facility. It is required that the Contractor provide a separate bond in an amount equal to the installed total roofing system cost in favor of the owner (Government) covering the Contractor's warranty responsibilities effective throughout the five year Contractor's warranty period for the entire SSSMR system as outlined above.

1.7.2 Manufacturer's Material Warranties.

The Contractor shall furnish, in writing, the following manufacturer's material warranties which cover all SSSMR system components such as roof panels, anchor clips and fasteners, flashing, accessories, and trim, fabricated from coil material:

a. A manufacturer's 20 year material warranty warranting that the aluminum, zinc-coated steel, aluminum-zinc alloy coated steel or aluminum-coated steel as specified herein will not rupture, structurally fail, fracture, deteriorate, or become perforated under normal design atmospheric conditions and service design loads. Liability under this warranty shall be limited exclusively to the cost of either repairing or replacing nonconforming, ruptured, perforated, or structurally failed coil material.

b. A manufacturer's 20 year exterior material finish warranty on the factory colored finish warranting that the finish, under normal atmospheric conditions at the site, will not crack, peel, or delaminate; chalk in excess of a numerical rating of eight, as determined by ASTM D 4214 test procedures; or change color in excess of five CIE or Hunter Lab color difference (ΔE) units in accordance with ASTM D 2244. Liability under this warranty is exclusively limited to refinishing with an air-drying version of the specified finish or replacing the defective coated material.

c. A roofing system manufacturer's 20 year system weathertightness warranty.

1.8 COORDINATION MEETING

A coordination meeting shall be held 30 days prior to the first submittal, for mutual understanding of the Structural Standing Seam Metal Roof (SSSMR) System contract requirements. This meeting shall take place at the building site and shall include representatives from the Contractor, the roof system manufacturer, the roofing supplier, the erector, the SSSMR design engineer of record, and the Contracting Officer. All items required by paragraph SUBMITTALS shall be discussed, including applicable standard manufacturer shop drawings, and the approval process. The Contractor shall coordinate time and arrangements for the meeting.

PART 2 PRODUCTS

2.1 ROOF PANELS

Panels shall be steel or aluminum and shall have a factory color finish. Length of sheets shall be sufficient to cover the entire length of any unbroken roof slope for slope lengths that do not exceed 30 feet. When length of run exceeds 30 feet and panel laps are provided, each sheet in the run shall extend over three or more supports. Sheets longer than 100 feet may be furnished if approved by the Contracting Officer. Width of sheets shall provide not more than 24 inches of coverage in place. SSSMR system with roofing panels greater than 12 inches in width shall have standing seams rolled during installation by an electrically driven seaming machine. Height of standing seams shall be not less than 2 inches for rolled seam and 1-1/2 inches for seams that are not rolled.

2.1.1 Steel Panels

Steel panels shall be zinc-coated steel conforming to ASTM A 653/A 653M; aluminum-zinc alloy coated steel conforming to ASTM A 792/A 792M, AZ 50 coating; or aluminum-coated steel conforming to ASTM A 463/A 463M, Type 2, coating designation T2 65. Zinc, zinc-aluminum alloy or aluminum coated panels shall be 0.023 inch thick minimum. Panels shall be within 95 percent of reported tested thickness as noted in wind uplift resistance testing required in paragraph PERFORMANCE REQUIREMENTS.

2.1.2 Aluminum Panels

Alloy conforming to ASTM B 209, temper as required for the forming operation, minimum 0.032 inch thick.

2.2 CONCEALED ANCHOR CLIPS

Concealed anchor clips shall be the same as the tested roofing system. Clip bases shall have factory punched or drilled holes for attachment. Clips shall be made from multiple pieces with the allowance for the total thermal movement required to take place within the clip. Single piece clips may be acceptable when the manufacturer can substantiate that the system can accommodate the thermal cyclic movement under sustained live or snow loads.

2.3 ACCESSORIES

Flashing, trim, metal closure strips, caps and similar metal accessories shall be the manufacturer's standard products. Exposed metal accessories shall be finished to match the panels furnished. Die cast metal closures shall be installed with double bead tape sealant and fasteners that stitch the panel to a 16 gage preformed backer plate to ensure a positive compression of the tape sealant. The use of a continuous angle butted to the panel ends to form a closure will not be allowed.

2.4 FASTENERS

Fasteners for steel roof panels shall be zinc-coated steel, aluminum, corrosion resisting steel, or nylon capped steel, type and size specified below or as otherwise approved for the applicable requirements. Fasteners for aluminum roof panels shall be aluminum or corrosion resisting steel. Fasteners for structural connections shall provide both tensile and shear ultimate strengths of not less than 750 pounds per fastener. Fasteners for accessories shall be the manufacturer's standard. Exposed roof fasteners shall be sealed or have sealed washers on the exterior side of the roof to waterproof the fastener penetration. Washer material shall be compatible with the roofing; have a minimum diameter of 3/8 inch for structural connections; and gasketed portion of fasteners or washers shall be neoprene or other equally durable elastomeric material approximately 1/8 inch thick. Exposed fasteners for factory color finished panels shall be factory finished to match the color of the panels.

2.4.1 Screws

Screws for attaching anchor devices shall be not less than No. 14. Actual screw pull out test results shall be performed for the actual material gage and yield strength of the structural purlins or deck to which the clip is to be anchored/attached. Other screws shall be as recommended by the manufacturer to meet the strength design requirements of the panels.

2.4.2 Bolts

Bolts shall be not less than 1/4 inch diameter, shouldered or plain shank as required, with locking washers and nuts.

2.4.3 Structural Blind Fasteners

Blind screw-type expandable fasteners shall be not less than 1/4 inch

diameter. Blind (pop) rivets shall be not less than 9/32 inch minimum diameter.

2.5 OMITTED

2.5 FACTORY COLOR FINISH

Panels shall have a factory applied polyvinylidene fluoride finish on the exposed side. The exterior finish shall consist of a baked-on topcoat with an appropriate prime coat. Color shall match the existing building. The exterior coating shall be a nominal 2 mil thickness consisting of a topcoat of not less than 0.7 mil dry film thickness and the paint manufacturer's recommended primer of not less than 1.0 mil thickness. The interior color finish shall consist of a backer coat with a dry film thickness of 0.5 mil. The exterior color finish shall meet the test requirements specified below.

2.5.1 Salt Spray Test

A sample of the sheets shall withstand a cyclic corrosion test for a minimum of 2016 hours in accordance with ASTM D 5894, including the scribe requirement in the test. Immediately upon removal of the panel from the test, the coating shall receive a rating of not less than 10, no blistering, as determined by ASTM D 714; 10, no rusting, as determined by ASTM D 610; and a rating of 6, over 21/16 to 1/8 inch failure at scribe, as determined by ASTM D 1654.

2.5.2 Formability Test

When subjected to testing in accordance with ASTM D 522 Method B, 1/8 inch diameter mandrel, the coating film shall show no evidence of cracking to the naked eye.

2.5.3 Accelerated Weathering, Chalking Resistance and Color Change

A sample of the sheets shall be tested in accordance with ASTM G 154, test condition B for 1000 total hours. The coating shall withstand the weathering test without cracking, peeling, blistering, loss of adhesion of the protective coating, or corrosion of the base metal. Protective coating that can be readily removed from the base metal with tape in accordance with ASTM D 3359, Test Method B, shall be considered as an area indicating loss of adhesion. Following the accelerated weathering test, the coating shall have a chalk rating not less than No. 8 in accordance with ASTM D 4214 test procedures, and the color change shall not exceed 5 CIE or Hunter Lab color difference (delta E) units in accordance with ASTM D 2244.

2.5.4 Humidity Test

When subjected to a humidity cabinet test in accordance with ASTM D 2247 for 1000 hours, a scored panel shall show no signs of blistering, cracking, creepage or corrosion.

2.5.5 Impact Resistance

Factory-painted sheet shall withstand direct and reverse impact in accordance with ASTM D 2794 0.500 inch diameter hemispherical head indenter, equal to 1.5 times the metal thickness in mils, expressed in inch-pounds, with no cracking.

2.5.6 Abrasion Resistance Test

When subjected to the falling sand test in accordance with ASTM D 968, Method A, the coating system shall withstand a minimum of 50 liters of sand before the appearance of the base metal. The term "appearance of base metal" refers to the metallic coating on steel or the aluminum base metal.

2.5.7 Omitted

2.5.8 Pollution Resistance

Coating shall show no visual effects when covered spot tested in a 10 percent hydrochloric acid solution for 24 hours in accordance with ASTM D 1308.

2.6 INSULATION

Thermal resistance of insulation shall be not less than the R-values shown on the contract drawings. R-values shall be determined at a mean temperature of 75 degrees F in accordance with ASTM C 518. Insulation shall be a standard product with the insulation manufacturer, factory marked or identified with insulation manufacturer's name or trademark and R-value. Identification shall be on individual pieces or individual packages. Insulation shall have a flame spread not in excess of 25 and a smoke developed rating not in excess of 250 when tested in accordance with ASTM E 84. The stated R-value of the insulation shall be certified by an independent Registered Professional Engineer if tests are conducted in the insulation manufacturer's laboratory.

2.6.1 Polyisocyanurate Rigid Board Insulation for Use Above a Roof Deck

Polyisocyanurate insulation shall conform to ASTM C 1289, Type II, (having a minimum recovered material content of 9 percent by weight of core material in the polyisocyanurate portion). For polyisocyanurate, the maximum design R-value per 1 inch of insulation used shall be 7.2. Facings shall be non-asphaltic, glass fiber reinforced.

2.6.2 Omitted

2.6.3 Glass Mat Gypsum Roof Board

Glass mat gypsum roof board for use above the insulation shall have a flame spread - 0, smoke developed - 0, shall be water resistant and have a compressive strength of 500 psi. Glass mat gypsum roof board shall conform to ASTM C 1177/C 1177M.

2.7 OMITTED

2.8 SEALANT

Sealants shall be elastomeric type containing no oil or asphalt. Exposed sealant shall be colored to match the applicable building color and shall cure to a rubberlike consistency. Sealant placed in the roof panel standing seam ribs shall be provided in accordance with the manufacturer's recommendations.

2.9 GASKETS AND INSULATING COMPOUNDS

Gaskets and insulating compounds shall be nonabsorptive and suitable for insulating contact points of incompatible materials. Insulating compounds

shall be nonrunning after drying.

2.10 UNDERLAYMENT

2.10.1 Self-Adhering Membrane

ASTM D 1970, 40 mils thick minimum, consisting of slip-resisting polyethylene-film reinforcing and top surface laminated to SBS-modified asphalt adhesive, with release-paper backing; cold applied..

2.10.2 Slip Sheet for Use With Underlayment

Slip sheet for use with underlayment shall be a 5 lb. per 100 square feet rosin-sized, unsaturated building paper.

2.11 EPDM RUBBER BOOTS

Flashing devices around pipe penetrations shall be flexible, one-piece devices molded from weather-resistant EPDM rubber. Rubber boot material shall be as recommended by the manufacturer. The boots shall have base rings made of aluminum or corrosion resisting steel that conform to the contours of the roof panel to form a weather-tight seal.

PART 3 EXECUTION

3.1 INSTALLATION

Installation shall be in accordance with the manufacturer's erection instructions and drawings. Dissimilar materials which are not compatible when contacting each other shall be insulated by means of gaskets or insulating compounds. Closure strips shall be installed wherever roofing sheets terminate in open-end configurations, exclusive of flashings. The closure strip installation shall be weather-tight and sealed. Screws shall be installed with a clutching screw gun, to assure screws are not stripped.

Field test shall be conducted on each gun prior to starting installation and periodically thereafter to assure it is adjusted properly to install particular type and size of screw as recommended by manufacturer's literature. Improper or mislocated drill holes shall be plugged with an oversize screw fastener and gasketed washer; however, sheets with an excess of such holes or with such holes in critical locations shall not be used. Exposed surfaces and edges shall be kept clean and free from sealant, metal cuttings, hazardous burrs, and other foreign material. Stained, discolored, or damaged sheets shall be removed from the site.

3.1.1 Field Forming of Panels for Unique Area

When roofing panels are formed from factory-color-finished steel coils at the project site, the same care and quality control measures that are taken in shop forming of roofing panels shall be observed. Rollformer shall be operated by the metal roofing manufacturer's representative. In cold weather conditions, preheating of the steel coils to be field formed shall be performed as necessary just prior to the rolling operations.

3.1.2 Omitted

3.1.3 Roof Panel Installation

Roof panels shall be installed with the standing seams in the direction of the roof slope. The side seam connections for installed panels shall be

completed at the end of each day's work. Method of applying joint sealant shall conform to the manufacturer's recommendation to achieve a complete weather-tight installation. End laps of panels shall be provided in accordance with the manufacturer's instructions. Closures, flashings, EPDM rubber boots, roof curbs, and related accessories shall be installed according to the manufacturer's drawings. Fasteners shall not puncture roofing sheets except as provided for in the manufacturer's instructions for erection and installation. Expansion joints for the standing seam roof system shall be installed at locations indicated on the contract drawings and other locations indicated on the manufacturer's drawings.

3.1.4 Concealed Anchor Clips

Concealed anchor clips shall be fastened through the roof board and insulation to the metal deck in strict accordance with the approved detail drawings and the manufacturer's instructions. The maximum distance, parallel to the seams, between clips shall be 30 inches on center at the corner, edge, and ridge zones, and 5 feet maximum on centers for the remainder of the roof.

3.2 INSULATION INSTALLATION

Insulation shall be continuous over entire roof surface. Where expansion joints, terminations, and other connections are made, the cavity shall be filled with batt insulation with vapor retarder providing equivalent R-value and perm rating as remaining insulation. Insulation shall be installed as indicated and in accordance with manufacturer's instructions.

3.2.1 Board Insulation

Rigid or semirigid board insulation shall be laid in close contact. Board shall be attached to the metal roof deck with bearing plates and fasteners, as recommended by the insulation manufacturer, so that the insulation joints are held tight against each other, and shall have a minimum of 1 fastener per 4 square feet. Layout and joint pattern of insulation and fasteners shall be indicated on the shop drawings. If more than one layer of insulation is required, joints in the second layer shall be offset from joints in the first layer.

3.3 OMITTED

3.4 UNDERLAYMENT INSTALLATION

3.4.1 Self-Adhering Sheet Underlayment

: Install self-adhering sheet underlayment, wrinkle free, on roof board under metal roof panels. Apply primer if required by manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation; use primer rather than nails for installing underlayment at low temperatures. Apply over entire roof, in shingle fashion to shed water, with end laps of not less than 6 inches staggered 24 inches between courses. Overlap side edges not less than 3-1/2 inches. Roll laps with roller. Cover underlayment within 14 days³. Apply slip sheet over underlayment before installing metal roof panels.

3.5 OMITTED

3.6 CLEANING AND TOUCH-UP

Exposed SSSMR systems shall be cleaned at completion of installation. Debris that could cause discoloration and harm to the panels, flashings, closures and other accessories shall be removed. Grease and oil films, excess sealants, and handling marks shall be removed and the work shall be scrubbed clean. Exposed metal surfaces shall be free of dents, creases, waves, scratch marks, and solder or weld marks. Immediately upon detection, abraded or corroded spots on shop-painted surfaces shall be wire brushed and touched up with the same material used for the shop coat. Factory color finished surfaces shall be touched up with the manufacturer's recommended touch up paint.

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM

FACILITY DESCRIPTION _____

BUILDING NUMBER: _____

CORPS OF ENGINEERS CONTRACT NUMBER: _____

CONTRACTOR

CONTRACTOR: _____

ADDRESS: _____

POINT OF CONTACT: _____

TELEPHONE NUMBER: _____

OWNER

OWNER: _____

ADDRESS: _____

POINT OF CONTACT: _____

TELEPHONE NUMBER: _____

CONSTRUCTION AGENT

CONSTRUCTION AGENT: _____

ADDRESS: _____

POINT OF CONTACT: _____

TELEPHONE NUMBER: _____

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM
(continued)

THE SSSMR SYSTEM INSTALLED ON THE ABOVE NAMED BUILDING IS WARRANTED BY _____ FOR A PERIOD OF FIVE (5) YEARS AGAINST WORKMANSHIP AND MATERIAL DEFICIENCIES, WIND DAMAGE, STRUCTURAL FAILURE, AND LEAKAGE. THE SSSMR SYSTEM COVERED UNDER THIS WARRANTY SHALL INCLUDE, BUT SHALL NOT BE LIMITED TO, THE FOLLOWING: THE ENTIRE ROOFING SYSTEM, MANUFACTURER SUPPLIED FRAMING AND STRUCTURAL MEMBERS, METAL ROOF PANELS, FASTENERS, CONNECTORS, ROOF SECUREMENT COMPONENTS, AND ASSEMBLIES TESTED AND APPROVED IN ACCORDANCE WITH ASTM E 1592. IN ADDITION, THE SYSTEM PANEL FINISHES, SLIP SHEET, INSULATION, UNDERLAYMENT, ALL ACCESSORIES, COMPONENTS, AND TRIM AND ALL CONNECTIONS ARE INCLUDED. THIS INCLUDES ROOF PENETRATION ITEMS SUCH AS VENTS, CURBS, SKYLIGHTS; INTERIOR OR EXTERIOR GUTTERS AND DOWNSPOUTS; EAVES, RIDGE, HIP, VALLEY, RAKE, WALL, OR OTHER ROOF SYSTEM FLASHINGS INSTALLED AND ANY OTHER COMPONENTS SPECIFIED WITHIN THIS CONTRACT TO PROVIDE A WEATHERTIGHT ROOF SYSTEM; AND ITEMS SPECIFIED IN OTHER SECTIONS OF THE SPECIFICATIONS THAT ARE PART OF THE SSSMR SYSTEM.

ALL MATERIAL DEFICIENCIES, WIND DAMAGE, STRUCTURAL FAILURE, AND LEAKAGE ASSOCIATED WITH THE SSSMR SYSTEM COVERED UNDER THIS WARRANTY SHALL BE REPAIRED AS APPROVED BY THE CONTRACTING OFFICER. THIS WARRANTY SHALL COVER THE ENTIRE COST OF REPAIR OR REPLACEMENT, INCLUDING ALL MATERIAL, LABOR, AND RELATED MARKUPS. THE ABOVE REFERENCED WARRANTY COMMENCED ON THE DATE OF FINAL ACCEPTANCE ON _____ AND WILL REMAIN IN EFFECT FOR STATED DURATION FROM THIS DATE.

SIGNED, DATED, AND NOTARIZED (BY COMPANY PRESIDENT)

(Company President) (Date)

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM
(continued)

THE CONTRACTOR SHALL SUPPLEMENT THIS WARRANTY WITH WRITTEN WARRANTIES FROM THE MANUFACTURER AND/OR INSTALLER OF THE SSSMR SYSTEM, WHICH SHALL BE SUBMITTED ALONG WITH THE CONTRACTOR'S WARRANTY. HOWEVER, THE CONTRACTOR WILL BE ULTIMATELY RESPONSIBLE FOR THIS WARRANTY AS OUTLINED IN THE SPECIFICATIONS AND AS INDICATED IN THIS WARRANTY EXAMPLE.

EXCLUSIONS FROM COVERAGE

1. NATURAL DISASTERS, ACTS OF GOD (LIGHTNING, FIRE, EXPLOSIONS, SUSTAINED WIND FORCES IN EXCESS OF THE DESIGN CRITERIA, EARTHQUAKES, AND HAIL).
2. ACTS OF NEGLIGENCE OR ABUSE OR MISUSE BY GOVERNMENT OR OTHER PERSONNEL, INCLUDING ACCIDENTS, VANDALISM, CIVIL DISOBEDIENCE, WAR, OR DAMAGE CAUSED BY FALLING OBJECTS.
3. DAMAGE BY STRUCTURAL FAILURE, SETTLEMENT, MOVEMENT, DISTORTION, WARPAGE, OR DISPLACEMENT OF THE BUILDING STRUCTURE OR ALTERATIONS MADE TO THE BUILDING.
4. CORROSION CAUSED BY EXPOSURE TO CORROSIVE CHEMICALS, ASH OR FUMES GENERATED OR RELEASED INSIDE OR OUTSIDE THE BUILDING FROM CHEMICAL PLANTS, FOUNDRIES, PLATING WORKS, KILNS, FERTILIZER FACTORIES, PAPER PLANTS, AND THE LIKE.
5. FAILURE OF ANY PART OF THE SSSMR SYSTEM DUE TO ACTIONS BY THE OWNER TO INHIBIT FREE DRAINAGE OF WATER FROM THE ROOF AND GUTTERS AND DOWNSPOUTS OR ALLOW PONDING WATER TO COLLECT ON THE ROOF SURFACE. CONTRACTOR'S DESIGN SHALL INSURE FREE DRAINAGE FROM THE ROOF AND NOT ALLOW PONDING WATER.
6. THIS WARRANTY APPLIES TO THE SSSMR SYSTEM. IT DOES NOT INCLUDE ANY CONSEQUENTIAL DAMAGE TO THE BUILDING INTERIOR OR CONTENTS WHICH IS COVERED BY THE WARRANTY OF CONSTRUCTION CLAUSE INCLUDED IN THIS CONTRACT.
7. THIS WARRANTY CANNOT BE TRANSFERRED TO ANOTHER OWNER WITHOUT WRITTEN CONSENT OF THE CONTRACTOR; AND THIS WARRANTY AND THE CONTRACT PROVISIONS WILL TAKE PRECEDENCE OVER ANY CONFLICTS WITH STATE STATUTES.

**

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM
(continued)

**REPORTS OF LEAKS AND SSSMR SYSTEM DEFICIENCIES SHALL BE RESPONDED TO WITHIN 48 HOURS OF RECEIPT OF NOTICE, BY TELEPHONE OR IN WRITING, FROM EITHER THE OWNER OR CONTRACTING OFFICER. EMERGENCY REPAIRS TO PREVENT FURTHER ROOF LEAKS SHALL BE INITIATED IMMEDIATELY; A WRITTEN PLAN SHALL BE SUBMITTED FOR APPROVAL TO REPAIR OR REPLACE THIS SSSMR SYSTEM WITHIN SEVEN (7) CALENDAR DAYS. ACTUAL WORK FOR PERMANENT REPAIRS OR REPLACEMENT SHALL BE STARTED WITHIN 30 DAYS AFTER RECEIPT OF NOTICE, AND COMPLETED WITHIN A REASONABLE TIME FRAME. IF THE CONTRACTOR FAILS TO ADEQUATELY RESPOND TO THE WARRANTY PROVISIONS, AS STATED IN THE CONTRACT AND AS CONTAINED HEREIN, THE CONTRACTING OFFICER MAY HAVE THE SSSMR SYSTEM REPAIRED OR REPLACED BY OTHERS AND CHARGE THE COST TO THE CONTRACTOR.

IN THE EVENT THE CONTRACTOR DISPUTES THE EXISTENCE OF A WARRANTABLE DEFECT, THE CONTRACTOR MAY CHALLENGE THE OWNER'S DEMAND FOR REPAIRS AND/OR REPLACEMENT DIRECTED BY THE OWNER OR CONTRACTING OFFICER EITHER BY REQUESTING A CONTRACTING OFFICER'S DECISION UNDER THE CONTRACT DISPUTES ACT, OR BY REQUESTING THAT AN ARBITRATOR RESOLVE THE ISSUE. THE REQUEST FOR AN ARBITRATOR MUST BE MADE WITHIN 48 HOURS OF BEING NOTIFIED OF THE DISPUTED DEFECTS. UPON BEING INVOKED, THE PARTIES SHALL, WITHIN TEN (10) DAYS, JOINTLY REQUEST A LIST OF FIVE (5) ARBITRATORS FROM THE FEDERAL MEDIATION AND CONCILIATION SERVICE. THE PARTIES SHALL CONFER WITHIN TEN (10) DAYS AFTER RECEIPT OF THE LIST TO SEEK AGREEMENT ON AN ARBITRATOR. IF THE PARTIES CANNOT AGREE ON AN ARBITRATOR, THE CONTRACTING OFFICER AND THE PRESIDENT OF THE CONTRACTOR'S COMPANY WILL STRIKE ONE (1) NAME FROM THE LIST ALTERNATIVELY UNTIL ONE (1) NAME REMAINS. THE REMAINING PERSON SHALL BE THE DULY SELECTED ARBITRATOR. THE COSTS OF THE ARBITRATION, INCLUDING THE ARBITRATOR'S FEE AND EXPENSES, COURT REPORTER, COURTROOM OR SITE SELECTED, ETC., SHALL BE BORNE EQUALLY BETWEEN THE PARTIES. EITHER PARTY DESIRING A COPY OF THE TRANSCRIPT SHALL PAY FOR THE TRANSCRIPT. A HEARING WILL BE HELD AS SOON AS THE PARTIES CAN MUTUALLY AGREE. A WRITTEN ARBITRATOR'S DECISION WILL BE REQUESTED NOT LATER THAN 30 DAYS FOLLOWING THE HEARING. THE DECISION OF THE ARBITRATOR WILL NOT BE BINDING; HOWEVER, IT WILL BE ADMISSIBLE IN ANY SUBSEQUENT APPEAL UNDER THE CONTRACT DISPUTES ACT.

A FRAMED COPY OF THIS WARRANTY SHALL BE POSTED IN THE MECHANICAL ROOM OR OTHER APPROVED LOCATION DURING THE ENTIRE WARRANTY PERIOD.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL & MOISTURE PROTECTION

SECTION 07600A

SHEET METALWORK, GENERAL

11/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 GENERAL REQUIREMENTS
- 1.3 SUBMITTALS
- 1.4 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Accessories
 - 2.1.2 Aluminum Extrusions
 - 2.1.3 Bituminous Cement
 - 2.1.4 Sealant
 - 2.1.5 Fasteners
 - 2.1.6 Felt
 - 2.1.7 Polyvinyl Chloride (PVC) Reglets
 - 2.1.8 Aluminum Alloy Sheet and Plate
 - 2.1.9 Copper
 - 2.1.10 Stainless Steel
 - 2.1.11 Solder
 - 2.1.12 Through-Wall Flashing

PART 3 EXECUTION

- 3.1 GENERAL REQUIREMENTS
- 3.2 EXPANSION JOINTS
- 3.3 PROTECTION OF ALUMINUM
 - 3.3.1 Paint
 - 3.3.2 Nonabsorptive Tape or Gasket
- 3.4 CONNECTIONS AND JOINTING
 - 3.4.1 Soldering
 - 3.4.2 Riveting
 - 3.4.3 Seaming
- 3.5 CLEATS
- 3.6 GUTTERS AND DOWNSPOUTS
- 3.7 FLASHINGS
 - 3.7.1 Base Flashing
 - 3.7.2 Counter Flashings
 - 3.7.3 Stepped Flashing
 - 3.7.4 Through-Wall Flashing
 - 3.7.4.1 Lintel Flashing
 - 3.7.4.2 Sill Flashing
- 3.8 OMITTED
- 3.9 OMITTED
- 3.10 REGLETS
- 3.11 CONTRACTOR QUALITY CONTROL

-- End of Section Table of Contents --

UFGS-07600A (November 2001)

SECTION 07600A

SHEET METALWORK, GENERAL
11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 167	(1999) Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM B 209	(2000) Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B 221	(2000) Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B 32	(1996) Solder Metal
ASTM B 370	(1998) Copper Sheet and Strip for Building Construction
ASTM D 1784	(1999a) Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D 226	(1997a) Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D 2822	(1991; R 1997e1) Asphalt Roof Cement
ASTM D 4022	(1994) Coal Tar Roof Cement, Asbestos Containing
ASTM D 4586	(1993; R 1999) Asphalt Roof Cement, Asbestos Free

SHEET METAL & AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION
(SMACNA)

SMACNA Arch. Manual	(1993; Errata; Addenda Oct 1997) Architectural Sheet Metal Manual
---------------------	--

1.2 GENERAL REQUIREMENTS

Sheet metalwork not being provided under Section 07416A STRUCTURAL STANDING SEAM METAL ROOF (SSSMR) SYSTEM shall be accomplished to form weathertight construction without waves, warps, buckles, fastening stresses or distortion, and shall allow for expansion and contraction. Cutting, fitting, drilling, and other operations in connection with sheet metal required to accommodate the work of other trades shall be performed by sheet metal mechanics. Installation of sheet metal items used in conjunction with roofing shall be coordinated with roofing work to permit continuous roofing operations. Sheet metalwork pertaining to heating, ventilating, and air conditioning is specified in Section 15700A UNITARY HEATING AND COOLING EQUIPMENT.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Materials

Drawings of sheet metal items showing weights, gauges or thicknesses; types of materials; expansion-joint spacing; fabrication details; and installation procedures.

1.4 DELIVERY, STORAGE, AND HANDLING

Materials shall be adequately packaged and protected during shipment and shall be inspected for damage, dampness, and wet-storage stains upon delivery to the jobsite. Materials shall be clearly labeled as to type and manufacturer. Sheet metal items shall be carefully handled to avoid damage. Materials shall be stored in dry, ventilated areas until immediately before installation.

PART 2 PRODUCTS

2.1 MATERIALS

Lead, lead-coated metal shall not be used. Galvanized steel shall be used only where specifically indicated. Except for these restrictions, any metal listed by SMACNA Arch. Manual for a particular item may be used, unless otherwise specified or indicated. Galvanized steel shall only be used with a 40 mil thick EPDM liner, fully adhered with adhesive recommended by the EPDM manufacturer, for internal (concealed) gutter and outlets and transitions from gutter into leaders. Materials shall conform to the requirements specified below and to the thicknesses and configurations established in SMACNA Arch. Manual. Different items need not be of the same metal, except that if copper is selected for any exposed item, all exposed items shall be copper.

2.1.1 Accessories

Accessories and other items essential to complete the sheet metal installation, though not specifically indicated or specified, shall be provided.

2.1.2 Aluminum Extrusions

ASTM B 221, Alloy 6063, Temper T5.

2.1.3 Bituminous Cement

Type I asphalt cement conforming to ASTM D 2822 or ASTM D 4586. For coal tar roofing; coal tar cement conforming to ASTM D 4022.

2.1.4 Sealant

Unless otherwise specified, sealant shall be an elastomeric weather resistant sealant as specified in Section 07900A JOINT SEALING.

2.1.5 Fasteners

Fasteners shall be compatible with the fastened material and shall be the type best suited for the application.

2.1.6 Felt

ASTM D 226, Type I.

2.1.7 Polyvinyl Chloride (PVC) Reglets

ASTM D 1784, Class 14333D, 0.075 inch minimum thickness.

2.1.8 Aluminum Alloy Sheet and Plate

ASTM B 209, fluoropolymer color clad, form, alloy, and temper appropriate for use. Use for all sheet metalwork exposed to view in finished structure.

2.1.9 Copper

ASTM B 370, Temper H 00.

2.1.10 Stainless Steel

ASTM A 167, Type 302 or 304; fully annealed, dead soft temper.

2.1.11 Solder

ASTM B 32, 95-5 tin-antimony.

2.1.12 Through-Wall Flashing

- a. Electro-sheet copper not less than 5 ounces, factory coated both sides with acid- and alkali-resistant bituminous compound not less than 6 ounces per square foot or factory covered both sides with asphalt-saturated cotton fabric, asphalt saturated glass-fiber fabric, or with 40 pound reinforced kraft paper bonded with asphalt.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Gutters and downspouts shall be designed and fabricated in conformance with

SMACNA Arch. Manual; louvers are specified in Section 10201N. Unless otherwise specified or indicated, exposed edges shall be folded back to form a 1/2 inch hem on the concealed side, and bottom edges of exposed vertical surfaces shall be angled to form drips. Bituminous cement shall not be placed in contact with roofing membranes other than built-up roofing.

3.2 EXPANSION JOINTS

Expansion joints shall be provided as specified in SMACNA Arch. Manual. Expansion joints in continuous sheet metal shall be provided at 40 foot intervals for copper and stainless steel and at 32 foot intervals for aluminum, except extruded aluminum gravel stops and fasciae which shall have expansion joints at not more than 12 foot spacing. Joints shall be evenly spaced. An additional joint shall be provided where the distance between the last expansion joint and the end of the continuous run is more than half the required interval spacing.

3.3 PROTECTION OF ALUMINUM

Aluminum shall not be used where it will be in contact with copper or where it will contact water which flows over copper surfaces. Aluminum that will be in contact with wet or pressure-treated wood, mortar, concrete, masonry, or ferrous metals shall be protected against galvanic or corrosive action by one of the following methods:

3.3.1 Paint

Aluminum surfaces shall be solvent cleaned and given one coat of zinc-molybdate primer and one coat of aluminum paint as specified in Section 09900 PAINTING, GENERAL.

3.3.2 Nonabsorptive Tape or Gasket

Nonabsorptive tape or gasket shall be placed between the adjoining surfaces and cemented to the aluminum surface using a cement compatible with aluminum.

3.4 CONNECTIONS AND JOINTING

3.4.1 Soldering

Soldering shall apply to copper, and stainless steel items. Edges of sheet metal shall be pretinned before soldering is begun. Soldering shall be done slowly with well heated soldering irons so as to thoroughly heat the seams and completely sweat the solder through the full width of the seam. Edges of stainless steel to be pretinned shall be treated with soldering acid flux. Soldering shall follow immediately after application of the flux. Upon completion of soldering, the acid flux residue shall be thoroughly cleaned from the sheet metal with a water solution of washing soda and rinsed with clean water.

3.4.2 Riveting

Joints in aluminum sheets 0.040 inch or less in thickness shall be mechanically made.

3.4.3 Seaming

Flat-lock and soldered-lap seams shall finish not less than 1 inch wide.

Unsoldered plain-lap seams shall lap not less than 3 inches unless otherwise specified. Flat seams shall be made in the direction of the flow.

3.5 CLEATS

A continuous cleat shall be provided where indicated or specified to secure loose edges of the sheet metalwork. Butt joints of cleats shall be spaced approximately 1/8 inch apart. The cleat shall be fastened to supporting wood construction with nails evenly spaced not over 12 inches on centers. Where the fastening is to be made to concrete or masonry, screws shall be used and shall be driven in expansion shields set in concrete or masonry.

3.6 GUTTERS AND DOWNSPOUTS

Gutters and downspouts if not provided as part of the SSSMR, shall be installed as indicated. Gutters shall be supported as indicated. Downspouts shall be rigidly attached to the building. Supports for downspouts shall be spaced according to manufacturer's recommendations.

3.7 FLASHINGS

Flashings shall be installed at locations indicated and as specified below. Sealing shall be according to the flashing manufacturer's recommendations. Flashings shall be installed at intersections of roof with vertical surfaces and at projections through roof, except that flashing for heating and plumbing, including piping, roof, and floor drains, and for electrical conduit projections through roof or walls are specified in other sections. Except as otherwise indicated, counter flashings shall be provided over base flashings. Perforations in flashings made by masonry anchors shall be covered up by an application of bituminous plastic cement at the perforation. Flashing shall be installed on top of joint reinforcement. Flashing shall be formed to direct water to the outside of the system.

3.7.1 Base Flashing

Metal base flashing shall be coordinated with roofing work. Metal base flashing shall be set in plastic bituminous cement over the roofing membrane, nailed to nailing strip, and secured in place on the roof side with nails spaced not more than 3 inches on centers. Metal base flashing shall not be used on built-up roofing.

3.7.2 Counter Flashings

Except as otherwise indicated, counter flashings shall be provided over base flashings. Counter flashing shall be installed as shown on the drawings. Where bituminous base flashings are provided, the counter flashing shall extend down as close as practicable to the top of the cant strip. Counter flashing shall be factory formed to provide spring action against the base flashing.

3.7.3 Stepped Flashing

Stepped flashing shall be installed where sloping roofs surfaced with shingles abut vertical surfaces. Separate pieces of base flashing shall be placed in alternate shingle courses.

3.7.4 Through-Wall Flashing

Through-wall flashing includes sill, lintel, and spandrel flashing. The

flashing shall be laid with a layer of mortar above and below the flashing so that the total thickness of the two layers of the mortar and flashing are the same thickness as the regular mortar joints. Flashing shall not extend further into the masonry backup wall than the first mortar joint. Joints in flashing shall be lapped and sealed. Flashing shall be one piece for lintels and sills.

3.7.4.1 Lintel Flashing

Lintel flashing shall extend the full length of lintel. Flashing shall extend through the wall one masonry course above the lintels and shall be bent down over the vertical leg of the outer steel lintel angle not less than 2 inches, or shall be applied over top of masonry and precast concrete lintels. Bedjoints of lintels at control joints shall be underlaid with sheet metal bond breaker.

3.7.4.2 Sill Flashing

Sill flashing shall extend the full width of the sill and not less than 4 inches beyond ends of sill except at control joint where the flashing shall be terminated at the end of the sill.

3.8 OMITTED

3.9 OMITTED

3.10 REGLETS

Reglets shall be a factory fabricated product of proven design, complete with fittings and special shapes as required. Open-type reglets shall be filled with fiberboard or other suitable separator to prevent crushing of the slot during installation. Reglet plugs shall be spaced not over 12 inches on centers and reglet grooves shall be filled with sealant. Friction or slot-type reglets shall have metal flashings inserted the full depth of slot and shall be lightly punched every 12 inches to crimp the reglet and counter flashing together. Polyvinyl chloride reglets shall be sealed with the manufacturer's recommended sealant.

3.11 CONTRACTOR QUALITY CONTROL

The Contractor shall establish and maintain a quality control procedure for sheet metal used in conjunction with roofing to assure compliance of the installed sheet metalwork with the contract requirements. Any work found not to be in compliance with the contract shall be promptly removed and replaced or corrected in an approved manner. Quality control shall include, but not be limited to, the following:

- a. Observation of environmental conditions; number and skill level of sheet metal workers; condition of substrate.
- b. Verification of compliance of materials before, during, and after installation.
- c. Inspection of sheet metalwork for proper size and thickness, fastening and joining, and proper installation.

The actual quality control observations and inspections shall be documented and a copy of the documentation furnished to the Contracting Officer at the end of each day.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL & MOISTURE PROTECTION

SECTION 07840A

FIRESTOPPING

08/00

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL REQUIREMENTS
- 1.4 STORAGE AND DELIVERY
- 1.5 INSTALLER QUALIFICATIONS
- 1.6 COORDINATION

PART 2 PRODUCTS

- 2.1 FIRESTOPPING MATERIALS
 - 2.1.1 Fire Hazard Classification
 - 2.1.2 Toxicity
 - 2.1.3 Fire Resistance Rating
 - 2.1.3.1 Through-Penetrations
 - 2.1.3.2 Construction Joints and Gaps

PART 3 EXECUTION

- 3.1 PREPARATION
- 3.2 INSTALLATION
 - 3.2.1 Insulated Pipes and Ducts
 - 3.2.2 Fire Dampers
- 3.3 INSPECTION

-- End of Section Table of Contents --

UFGS-07840A (August 2000)

SECTION 07840A

FIRESTOPPING
08/00

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM E 84	(1999) Surface Burning Characteristics of Building Materials
ASTM E 119	(1998) Fire Tests of Building Construction and Materials
ASTM E 814	(1997) Fire Tests of Through-Penetration Fire Stops
ASTM E 1399	(1997) Cyclic Movement and Measuring the Minimum and Maximum Joint Widths of Architectural Joint Systems

UNDERWRITERS LABORATORIES (UL)

UL 723	(1996; Rev thru Dec 1998) Test for Surface Burning Characteristics of Building Materials
UL 1479	(1994; Rev thru Feb 1998) Fire Tests of Through-Penetration Firestops
UL 2079	(1998) Tests for Fire Resistance of Building Joint Systems
UL Fire Resist Dir	(1999) Fire Resistance Directory (2 Vol.)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

*1

Firestopping Materials.

Detail drawings including manufacturer's descriptive data, typical details conforming to UL Fire Resist Dir or other details certified by another nationally recognized testing laboratory, installation instructions or UL listing details for a firestopping assembly in lieu of fire-test data or report. For those firestop applications for which no UL tested system is available through a manufacturer, a manufacturer's engineering judgement, derived from similar UL system designs or other tests, shall be submitted for review and approval prior to installation. Submittal shall indicate the firestopping material to be provided for each type of application. When more than 5 penetrations or construction joints are to receive firestopping, drawings shall indicate location and type of application.

SD-07 Certificates

*1

Firestopping Materials.

Certificates attesting that firestopping material complies with the specified requirements. In lieu of certificates, drawings showing UL classified materials as part of a tested assembly may be provided. Drawings showing evidence of testing by an alternate nationally recognized independent laboratory may be substituted.

*1

Installer Qualifications.

Documentation of training and experience.

*1

Inspection.

Manufacturer's representative certification stating that firestopping work has been inspected and found to be applied according to the manufacturer's recommendations and the specified requirements.

1.3 GENERAL REQUIREMENTS

Firestopping shall consist of furnishing and installing tested and listed firestop systems, combination of materials, or devices to form an effective barrier against the spread of flame, smoke and gases, and maintain the integrity of fire resistance rated walls, partitions, floors, and ceiling-floor assemblies, including through-penetrations and construction joints and gaps. Through-penetrations include the annular space around pipes, tubes, conduit, wires, cables and vents. Construction joints include those used to accommodate expansion, contraction, wind, or seismic movement; firestopping material shall not interfere with the required movement of the joint. Gaps requiring firestopping include gaps between the curtain wall and the floor slab and between the top of the fire-rated walls and the roof or floor deck above.

1.4 STORAGE AND DELIVERY

Materials shall be delivered in the original unopened packages or containers showing name of the manufacturer and the brand name. Materials shall be stored off the ground and shall be protected from damage and exposure to elements. Damaged or deteriorated materials shall be removed from the site.

1.5 INSTALLER QUALIFICATIONS

The Contractor shall engage an experienced Installer who is certified, licensed, or otherwise qualified by the firestopping manufacturer as having the necessary staff, training, and a minimum of 3 years experience in the installation of manufacturer's products per specified requirements. A manufacturer's willingness to sell its firestopping products to the Contractor or to an installer engaged by the Contractor does not in itself confer qualification on the buyer. The Installer shall have been trained by a direct representative of the manufacturer (not distributor or agent) in the proper selection and installation procedures.

1.6 COORDINATION

The specified work shall be coordinated with other trades. Firestopping materials, at penetrations of pipes and ducts, shall be applied prior to insulating, unless insulation meets requirements specified for firestopping. Firestopping materials at building joints and construction gaps shall be applied prior to completion of enclosing walls or assemblies. Cast-in-place firestop devices shall be located and installed in place before concrete placement. Pipe, conduit or cable bundles shall be installed through cast-in-place device after concrete placement but before area is concealed or made inaccessible.

PART 2 PRODUCTS

2.1 FIRESTOPPING MATERIALS

Firestopping materials shall consist of commercially manufactured, asbestos-free products complying with the following minimum requirements:

2.1.1 Fire Hazard Classification

Material shall have a flame spread of 25 or less, and a smoke developed rating of 50 or less, when tested in accordance with ASTM E 84 or UL 723. Material shall be an approved firestopping material as listed in UL Fire Resist Dir or by a nationally recognized testing laboratory.

2.1.2 Toxicity

Material shall be nontoxic to humans at all stages of application.

2.1.3 Fire Resistance Rating

Firestopping will not be required to have a greater fire resistance rating than that of the assembly in which it is being placed.

2.1.3.1 Through-Penetrations

Firestopping materials for through-penetrations, as described in paragraph GENERAL REQUIREMENTS, shall provide "F" and "T" fire resistance ratings in accordance with ASTM E 814 or UL 1479. Fire resistance ratings shall be as follows:

- a. Penetrations of Fire Resistance Rated Walls and Partitions: F Rating = Rating of wall or partition being penetrated.
- b. Penetrations of Fire Resistance Rated Floors, Roof-Ceiling Assemblies and Ceiling-Floor Assemblies: F Rating = 1 hour, T

Rating = 1 hour.

2.1.3.2 Construction Joints and Gaps

Fire resistance ratings of construction joints, as described in paragraph GENERAL REQUIREMENTS, and gaps such as those between floor slabs or roof decks and curtain walls shall be the same as the construction in which they occur. Construction joints and gaps shall be provided with firestopping materials and systems that have been tested per ASTM E 119 or UL 2079 to meet the required fire resistance rating. Systems installed at construction joints shall meet the cycling requirements of ASTM E 1399 or UL 2079.

PART 3 EXECUTION

3.1 PREPARATION

Areas to receive firestopping shall be free of dirt, grease, oil, or loose materials which may affect the fitting or fire resistance of the firestopping system. For cast-in-place firestop devices, formwork or metal deck to receive device prior to concrete placement shall be sound and capable of supporting device.

3.2 INSTALLATION

Firestopping material shall completely fill void spaces regardless of geometric configuration, subject to tolerance established by the manufacturer. Firestopping systems for filling floor voids 4 inches or more in any direction shall be capable of supporting the same load as the floor is designed to support or shall be protected by a permanent barrier to prevent loading or traffic in the firestopped area. Firestopping shall be installed in accordance with manufacturer's written instructions. Tested and listed firestop systems shall be provided in the following locations, except in floor slabs on grade:

- a. Penetrations of duct, conduit, tubing, cable and pipe through floors and through fire-resistance rated walls, partitions, and ceiling-floor assemblies.
- b. Penetrations of vertical shafts such as pipe chases, elevator shafts, and utility chutes.
- c. Gaps at the intersection of floor slabs and curtain walls, including inside of hollow curtain walls at the floor slab.
- d. Gaps at perimeter of fire-resistance rated walls and partitions, such as between the top of the walls and the bottom of roof decks.
- e. Construction joints in floors and fire rated walls and partitions.
- f. Other locations where required to maintain fire resistance rating of the construction.

3.2.1 Insulated Pipes and Ducts

Thermal insulation shall be cut and removed where pipes or ducts pass through firestopping, unless insulation meets requirements specified for firestopping. Thermal insulation shall be replaced with a material having equal thermal insulating and firestopping characteristics.

3.2.2 Fire Dampers

Fire dampers shall be installed and firestopped in accordance with Section 15895 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEM.

3.3 INSPECTION

Firestopped areas shall not be covered or enclosed until inspection is complete and approved. A manufacturer's representative shall inspect the applications initially to ensure adequate preparations (clean surfaces suitable for application, etc.) and periodically during the work to assure that the completed work has been accomplished according to the manufacturer's written instructions and the specified requirements.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL & MOISTURE PROTECTION

SECTION 07900A

JOINT SEALING

06/97

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 ENVIRONMENTAL REQUIREMENTS
- 1.4 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 BACKING
 - 2.1.1 Omitted
 - 2.1.2 PVC
 - 2.1.3 Synthetic Rubber
 - 2.1.4 Neoprene
- 2.2 BOND-BREAKER
- 2.3 PRIMER
- 2.4 CAULKING
- 2.5 SEALANT
 - 2.5.1 LATEX
 - 2.5.2 ELASTOMERIC
 - 2.5.3 ACOUSTICAL
 - 2.5.4 BUTYL
 - 2.5.5 PREFORMED
 - 2.5.5.1 Tape
- 2.6 SOLVENTS AND CLEANING AGENTS

PART 3 EXECUTION

- 3.1 GENERAL
 - 3.1.1 Surface Preparation
 - 3.1.2 Concrete and Masonry Surfaces
 - 3.1.3 Steel Surfaces
 - 3.1.4 Aluminum Surfaces
 - 3.1.5 Wood Surfaces
- 3.2 APPLICATION
 - 3.2.1 Masking Tape
 - 3.2.2 Backing
 - 3.2.3 Bond-Breaker
 - 3.2.4 Primer
 - 3.2.5 Sealant
- 3.3 CLEANING
- 3.4 SCHEDULE

-- End of Section Table of Contents --

UFGS-07900A (June 1997)

SECTION 07900A

JOINT SEALING
06/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 509	(1994) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C 570	(1995) Oil- and Resin-Base Caulking Compound for Building Construction
ASTM C 734	(1993) Low-Temperature Flexibility of Latex Sealants After Artificial Weathering
ASTM C 834	(1995) Latex Sealants
ASTM C 920	(1998) Elastomeric Joint Sealants
ASTM C 1085	(1991) Butyl Rubber-Based Solvent-Release Sealants
ASTM D 217	(1997) Cone Penetration of Lubricating Grease (IP50/88)
ASTM D 1056	(1998) Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D 1565	(1999) Flexible Cellular Materials - Vinyl Chloride Polymers and Copolymers (Open-Cell Foam)
ASTM E 84	(1999) Surface Burning Characteristics of Building Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Backing
Bond-Breaker
Sealant

Manufacturer's descriptive data including storage requirements, shelf life, curing time, instructions for mixing and application, and primer data (if required). A copy of the Material Safety Data Sheet shall be provided for each solvent, primer or sealant material.

SD-07 Certificates

Sealant.

Certificates of compliance stating that the materials conform to the specified requirements.

1.3 ENVIRONMENTAL REQUIREMENTS

The ambient temperature shall be within the limits of 40 to 90 degrees F when the sealants are applied.

1.4 DELIVERY AND STORAGE

Materials shall be delivered to the job in the manufacturer's original unopened containers. The container label or accompanying data sheet shall include the following information as applicable: manufacturer, name of material, formula or specification number, lot number, color, date of manufacture, mixing instructions, shelf life, and curing time at the standard conditions for laboratory tests. Materials shall be handled and stored to prevent inclusion of foreign materials. Materials shall be stored at temperatures between 40 and 90 degrees F unless otherwise specified by the manufacturer.

PART 2 PRODUCTS

2.1 BACKING

Backing shall be 25 to 33 percent oversize for closed cell and 40 to 50 percent oversize for open cell material, unless otherwise indicated.

2.1.1 Omitted

2.1.2 PVC

Polyvinyl chloride (PVC) backing shall be ASTM D 1565, Grade VO 12, open-cell foam, round cross section.

2.1.3 Synthetic Rubber

Synthetic rubber backing shall be ASTM C 509, Option I, Type I preformed rods or tubes.

2.1.4 Neoprene

Neoprene backing shall be ASTM D 1056, closed cell expanded neoprene cord Type 2, Class C, Grade 2C2.

2.2 BOND-BREAKER

Bond-breaker shall be as recommended by the sealant manufacturer to prevent adhesion of the sealant to backing or to bottom of the joint.

2.3 PRIMER

Primer shall be non-staining type as recommended by sealant manufacturer for the application.

2.4 CAULKING

Oil- and resin-based caulking shall be ASTM C 570, Type S, Use NT.

2.5 SEALANT

2.5.1 LATEX

Latex Sealant shall be ASTM C 834.

2.5.2 ELASTOMERIC

Elastomeric sealants shall conform to ASTM C 920 and the following:

- a. Polyurethane sealant: Grade NS or P, Class 25, Use T or NT, M, G, A and O.

2.5.3 ACOUSTICAL

Rubber or polymer-based acoustical sealant shall have a flame spread of 25 or less and a smoke developed rating of 50 or less when tested in accordance with ASTM E 84. Acoustical sealant shall have a consistency of 250 to 310 when tested in accordance with ASTM D 217, and shall remain flexible and adhesive after 500 hours of accelerated weathering as specified in ASTM C 734, and shall be non-staining.

2.5.4 BUTYL

Butyl sealant for bedding of thresholds shall be ASTM C 1085.

2.5.5 PREFORMED

Preformed sealant shall be polybutylene or isoprene-butylene based pressure sensitive weather resistant tape or bead sealant capable of sealing out moisture, air and dust when installed as recommended by the manufacturer. At temperatures from minus 30 to plus 160 degrees F, the sealant shall be non-bleeding and shall have no loss of adhesion.

2.5.5.1 Tape

Tape sealant: cross-section dimensions shall be as indicated.

2.6 SOLVENTS AND CLEANING AGENTS

Solvents, cleaning agents, and accessory materials shall be provided as recommended by the manufacturer.

PART 3 EXECUTION

3.1 GENERAL

3.1.1 Surface Preparation

The surfaces of joints to receive sealant or caulk shall be free of all frost, condensation and moisture. Oil, grease, dirt, chalk, particles of mortar, dust, loose rust, loose mill scale, and other foreign substances shall be removed from surfaces of joints to be in contact with the sealant.

Oil and grease shall be removed with solvent and surfaces shall be wiped dry with clean cloths. For surface types not listed below, the sealant manufacturer shall be contacted for specific recommendations.

3.1.2 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil, or other such materials, the materials shall be removed by sandblasting or wire brushing. Laitance, efflorescence and loose mortar shall be removed from the joint cavity.

3.1.3 Steel Surfaces

Steel surfaces to be in contact with sealant shall be sandblasted or, if sandblasting would not be practical or would damage adjacent finish work, the metal shall be scraped and wire brushed to remove loose mill scale. Protective coatings on steel surfaces shall be removed by sandblasting or by a solvent that leaves no residue.

3.1.4 Aluminum Surfaces

Aluminum surfaces to be in contact with sealants shall be cleaned of temporary protective coatings. When masking tape is used for a protective cover, the tape and any residual adhesive shall be removed just prior to applying the sealant. Solvents used to remove protective coating shall be as recommended by the manufacturer of the aluminum work and shall be non-staining.

3.1.5 Wood Surfaces

Wood surfaces to be in contact with sealants shall be free of splinters and sawdust or other loose particles.

3.2 APPLICATION

3.2.1 Masking Tape

Masking tape may be placed on the finish surface on one or both sides of a joint cavity to protect adjacent finish surfaces from primer or sealant smears. Masking tape shall be removed within 10 minutes after joint has been filled and tooled.

3.2.2 Backing

Backing shall be installed to provide the indicated sealant depth. The installation tool shall be shaped to avoid puncturing the backing.

3.2.3 Bond-Breaker

Bond-breaker shall be applied to fully cover the bottom of the joint without contaminating the sides where sealant adhesion is required.

3.2.4 Primer

Primer shall be used on concrete masonry units, wood, or other porous surfaces in accordance with instructions furnished with the sealant. Primer shall be applied to the joint surfaces to be sealed. Surfaces adjacent to joints shall not be primed.

3.2.5 Sealant

Sealant shall be used before expiration of shelf life. Multi-component sealants shall be mixed according to manufacturer's printed instructions. Sealant in guns shall be applied with a nozzle of proper size to fit the width of joint. Joints shall be sealed as detailed in the drawings. Sealant shall be forced into joints with sufficient pressure to expel air and fill the groove solidly. Sealant shall be installed to the indicated depth without displacing the backing. Unless otherwise indicated, specified, or recommended by the manufacturer, the installed sealant shall be dry tooled to produce a uniformly smooth surface free of wrinkles and to ensure full adhesion to the sides of the joint; the use of solvents, soapy water, etc., will not be allowed. Sealants shall be installed free of air pockets, foreign embedded matter, ridges and sags. Sealer shall be applied over the sealant when and as specified by the sealant manufacturer.

3.3 CLEANING

The surfaces adjoining the sealed joints shall be cleaned of smears and other soiling resulting from the sealant application as work progresses.

3.4 SCHEDULE

Type of Sealant	Location
caulking	Glazing in wood doors
Latex Sealant	Interior non-moving joints
Polyurethane Sealant	All interior joints, door and window frames, interior movement joints
Acoustical Sealant	Acoustical ceiling perimeters, elsewhere as indicated
Butyl Sealant	Bedding for metal thresholds
Tape Sealant	Precast concrete joints except as noted otherwise.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - DOORS & WINDOWS

SECTION 08110

STEEL DOORS AND FRAMES

05/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 STANDARD STEEL DOORS
 - 2.1.1 Classification - Level, Performance, Model
 - 2.1.1.1 Omitted
 - 2.1.1.2 Heavy Duty Doors
 - 2.1.1.3 Extra Heavy Duty Doors
 - 2.2 CUSTOM HOLLOW METAL DOORS
 - 2.3 OMITTED
 - 2.4 OMITTED
 - 2.5 ACCESSORIES
 - 2.5.1 Omitted
 - 2.5.2 Omitted
 - 2.5.3 Astragals
 - 2.6 INSULATION CORES
 - 2.7 STANDARD STEEL FRAMES
 - 2.7.1 Welded Frames
 - 2.7.2 Knock-Down Frames
 - 2.7.3 Omitted
 - 2.7.4 Stops and Beads
 - 2.7.5 Omitted
 - 2.7.6 Omitted
 - 2.7.7 Anchors
 - 2.7.7.1 Wall Anchors
 - 2.7.7.2 Floor Anchors
 - 2.8 FIRE DOORS AND FRAMES
 - 2.8.1 Labels
 - 2.8.2 Omitted
 - 2.8.3 Astragal on Fire Doors
 - 2.9 WEATHERSTRIPPING
 - 2.10 HARDWARE PREPARATION
 - 2.11 FINISHES
 - 2.11.1 Factory-Primed Finish
 - 2.11.2 Hot-Dip Zinc-Coated and Factory-Primed Finish
 - 2.11.3 Electrolytic Zinc-Coated Anchors and Accessories
 - 2.12 FABRICATION AND WORKMANSHIP
 - 2.12.1 Grouted Frames

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Frames

- 3.1.2 Doors
- 3.1.3 Fire Doors and Frames
- 3.2 PROTECTION
- 3.3 CLEANING

-- End of Section Table of Contents --

UFGS-08110 (May 2001)

SECTION 08110

STEEL DOORS AND FRAMES

05/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

- ANSI A250.6 (1997) Hardware on Standard Steel Doors
(Reinforcement - Application)
- ANSI A250.8 (1998) SDI-100 Recommended Specifications
for Standard Steel Doors and Frames

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

- ASTM A 591 (1998) Steel Sheet, Electrolytic
Zinc-Coated, for Light Coating Mass
Applications
- ASTM A 653/A 653M (2000) Steel Sheet, Zinc-Coated
(Galvanized) or Zinc-Iron Alloy-Coated
(Galvannealed) by the Hot-Dip Process
- ASTM A 924/A 924M (1999) General Requirements for Steel
Sheet, Metallic-Coated by the Hot-Dip
Process
- ASTM C 578 (1995) Rigid, Cellular Polystyrene Thermal
Insulation
- ASTM C 591 (1994) Unfaced Preformed Rigid Cellular
Polyisocyanurate Thermal Insulation
- ASTM C 612 (1993) Mineral Fiber Block and Board
Thermal Insulation
- ASTM D 2863 (1997) Measuring the Minimum Oxygen
Concentration to Support Candle-Like
Combustion of Plastics (Oxygen Index)

DOOR AND HARDWARE INSTITUTE (DHI)

- DHI A115 (1991) Steel Door Preparation Standards
(Consisting of A115.1 through A115.6 and

A115.12 through A115.18)

HOLLOW METAL MANUFACTURERS ASSOCIATION (HMMA)

HMMA HMM (1992) Hollow Metal Manual

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80 (1999) Fire Doors and Fire Windows

NFPA 252 (1999) Standard Methods of Fire Tests of Door Assemblies

STEEL DOOR INSTITUTE (SDOI)

SDI 105 (1998) Recommended Erection Instructions for Steel Frames

SDI 111-F Recommended Existing Wall Anchors for Standard Steel Doors and Frames

SDI 113 (1979) Apparent Thermal Performance of STEEL DOOR and FRAME ASSEMBLIES

UNDERWRITERS LABORATORIES (UL)

UL 10B (1997) Fire Tests of Door Assemblies

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Doors

Frames

Accessories

Show elevations, construction details, metal gages, hardware provisions, method of glazing, and installation details.

Schedule of doors

Schedule of frames

Submit door and frame locations.

SD-03 Product Data

Doors

Frames; G

Accessories

Submit manufacturer's descriptive literature for doors, frames, and accessories. Include data and details on door construction, panel (internal) reinforcement, insulation, and door edge construction. When "custom hollow metal doors" are provided in lieu of "standard steel doors," provide additional details and data sufficient for comparison to ANSI A250.8 requirements.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver doors, frames, and accessories undamaged and with protective wrappings or packaging. Strap knock-down frames in bundles. Provide temporary steel spreaders securely fastened to the bottom of each welded frame. Store doors and frames on platforms under cover in clean, dry, ventilated, and accessible locations, with 1/4 inch airspace between doors. Remove damp or wet packaging immediately and wipe affected surfaces dry. Replace damaged materials with new.

PART 2 PRODUCTS

2.1 STANDARD STEEL DOORS

ANSI A250.8, except as specified otherwise. Prepare doors to receive hardware specified in Section 08710, "Door Hardware." Exterior doors shall have top edge closed flush and sealed to prevent water intrusion. Doors shall be 1 3/4 inches thick, unless otherwise indicated.

2.1.1 Classification - Level, Performance, Model

2.1.1.1 Omitted

2.1.1.2 Heavy Duty Doors

ANSI A250.8, Level 2, physical performance Level B, Model 2, with core construction as required by the manufacturer for interior doors, of size(s) and design(s) indicated. Where vertical stiffener cores are required, the space between the stiffeners shall be filled with mineral board insulation.

2.1.1.3 Extra Heavy Duty Doors

ANSI A250.8, Level 3, physical performance Level A, Model 2 with core construction as required by the manufacturer for exterior doors, of size(s) and design(s) indicated. Where vertical stiffener cores are required, the space between the stiffeners shall be filled with mineral board insulation.

2.2 CUSTOM HOLLOW METAL DOORS

Provide custom hollow metal doors where nonstandard steel doors are indicated. At the Contractor's option, custom hollow metal doors may be provided in lieu of standard steel doors. Door size(s), design, materials, construction, gages, and finish shall be as specified for standard steel doors and shall comply with the requirement of HMMA HMM. Fill all spaces in doors with insulation. Close top and bottom edges with steel channels not lighter than 16 gage. Close tops of exterior doors flush with an additional channel and seal to prevent water intrusion. Prepare doors to

receive hardware specified in Section 08710, "Door Hardware." Doors shall be 1 3/4 inches thick, unless otherwise indicated.

2.3 OMITTED

2.4 OMITTED

2.5 ACCESSORIES

2.5.1 Omitted

2.5.2 Omitted

2.5.3 Astragals

For pairs of exterior steel doors which will not have aluminum astragals or removable mullions, as specified in Section 08710, "Door Hardware," provide overlapping steel astragals with the doors. For interior pairs of fire rated doors, provide stainless steel astragals complying with NFPA 80 for fire rated assemblies.

2.6 INSULATION CORES

Insulated cores shall be of type specified, and provide an apparent U-factor of .48 in accordance with SDI 113 and shall conform to:

- a. Rigid Polyurethane Foam: ASTM C 591, Type 1 or 2, foamed-in-place or in board form, with oxygen index of not less than 22 percent when tested in accordance with ASTM D 2863; or
- b. Rigid Polystyrene Foam Board: ASTM C 578, Type I or II; or
- c. Mineral board: ASTM C 612, Type I.

2.7 STANDARD STEEL FRAMES

ANSI A250.8, except as otherwise specified. Form frames to sizes and shapes indicated, with welded corners or knock-down field-assembled corners. Provide steel frames for doors and interior glazed panels, unless otherwise indicated.

2.7.1 Welded Frames

Continuously weld frame faces at corner joints. Mechanically interlock or continuously weld stops and rabbets. Grind welds smooth.

2.7.2 Knock-Down Frames

Design corners for simple field assembly by concealed tenons, splice plates, or interlocking joints that produce square, rigid corners and a tight fit and maintain the alignment of adjoining members. Provide locknuts for bolted connections.

2.7.3 Omitted

2.7.4 Stops and Beads

Form stops and beads from 20 gage steel. Provide for glazed and other openings in standard steel frames. Secure beads to frames with oval-head, countersunk Phillips self-tapping sheet metal screws or concealed clips and

fasteners. Space fasteners approximately 12 to 16 inches on centers. Miter molded shapes at corners. Butt or miter square or rectangular beads at corners.

2.7.5 Omitted

2.7.6 Omitted

2.7.7 Anchors

Provide anchors to secure the frame to adjoining construction. Provide steel anchors, zinc-coated or painted with rust-inhibitive paint, not lighter than 18 gage.

2.7.7.1 Wall Anchors

Provide at least four anchors for each exterior jamb and three for each interior jamb. For frames which are more than 7.5 feet in height, provide one additional anchor for each jamb for each additional 2.5 feet or fraction thereof.

- a. Masonry: Provide anchors of 16 gage corrugated or perforated steel straps or 3/16 inch diameter steel wire, adjustable or T-shaped;
- b. Stud partitions: Weld or otherwise securely fasten anchors to backs of frames. Design anchors to be fastened to closed steel studs with sheet metal screws, and to open steel studs by wiring or welding;
- c. Completed openings: Secure frames to previously placed concrete or masonry with expansion bolts in accordance with SDI 111-F; and

2.7.7.2 Floor Anchors

Provide floor anchors drilled for 3/8 inch anchor bolts at bottom of each jamb member. Where floor fill occurs, terminate bottom of frames at the indicated finished floor levels and support by adjustable extension clips resting on and anchored to the structural slabs.

2.8 FIRE DOORS AND FRAMES

NFPA 80 and this specification. The requirements of NFPA 80 shall take precedence over details indicated or specified.

2.8.1 Labels

Fire doors and frames shall bear the label of Underwriters Laboratories (UL), Factory Mutual Engineering and Research (FM), or Warnock Hersey International (WHI) attesting to the rating required. Testing shall be in accordance with NFPA 252 or UL 10B. Labels shall be metal with raised letters, and shall bear the name or file number of the door and frame manufacturer. Labels shall be permanently affixed at the factory to frames and to the hinge edge of the door. Door labels shall not be painted.

2.8.2 Omitted

2.8.3 Astragal on Fire Doors

On pairs of labeled fire doors, conform to NFPA 80 and UL requirements.

2.9 WEATHERSTRIPPING

As specified in Section 08710, "Door Hardware."

2.10 HARDWARE PREPARATION

Provide minimum hardware reinforcing gages as specified in ANSI A250.6. Drill and tap doors and frames to receive finish hardware. Prepare doors and frames for hardware in accordance with the applicable requirements of ANSI A250.8 and ANSI A250.6. For additional requirements refer to DHI A115.

Drill and tap for surface-applied hardware at the project site. Build additional reinforcing for surface-applied hardware into the door at the factory. Locate hardware in accordance with the requirements of ANSI A250.8, as applicable. Punch door frames, with the exception of frames that will have weatherstripping or soundproof gasketing, to receive a minimum of two rubber or vinyl door silencers on lock side of single doors and one silencer for each leaf at heads of double doors. Set lock strikes out to provide clearance for silencers.

2.11 FINISHES

2.11.1 Factory-Primed Finish

All surfaces of doors and frames shall be thoroughly cleaned, chemically treated and factory primed with a rust inhibiting coating as specified in ANSI A250.8. or paintable A25 galvanized steel without primer. Where coating is removed by welding, apply touchup of factory primer.

2.11.2 Hot-Dip Zinc-Coated and Factory-Primed Finish

Fabricate exterior doors and frames from hot dipped zinc coated steel, alloyed type, that complies with ASTM A 924/A 924M and ASTM A 653/A 653M. The Coating weight shall meet or exceed the minimum requirements for coatings having 0.4 ounces per square foot, total both sides, i.e., A40. Repair damaged zinc-coated surfaces by the application of zinc dust paint. Thoroughly clean and chemically treat to insure maximum paint adhesion. Factory prime as specified in ANSI A250.8. Provide for exterior doors.

2.11.3 Electrolytic Zinc-Coated Anchors and Accessories

Provide electrolytically deposited zinc-coated steel in accordance with ASTM A 591, Commercial Quality, Coating Class A. Phosphate treat and factory prime zinc-coated surfaces as specified in ANSI A250.8.

2.12 FABRICATION AND WORKMANSHIP

Finished doors and frames shall be strong and rigid, neat in appearance, and free from defects, waves, scratches, cuts, dents, ridges, holes, warp, and buckle. Molded members shall be clean cut, straight, and true, with joints coped or mitered, well formed, and in true alignment. Dress exposed welded and soldered joints smooth. Design door frame sections for use with the wall construction indicated. Corner joints shall be well formed and in true alignment. Conceal fastenings where practicable.

2.12.1 Grouted Frames

For frames to be installed in exterior walls and to be filled with mortar or grout, fill the stops with strips of rigid insulation to keep the grout

out of the stops and to facilitate installation of stop-applied head and jamb seals.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Frames

Set frames in accordance with SDI 105. Plumb, align, and brace securely until permanent anchors are set. Anchor bottoms of frames with expansion bolts or powder-actuated fasteners. Build in or secure wall anchors to adjoining construction. Where frames require ceiling struts or overhead bracing, anchor frames to the struts or bracing. Backfill frames with mortar. When an additive is provided in the mortar, coat inside of frames with corrosion-inhibiting bituminous material. For frames in exterior walls, ensure that stops are filled with rigid insulation before grout is placed.

3.1.2 Doors

Hang doors in accordance with clearances specified in ANSI A250.8. After erection and glazing, clean and adjust hardware.

3.1.3 Fire Doors and Frames

Install fire doors and frames, including hardware, in accordance with NFPA 80.

3.2 PROTECTION

Protect doors and frames from damage. Repair damaged doors and frames prior to completion and acceptance of the project or replace with new, as directed. Wire brush rusted frames until rust is removed. Clean thoroughly. Apply an all-over coat of rust-inhibitive paint of the same type used for shop coat.

3.3 CLEANING

Upon completion, clean exposed surfaces of doors and frames thoroughly. Remove mastic smears and other unsightly marks.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - DOORS & WINDOWS

SECTION 08210

WOOD DOORS

09/99

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, STORAGE, AND HANDLING
- 1.4 WARRANTY

PART 2 PRODUCTS

- 2.1 DOORS
 - 2.1.1 Omitted
 - 2.1.2 Flush Doors
 - 2.1.2.1 Omitted
 - 2.1.2.2 Interior Flush Doors
 - 2.1.3 Omitted
 - 2.1.4 Omitted
 - 2.1.5 Omitted
 - 2.1.6 Acoustical Doors
 - 2.1.7 Fire Doors
- 2.2 ACCESSORIES
 - 2.2.1 Omitted
 - 2.2.2 Door Light Openings
 - 2.2.3 Omitted
 - 2.2.4 Additional Hardware Reinforcement
- 2.3 FABRICATION
 - 2.3.1 Marking
 - 2.3.2 Quality and Construction
 - 2.3.3 Omitted
 - 2.3.4 Adhesives and Bonds
 - 2.3.5 Prefitting
 - 2.3.6 Finishes
 - 2.3.6.1 Field Painting
- 2.4 SOURCE QUALITY CONTROL

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Fire Doors

-- End of Section Table of Contents --

UFGS-08210 (September 1999)

SECTION 08210

WOOD DOORS

09/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM E 90	(1997) Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E 152	(1981; Rev. A) Fire Tests of Door Assemblies

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80	(1995) Fire Doors and Fire Windows
NFPA 252	(1995) Fire Tests of Door Assemblies

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)

NWWDA I.S. 1-A	(1993) Architectural Wood Flush Doors
NWWDA TM-5	(1990) Split Resistance Test
NWWDA TM-7	(1990) Cycle - Slam Test
NWWDA TM-8	(1990) Hinge Loading Resistance Test

UNDERWRITERS LABORATORIES (UL)

UL 10B	(1997) Fire Tests of Door Assemblies
--------	--------------------------------------

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

SD-02 Shop Drawings

Doors

Submit drawings or catalog data showing each type of door unit. Drawings and data shall indicate door type and construction, sizes, thickness, methods of assembly, and glazing,.

SD-03 Product Data

Doors

Accessories

Sample warranty

Sound transmission class rating

Fire resistance rating

SD-06 Test Reports

Split resistance

Cycle-slam

Hinge loading resistance

Submit split resistance test report for doors tested in accordance with NWWDA TM-5, cycle-slam test report for doors tested in accordance with NWWDA TM-7, and hinge loading resistance test report for doors tested in accordance with NWWDA TM-8.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver doors to the site in an undamaged condition and protect against damage and dampness. Stack doors flat under cover. Support on blocking, a minimum of 4 inches thick, located at each end and at the midpoint of the door. Store doors in a well-ventilated building so that they will not be exposed to excessive moisture, heat, dryness, direct sunlight, or extreme changes of temperature and humidity. Do not store in a building under construction until concrete, masonry work, and plaster are dry. Replace defective or damaged doors with new ones.

1.4 WARRANTY

Warranty shall warrant doors free of defects as set forth in the door manufacturer's standard door warranty.

PART 2 PRODUCTS

2.1 DOORS

Provide doors of the types, sizes, and designs indicated.

2.1.1 Omitted

2.1.2 Flush Doors

Flush doors shall conform to NWWDA I.S. 1-A. Stile edge bands of doors to receive natural finish shall be hardwood, compatible with face veneer. No visible finger joints will be accepted in stile edge bands. When used, locate finger-joints under hardware.

2.1.2.1 Omitted

2.1.2.2 Interior Flush Doors

Provide staved lumber or particleboard core, Type II flush doors conforming to NWWDA I.S. 1-A with faces of premium grade red oak. Hardwood veneers shall be plain sliced or quarter sliced.

2.1.3 Omitted

2.1.4 Omitted

2.1.5 Omitted

2.1.6 Acoustical Doors

NWWDA I.S. 1-A, solid core, constructed to provide Sound Transmission Class rating of 45 when tested in accordance with ASTM E 90.

2.1.7 Fire Doors

Doors specified or indicated to have a fire resistance rating shall conform to the requirements of UL 10B, ASTM E 152, or NFPA 252 for the class of door indicated. Affix a permanent metal label with raised or incised markings indicating testing agency's name and approved hourly fire rating to hinge edge of each door.

2.2 ACCESSORIES

2.2.1 Omitted

2.2.2 Door Light Openings

Provide glazed openings with the manufacturer's standard wood moldings except that moldings for doors to receive natural finish shall be of the same specie and color as the face veneers. Moldings on exterior doors shall have sloped surfaces. Moldings for flush doors shall be lip type. Provide glazed openings in fire-rated doors with fire rated frames. Glazing is specified in Section 08810A GLASS AND GLAZING.

2.2.3 Omitted

2.2.4 Additional Hardware Reinforcement

Provide fire rated doors with hardware reinforcement blocking. Size of lock blocks shall be as required to secure the hardware specified. Reinforcement blocking shall be in compliance with the manufacturer's labeling requirements and shall not be mineral material similar to the core.

2.3 FABRICATION

2.3.1 Marking

Each door shall bear a stamp, brand, or other identifying mark indicating quality and construction of the door.

2.3.2 Quality and Construction

Identify the standard on which the construction of the door was based, identify the standard under which preservative treatment was made, and identify doors having a Type I glue bond.

2.3.3 Omitted

2.3.4 Adhesives and Bonds

NWWDA I.S. 1-A. Use Type II bond for interior doors. Adhesive for doors to receive a natural finish shall be nonstaining.

2.3.5 Prefitting

At the Contractor's option, doors may be provided factory pre-fit. Doors shall be sized and machined at the factory by the door manufacturer in accordance with the standards under which they are produced. The work shall include sizing, bevelling edges, mortising, and drilling for hardware and providing necessary beaded openings for glass and louvers. Provide the door manufacturer with the necessary hardware samples, and frame and hardware schedules as required to coordinate the work.

2.3.6 Finishes

2.3.6.1 Field Painting

Factory seal doors, and field paint as specified in Section 09900, "Paints and Coatings."

2.4 SOURCE QUALITY CONTROL

Stiles of "B" and "C" label fire doors utilizing standard mortise leaf hinges shall meet the following performance criteria:

- a. Split resistance: Average of ten test samples shall be not less than 500 pounds load when tested in accordance with NWWDA TM-5.
- b. Cycle-slam: 200,000 cycles with no loose hinge screws or other visible signs of failure when tested in accordance with the requirements of NWWDA TM-7.
- c. Hinge loading resistance: Average of ten test samples shall be not less than 700 pounds load when tested for direct screw withdrawal in accordance with NWWDA TM-8 using a No. 12, 1 1/4 inch long, steel, fully threaded wood screw. Drill 5/32 inch pilot hole, use 1 1/2 inch opening around screw for bearing surface, and engage screw full, except for last 1/8 inch. Do not use a steel plate to reinforce screw area.

PART 3 EXECUTION

3.1 INSTALLATION

Before installation, seal top and bottom edges of doors with the approved water-resistant sealer. Seal cuts made on the job immediately after cutting using approved water-resistant sealer. Fit, trim, and hang doors with a 1/16 inch minimum, 1/8 inch maximum clearance at sides and top, and a 3/16 inch minimum, 1/4 inch maximum clearance over thresholds. Provide 3/8 inch minimum, 7/16 inch maximum clearance at bottom where no threshold occurs. Bevel edges of doors at the rate of 1/8 inch in 2 inches. Door warp shall not exceed 1/4 inch when measured in accordance with NWWDA I.S. 1-A.

3.1.1 Fire Doors

Install fire doors in accordance with NFPA 80. Do not paint over labels.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - DOORS & WINDOWS

SECTION 08520A

ALUMINUM AND ENVIRONMENTAL CONTROL ALUMINUM WINDOWS

03/00

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 WINDOW PERFORMANCE
 - 1.2.1 Structural Performance
 - 1.2.2 Air Infiltration
 - 1.2.3 Water Penetration
 - 1.2.4 Thermal Performance
 - 1.2.5 Condensation Index Rating
- 1.3 SUBMITTALS
- 1.4 QUALIFICATION
- 1.5 OMITTED
- 1.6 DELIVERY AND STORAGE
- 1.7 WARRANTY

PART 2 PRODUCTS

- 2.1 ALUMINUM WINDOW TYPES
 - 2.1.1 Awning/Hopper/Projected Windows
 - 2.1.2 Omitted
 - 2.1.3 Omitted
 - 2.1.4 Fixed Windows
- 2.2 WEATHERSTRIPPING
- 2.3 INSECT SCREENS
- 2.4 ACCESSORIES
 - 2.4.1 Fasteners
 - 2.4.2 Hardware
 - 2.4.3 Window Anchors
- 2.5 GLASS AND GLAZING
- 2.6 FINISH
 - 2.6.1 Anodized Aluminum Finish
 - 2.6.2 Omitted
 - 2.6.3 High-Performance Coating
 - 2.6.4 Color

PART 3 EXECUTION

- 3.1 INSTALLATION
- 3.2 ADJUSTMENTS AND CLEANING
 - 3.2.1 Hardware Adjustments
 - 3.2.2 Cleaning

-- End of Section Table of Contents --

UFGS-08520A (March 2000)

SECTION 08520A

ALUMINUM AND ENVIRONMENTAL CONTROL ALUMINUM WINDOWS

03/00

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF-45 (1997) Designation System for Aluminum Finishes

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 101 (1997) Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors

AAMA 605 (1998) voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3656 (1997) Insect Screening and Louver Cloth Woven from Vinyl-Coated Glass Yarns

ASTM E 283 (1991) Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

ASTM E 330 (1997e1) Structural Performance of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference

ASTM E 547 (1996) Water Penetration of Exterior Windows, Curtain Walls, and Doors by Cyclic Static Air Pressure Differential

NATIONAL FENESTRATION RATING COUNCIL (NFRC)

NFRC 100 (1997) Procedure for Determining Fenestration Product U-factors

NFRC 200 (1997) Procedure for Determining Fenestration Product Solar Heat Gain Coefficients at Normal Incidence

SCREEN MANUFACTURERS ASSOCIATION (SMA)

SMA 1004 (1987) Aluminum Tubular Frame Screens for Windows

1.2 WINDOW PERFORMANCE

Aluminum windows shall meet the following performance requirements. Testing requirements shall be performed by an independent testing laboratory or agency.

1.2.1 Structural Performance

Structural test pressures on window units shall be for positive load (inward) and negative load (outward) in accordance with ASTM E 330. After testing, there shall be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms or any other damage which could cause window to be inoperable. There shall be no permanent deformation of any main frame, sash or ventilator member in excess of the requirements established by AAMA 101 for the window types and classification specified in this section.

1.2.2 Air Infiltration

Air infiltration shall not exceed the amount established by AAMA 101 for each window type when tested in accordance with ASTM E 283.

1.2.3 Water Penetration

Water penetration shall not exceed the amount established by AAMA 101 for each window type when tested in accordance with ASTM E 547.

1.2.4 Thermal Performance

Thermal transmittance for thermally broken aluminum windows with insulating glass shall not exceed a U-factor of 0.75 Btu/hr-ft²-F determined according to NFRC 100, and a solar heat gain coefficient (SHGC) of 0.40 Btu/hr-ft²-F determined according to NFRC 200. Window units shall comply with the U.S. Department of Energy, Energy Star Window Program for the Southern Climate Zone...

1.2.5 Condensation Index Rating

The condensation index rating shall be 85 as determined using NFRC approved software THERM.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Aluminum Windows
Insect Screens

Drawings indicating elevations of window, rough-opening dimensions for each type and size of window, full-size sections, thicknesses of metal, fastenings, methods of installation and anchorage, connections with other work, type of wall construction, size and spacing of anchors, method of glazing, types and locations of operating hardware, mullion details, weatherstripping details, screen details including method of attachment,, and window schedules showing locations of each window type.

SD-03 Product Data

Aluminum Windows

Manufacturer's descriptive data and catalog cut sheets.

Manufacturer's preprinted installation instructions and cleaning instructions.

SD-06 Test Reports

Aluminum Windows

Reports for each type of aluminum window attesting that identical windows have been tested and meet all performance requirements established under paragraph WINDOW PERFORMANCE.

SD-07 Certificates

Aluminum Windows

Certificates stating that the aluminum windows are AAMA certified conforming to requirements of this section. Labels or markings permanently affixed to the window will be accepted in lieu of certificates. Product ratings determined using NFRC 100 and NFRC 200 shall be authorized for certification and properly labeled by the manufacturer.

1.4 QUALIFICATION

Window manufacturer shall specialize in designing and manufacturing the type of aluminum windows specified in this section, and shall have a minimum of three years of documented successful experience. Manufacturer shall have the facilities capable of meeting contract requirements, single-source responsibility and warranty.

1.5 OMITTED

1.6 DELIVERY AND STORAGE

Aluminum windows shall be delivered to project site and stored in accordance with manufacturer's recommendations. Damaged windows shall be replaced with new windows.

1.7 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period shall be provided.

PART 2 PRODUCTS

2.1 ALUMINUM WINDOW TYPES

Aluminum windows shall consist of complete units including sash, glass, frame, weatherstripping, special anchors for resistance to blast loading, and hardware. Windows shall conform to AAMA 101. Windows shall be double-glazed. Operable windows shall permit cleaning the outside glass from inside the building.

2.1.1 Awning/Hopper/Projected Windows

Aluminum awning (A), hopper and projected windows shall conform to AAMA 101 Designation PA-AW145 type consisting of hinged ventilators arranged in a single or vertical series within a common frame. Ventilators shall be operated by a device which shall securely close the ventilator at both jambs without the use of additional manually-controlled locking device equipped with concealed four-bar friction hinges. Operating hardware, except ventilator arms and rotary operators, shall be concealed within frame and sill. Ventilator arms shall be concealed when windows are closed. Minimum "bite" for glazing shall be 1 inch.

2.1.2 Omitted

2.1.3 Omitted

2.1.4 Fixed Windows

Aluminum fixed (F) windows shall conform to AAMA 101 F-AW145 type, non-operable glazed frame, complete with provisions for reglazing in the field. Minimum "bite" for glazing shall be 1 inch.

2.2 WEATHERSTRIPPING

Weatherstripping for ventilating sections shall be of type designed to meet water penetration and air infiltration requirements specified in this section in accordance with AAMA 101, and shall be manufactured of material compatible with aluminum and resistant to weather. Weatherstrips shall be factory-applied and easily replaced in the field. Neoprene or polyvinylchloride weatherstripping are not acceptable where exposed to direct sunlight.

2.3 INSECT SCREENS

Insect screens shall be aluminum window manufacturer's standard design, and shall be provided where scheduled on drawings. Insect screens shall be fabricated of extruded tubular-shaped aluminum frames conforming to SMA 1004 and (18 x 16) vinyl coated glass screening conforming to ASTM D 3656.

2.4 ACCESSORIES

2.4.1 Fasteners

Fastening devices shall be window manufacturer's standard design made from

aluminum, magnetic stainless steel, cadmium-plated steel, nickel/chrome-plated steel in compliance with AAMA 101. Self-tapping sheet metal screws will not be acceptable for material thicker than 1/16 inch.

2.4.2 Hardware

Hardware shall be as specified for each window type and shall be fabricated of aluminum, stainless steel, cadmium-plated steel, zinc-plated steel or nickel/chrome-plated steel in accordance with requirements established by AAMA 101.

2.4.3 Window Anchors

Anchoring devices for installing windows shall be made of aluminum, cadmium-plated steel, stainless steel, or zinc-plated steel conforming to AAMA 101.

2.5 GLASS AND GLAZING

Aluminum windows shall be designed for inside glazing, field glazing, and for glass types scheduled on drawings and specified in Section 08810A GLASS AND GLAZING. Units shall be complete with glass and glazing provisions to meet AAMA 101. Glazing material shall be compatible with aluminum, and shall not require painting.

2.6 FINISH

2.6.1 Anodized Aluminum Finish

Exposed surfaces of aluminum windows shall be finished with anodic coating conforming to AA DAF-45: Architectural Class I, AA-M10-C22-A44, color anodic coating, 0.7 mil or thicker. Finish shall be free of scratches and other blemishes.

2.6.2 Omitted

2.6.3 High-Performance Coating

Exposed surfaces of aluminum windows shall be finished with a two-coat fluoropolymer coating system containing at least 70 percent by weight polyvinylidene fluoride, PVF2 resin, factory-applied, oven-baked, conforming to AAMA 605, with a primer coat of 0.20 to 0.30 mils and a color coat of minimum 1.0 mil, total dry film thickness of 1.20 to 1.3 mils. Finish shall be free of scratches and other blemishes.

2.6.4 Color

Color shall be as indicated on the drawings.

PART 3 EXECUTION

3.1 INSTALLATION

Aluminum windows shall be installed in accordance with approved shop drawings and manufacturer's published instructions. Aluminum surfaces in contact with masonry, concrete, wood and dissimilar metals other than stainless steel, zinc, cadmium or small areas of white bronze, shall be protected from direct contact using protective materials recommended by AAMA 101. The completed window installation shall be watertight in

accordance with Section 07900A JOINT SEALING. Glass and glazing shall be installed in accordance with requirements of this section and Section 08810A GLASS AND GLAZING.

3.2 ADJUSTMENTS AND CLEANING

3.2.1 Hardware Adjustments

Final operating adjustments shall be made after glazing work is complete. Operating sash or ventilators shall operate smoothly and shall be weathertight when in locked position.

3.2.2 Cleaning

Aluminum window finish and glass shall be cleaned on exterior and interior sides in accordance with window manufacturer's recommendations. Alkaline or abrasive agents shall not be used. Precautions shall be taken to avoid scratching or marring window finish and glass surfaces.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - DOORS & WINDOWS

SECTION 08633

FIBERGLASS-SANDWICH-PANEL SYSTEMS

04/02

PART # GENERAL

- 1.1 REFERENCES
- 1.2 PERFORMANCE REQUIREMENTS
 - 1.2.1 Supporting-Frame-Member Deflection Limits
 - 1.2.2 Structural Loads
 - 1.2.3 Thermal Movement
 - 1.2.3.1 Temperature Change (Range)
 - 1.2.4 Air Infiltration
 - 1.2.5 Water Penetration
- 1.3 SUBMITTALS
- 1.4 QUALITY ASSURANCE
 - 1.4.1 Installer Qualifications
 - 1.4.1.1 Engineering Responsibility
 - 1.4.2 Professional Engineer Qualifications
 - 1.4.3 Testing Agency Qualifications
 - 1.4.4 Product Options
 - 1.4.5 Sandwich-Panel Fire-Test-Response Characteristics
 - 1.4.6 Mockups
- 1.5 PROJECT CONDITIONS
 - 1.5.1 Field Measurements
 - 1.5.1.1 Established Dimensions
- 1.6 WARRANTY
 - 1.6.1 General Warranty

PART 2 PRODUCTS

- 2.1 MATERIALS AND PRODUCTS
 - 2.1.1 Aluminum
 - 2.1.1.1 Sheet and Plate
 - 2.1.1.2 Bars, Rods, and Wire
 - 2.1.2 Battens, Brackets, and Reinforcements
 - 2.1.3 Exposed Flashing and Closures
 - 2.1.4 Fasteners and Accessories
 - 2.1.5 Panel System Gaskets and Joint Fillers
 - 2.1.6 Panel System Sealants
 - 2.1.7 Bituminous Paint
 - 2.1.8 Thermal Insulation
 - 2.1.9 Fiberglass Sandwich Panels
 - 2.1.9.1 Erosion Protection
 - 2.1.9.2 U-Value
 - 2.1.9.3 Grid Core
 - 2.1.9.4 Grid Pattern
 - 2.1.9.5 Adhesive
 - 2.1.9.6 Impact Resistance
 - 2.1.9.7 Color Stability
 - 2.1.9.8 Color
- 2.2 FABRICATION

- 2.2.1 Aluminum Components
- 2.2.2 Flashing
- 2.2.3 Preparation
- 2.2.3 Fiberglass-Sandwich-Panel Fabrication
- 2.3 ALUMINUM FINISHES
 - 2.3.1 Class I, Clear Anodic Finish

PART 3 EXECUTION

- 3.1 PREPARATION
 - 3.1.1 Metal Protection
- 3.2 INSTALLATION
 - 3.2.1 Erection Tolerances
 - 3.2.2 Sealants
- 3.3 FIELD QUALITY CONTROL
 - 3.3.1 Water-Spray Test
 - 3.3.2 Correction
- 3.4 CLEANING

-- End of Section Table of Contents --

SECTION 08633

FIBERGLASS-SANDWICH-PANEL SYSTEMS
04/02

PART # GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 501.2 (1994) Field Check of Metal Storefronts, Curtain Walls, and Sloped Glazing Systems for Water Leakage

ASTM INTERNATIONAL (ASTM)

ASTM A 123 (1989a) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A 193/A 193M (1996b) Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service

ASTM A 307 (1994) Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength

ASTM B 209 (1995) Aluminum and Aluminum-Alloy Sheet and Plate

ASTM B 211 (1992a) Aluminum and Aluminum-Alloy Bar, Rod, and Wire

ASTM B 221 (1992a) Aluminum-Alloy Extruded Bars, Rods, Wire, Shapes, and Tubes

ASTM C 297 (1994) Flatwise Tensile Strength of Sandwich Constructions

ASTM D 635 (1998) Rate of Burning and/or Extent and Time of Burning of Self-Supporting Plastics in a Horizontal Position

ASTM D 1037 (1999) Evaluating Properties of Wood-Base Fiber and Particle Panel Materials

ASTM D 1183 (1996e1) Resistance of Adhesives to Cyclic Laboratory Aging Conditions

ASTM D 1929 (1996; R 2001) Determining Ignition Temperature of Plastics

ASTM D 2244	(1995) Calculation of Color Differences from Instrumentally Measured Color Coordinates
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials
ASTM E 283	(1991) Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E 331	(1996) Water Penetration of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference
ASTM E 548	(1994e1) Guide for General Criteria Used for Evaluating Laboratory Competence

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS
(NAAMM)

NAAMM AMP 500	8) Metal Finishes Manual for Architectural and Metal Products
---------------	---

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC-Paint 12	(1991) Cold-Applied Asphalt Mastic (Extra Thick Film)
---------------	---

1.2 PERFORMANCE REQUIREMENTS

Provide panel systems capable of withstanding loads and thermal and structural movements indicated without failure.

Failure includes the following:

1. Supporting-frame deflection exceeding specified limits.
2. Sandwich-panel deflection exceeding manufacturer's recommended limits or causing panel failure.
3. Thermal stresses transferred to the building structure.
4. Noise or vibration created by thermal and structural movement and wind.
5. Loosening or weakening of fasteners, attachments, and other components.
6. Sealant failure.

1.2.1 Supporting-Frame-Member Deflection Limits

As follows:

1. Deflection of the entire length of framing members in direction normal to panel system plane is limited to <Insert limit; e.g., 1/180>, unless otherwise indicated.
2. Deflection of the entire length of framing members for spans exceeding 6 m is limited to 1/240 of clear span.

1.2.2 Structural Loads

Provide panel systems, including anchorage, capable of withstanding the effects of the following design loads when supporting full dead loads:

1. Wind Loads: As indicated
2. Seismic Loads: As indicated.

1.2.3 Thermal Movement

Provide panel systems that allow for thermal movement resulting from the following maximum change (range) in ambient and surface temperatures by preventing buckling, sealant failure, and other detrimental effects.

1.2.3.1 Temperature Change (Range)

120 deg F ambient, 180 deg F material surfaces.

1.2.4 Air Infiltration

Provide panel systems with maximum air leakage of 0.03 L/s per sq. m of surface when tested according to ASTM E 283 at a minimum static-air-pressure differential of 75.2 Pa.

1.2.5 Water Penetration

Provide panel systems that do not evidence water penetration when tested according to ASTM E 331 at a minimum static pressure differential of 20 percent of positive design wind load, but not less than 299 Pa.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Panel Systems; G, AE.

Show plans, elevations, sections, details, and attachments to other Work. Include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

SD-03 Product Data

Panel Systems

Manufacturer's descriptive data and catalog cuts including air-infiltration data. Include construction details, material descriptions, dimensions, profiles, and finishes of panel system components.

Installation

Cleaning

Manufacturer's installation instructions and cleaning instructions.

SD-04 Samples

Finishes

For each exposed finish required, in same thickness and material indicated for the Work and in size indicated below. If finishes involve normal color variations, include sample sets consisting of two or more units showing the full range of variations expected.

1. Factory-Finished Aluminum: 12-inch-long sections.
2. Fiberglass Sandwich Panels: 12-inch-square units.

Cutaway Sample

Cutaway Sample: Of framing intersection, made from 300-mm- long lengths of full-size components and showing details of primary framing members, joinery, expansion provisions, fiberglass sandwich panels, and methods of drainage.

SD-06 Test Reports

Panel Systems

Certified test reports from an independent testing laboratory, stating that panel system assemblies are identical in design, materials, and construction to assemblies that have been tested and meets all test and specified requirements.

1.4 QUALITY ASSURANCE

1.4.1 Installer Qualifications

An experienced installer to assume engineering responsibility who has specialized in installing panel systems similar to those indicated for this Project and who is acceptable to manufacturer.

1.4.1.1 Engineering Responsibility

Preparation of Shop Drawings and comprehensive engineering analysis by a qualified professional engineer.

1.4.2 Professional Engineer Qualifications

A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of panel systems that are similar to those indicated for this Project in material, design, and extent.

1.4.3 Testing Agency Qualifications

An independent testing agency with the experience and capability to conduct the testing indicated, as documented according to ASTM E 548.

1.4.4 Product Options

Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of panel systems. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction. Performance characteristics are indicated by criteria subject to verification by one or more methods including testing or in-service performance.

1.4.5 Sandwich-Panel Fire-Test-Response Characteristics

Provide fiberglass sandwich panels identical to those tested for the following fire-test-response characteristics per test method indicated below by an independent testing and inspecting agency acceptable to Contracting Officer.

1. Plastic Self-Ignition Temperature: 650 deg F or more when tested per ASTM D 1929.
2. Interior-Face Burning Extent: 1 inch or less per ASTM D 635.
3. Interior-Face Surface Burning: Flame-spread and smoke-developed ratings of not more than 25 and 450, respectively, per ASTM E 84.

1.4.6 Mockups

Before installing panel systems, build mockups for each form of construction and finish required to verify selections made under sample Submittals and to demonstrate aesthetic effects and qualities of materials and execution. Build mockups to comply with the following requirements, using materials indicated for the completed Work:

1. Build mockups in the location and of the size indicated or, if not indicated, as directed by Contracting Officer.
2. Notify Contracting Officer seven days in advance of dates and times when mockups will be constructed.
3. Demonstrate the proposed range of aesthetic effects and workmanship.
4. Obtain Contracting Officer's's approval of mockups before starting fabrication.
5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
6. Demolish and remove mockups when directed.
7. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.5 PROJECT CONDITIONS

1.5.1 Field Measurements

Where panel systems are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1.5.1.1 Established Dimensions

Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating panel systems without field measurements. Coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.6 WARRANTY

1.6.1 General Warranty

Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

B. Special Warranty: Written warranty, executed by manufacturer agreeing to repair or replace components of panel systems that fail in materials or workmanship within specified warranty period. Failures include, but are not limited to, the following:

1. Structural failures.
2. Deterioration of metals, metal finishes, fiberglass sandwich panels, and other materials beyond normal weathering.
3. Water leakage, defined as uncontrolled water appearing on normally exposed interior surfaces of panel systems from sources other than condensation. Water controlled by flashing and gutters and drained back to the exterior and that cannot damage adjacent materials or finishes is not water leakage.
4. Warranty Period: Five years from date of Substantial Completion.

PART 2 PRODUCTS

2.1 MATERIALS AND PRODUCTS

2.1.1 Aluminum

Alloy and temper recommended by manufacturer for use and finish indicated, and as follows: 1. Extrusions: ASTM B 221.

2.1.1.1 Sheet and Plate

ASTM B 209.

2.1.1.2 Bars, Rods, and Wire

ASTM B 211.

2.1.2 Battens, Brackets, and Reinforcements

Manufacturer's standard high-strength aluminum units.

2.1.3 Exposed Flashing and Closures

Aluminum sheet, minimum 0.059 inch thick.

2.1.4 Fasteners and Accessories

Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories; compatible with adjacent materials.

1. Movement Joints: Provide slip-joint linings, spacers, and sleeves of material and type recommended by manufacturer.

2. Aluminum-Retaining-Cap or Batten Fasteners: ASTM A 193/A 193M, Series 300 stainless-steel screws; type as recommended by manufacturer.
3. Connections to Supporting Structure: ASTM A 307, zinc-coated steel fasteners.
4. Anchor Bolts: ASTM A 307, Grade A, zinc-coated steel anchor bolts.
5. Concrete or Masonry Inserts: Zinc-coated cast-iron, malleable-iron, or steel inserts; hot-dip galvanized according to ASTM A 123.
6. Shims: Nonstaining, nonferrous shims compatible with adjacent materials, for installing and aligning panel system.

2.1.5 Panel System Gaskets and Joint Fillers

Manufacturer's standard permanent gaskets and joint fillers for sliding, compression, and nonmoving joints.

2.1.6 Panel System Sealants

Compatible with components with which sealants come in contact and recommended by panel system and sealant manufacturers for this use.

2.1.7 Bituminous Paint

Cold-applied asphalt mastic paint complying with SSPC-Paint 12, except containing no asbestos, and formulated for .031 inch thickness per coat.

2.1.8 Thermal Insulation

Manufacturer's standard glass fiber batt, as required to achieve the specified thermal performance.

2.1.9 Fiberglass Sandwich Panels

70 mm thick with uniformly colored, translucent, fiberglass-reinforced-polymer face sheets permanently attached to a grid core using adhesive.

2.1.9.1 Erosion Protection

Manufacturer's standard.

2.1.9.2 U-Value

1.647

2.1.9.3 Grid Core

Aluminum I-beams complying with ASTM B 221 and in alloy and temper recommended by manufacturer.

2.1.9.4 Grid Pattern

As indicated.

2.1.9.5 Adhesive

Waterproof, heat-and-pressure-resin type with tensile bond strength 755 psi

when tested according to ASTM C 297 after aging according to ASTM D 1037, and shear bond strength of 700 psi when tested according to ASTM D 1002 after aging according to ASTM D 1183.

2.1.9.6 Impact Resistance

No failure at impact of 221 foot-pounds according to free-falling ball impact test using a 3-1/2 inch diameter, 6.4 pound ball.

2.1.9.7 Color Stability

Not more than 3.0 units Delta E after 60 months when tested according to ASTM D 2244.

2.1.9.8 Color

As indicated.

2.2 FABRICATION

2.2.1 Aluminum Components

Fabricate components that, when assembled, will have accurately fitted joints with ends coped, mitered, or butted to produce hairline joints free of burrs and distortion. Fabricate components to drain water passing joints and to drain condensation and moisture occurring or migrating within panel system to the exterior. Fabricate components to accommodate expansion, contraction, and field adjustment and to provide for minimum clearance and shimming at panel system perimeter. Form shapes with sharp profiles, straight and free of defects or deformations, before finishing. Fit and assemble components to greatest extent practicable before finishing. Reinforce members as required to retain fastener threads. Where fasteners are exposed to view from interior, countersink fastener heads and finish them to match framing. Before shipping, shop assemble, mark, and disassemble components that cannot be permanently shop assembled.

2.2.2 Flashing

Fabricate flashing with weatherproof expansion joints and corners.

2.2.3 Preparation

Prepare framing to receive anchor and connection devices and fasteners.

2.2.3 Fiberglass-Sandwich-Panel Fabrication

Laminate face sheets to grid core under a controlled heat-and-pressure process with straight adhesive bonding lines that cover the width of core members and that have sharp edges. White spots indicating lack of bond at intersections of grid core members are limited in number to 4 for every 36 sq. ft of panel and limited in diameter to 1/2 inch. Fabricate with grid pattern that is symmetrical about centerlines of each panel. Fabricate panel to allow condensation within the panel to escape. Reinforce panel corners.

2.3 ALUMINUM FINISHES

Comply with NAAMM AMP 500 for recommendations for applying and designating

finishes.

Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.

2.3.1 Class I, Clear Anodic Finish

AA-M10C22A41 (Mechanical Finish: as fabricated; Chemical Finish: etched, medium matte; Anodic Coating: Architectural Class I, clear coating 7 mils or thicker) complying with AAMA 607.1.

PART 3 EXECUTION

3.1 PREPARATION

Furnish anchor bolts and inserts for setting in concrete formwork or masonry indicated to support panel systems.

3.1.1 Metal Protection

Where aluminum will contact dissimilar metals, protect against galvanic action by painting contact surfaces with primer or by applying sealant or tape recommended by manufacturer for this purpose. Where aluminum will contact concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint. Where aluminum will contact pressure-treated wood, separate dissimilar materials by methods recommended by manufacturer.

3.2 INSTALLATION

Comply with manufacturer's written instructions for protecting, handling, and installing panel system components. Fit aluminum component joints to produce hairline joints free of burrs and distortion. Rigidly secure nonmovement joints. Accommodate thermal and mechanical movements. Install framing components to drain water passing joints and to drain condensation and moisture occurring or migrating within panel system system to the exterior. Coordinate installation of insulation and flashings at panel system perimeters to maintain continuity of thermal and water barriers. Set continuous flashings in a full sealant bed, unless otherwise indicated.

3.2.1 Erection Tolerances

Install panel system components true in plane, accurately aligned, and without warp or rack. Adjust to comply with the following tolerances:

1. Variation from Plane: Limit variation from plane or location shown to 1/8 inch in 10 feet; 1/4 inch over total length.
2. Alignment: Where surfaces abut in line and at corners and where surfaces are separated by less than 3 inches, limit offset from true alignment to less than 1/32 inch; otherwise, limit offset from true alignment to 1/8 inch.

3.2.2 Sealants

Install sealants according to sealant manufacturer's written instructions to provide weatherproof joints. Install joint fillers behind sealant as recommended by sealant manufacturer.

3.3 FIELD QUALITY CONTROL

3.3.1 Water-Spray Test

Test panel systems according to procedures in AAMA 501.2.

3.3.2 Correction

Repair or replace Work that does not pass testing or that is damaged by testing; and retest Work.

3.4 CLEANING

Clean panel systems inside and outside, immediately after installation, according to manufacturer's written recommendations. Remove temporary protective coverings and strippable coatings from factory-finished metal surfaces and fiberglass sandwich panels. Remove labels and markings from all components.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - DOORS & WINDOWS

SECTION 08710

DOOR HARDWARE

02/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 HARDWARE SCHEDULE
- 1.4 KEY BITTING CHART REQUIREMENTS
- 1.5 QUALITY ASSURANCE
 - 1.5.1 Hardware Manufacturers and Modifications
- 1.6 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 TEMPLATE HARDWARE
- 2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS
- 2.3 HARDWARE ITEMS
 - 2.3.1 Hinges
 - 2.3.2 Locks and Latches
 - 2.3.2.1 Mortise Locks and Latches
 - 2.3.3 Exit Devices
 - 2.3.4 Cylinders and Cores
 - 2.3.5 Keying System
 - 2.3.6 Lock Trim
 - 2.3.6.1 Knobs and Roses
 - 2.3.6.2 Lever Handles
 - 2.3.6.3 Texture
 - 2.3.7 Keys
 - 2.3.8 Door Bolts
 - 2.3.9 Closers
 - 2.3.9.1 Identification Marking
 - 2.3.10 Overhead Holders
 - 2.3.11 Door Protection Plates
 - 2.3.11.1 Sizes of Kick Plates
 - 2.3.12 Door Stops and Silencers
 - 2.3.13 Thresholds
 - 2.3.14 Weather Stripping Gasketing
 - 2.3.14.1 Extruded Aluminum Retainers
 - 2.3.15 Soundproofing Gasketing
 - 2.3.16 Rain Drips
 - 2.3.16.1 Door Rain Drips
 - 2.3.16.2 Overhead Rain Drips
 - 2.3.17 Special Tools
- 2.4 FASTENERS
- 2.5 FINISHES

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Weather Stripping Installation
 - 3.1.1.1 Stop-Applied Weather Stripping
 - 3.1.2 Soundproofing Installation
 - 3.1.3 Threshold Installation
- 3.2 FIRE DOORS AND EXIT DOORS
- 3.3 HARDWARE LOCATIONS
- 3.4 FIELD QUALITY CONTROL
- 3.5 HARDWARE SETS
 - 3.5.1 Manufacturers

-- End of Section Table of Contents --

SECTION 08710

DOOR HARDWARE
02/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM E 283 (1991) Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

BHMA A156.1 (1997) Butts and Hinges (BHMA 101)
BHMA A156.2 (1996) Bored and Preassembled Locks and Latches (BHMA 601)
BHMA A156.3 (1994) Exit Devices (BHMA 701)
BHMA A156.4 (1992) Door Controls - Closers (BHMA 301)
BHMA A156.6 (1994) Architectural Door Trim (BHMA 1001)
BHMA A156.7 (1988) Template Hinge Dimensions
BHMA A156.8 (1994) Door Controls - Overhead Holders (BHMA 311)
BHMA A156.13 (1994) Mortise Locks & Latches (BHMA 621)
BHMA A156.16 (1997) Auxiliary Hardware
BHMA A156.18 (1993) Materials and Finishes (BHMA 1301)
BHMA A156.21 (1996) Thresholds
BHMA A156.22 (1996) Door Gasketing Systems

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80 (1999) Fire Doors and Fire Windows
NFPA 101 (1997) Life Safety Code

STEEL DOOR INSTITUTE (SDOI)

SDI 100 (1991) Standard Steel Doors and Frames

UNDERWRITERS LABORATORIES (UL)

UL Bldg Mat Dir (1999) Building Materials Directory

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

SD-02 Shop Drawings

Hardware schedule

Keying system; G, RE

SD-03 Product Data

Hardware items

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule items, Data Package 1

Submit data package in accordance with Section 01781, "Operation and Maintenance Data."

SD-11 Closeout Submittals

Key bitting

1.3 HARDWARE SCHEDULE

Prepare and submit hardware schedule in the following form:

Hard-ware Item	Quan-tity	Size	Reference Publi-cation Type No.	Finish	Mfr. Name and Catalog No.	Key Con-trol Symbols	UL Mark (If fire rated and listed)	BHMA Finish Designa-tion
-----	-----	-----	-----	-----	-----	-----	-----	-----

1.4 KEY BITTING CHART REQUIREMENTS

Submit key bitting charts to the Contracting Officer prior to completion of the work. Include:

- a. Complete listing of all keys (AA1, AA2, etc.).
- b. Complete listing of all key cuts (AA1-123456, AA2-123458).
- c. Tabulation showing which key fits which door.
- d. Copy of floor plan showing doors and door numbers.

- e. Listing of 20 percent more key cuts than are presently required in each master system.

1.5 QUALITY ASSURANCE

1.5.1 Hardware Manufacturers and Modifications

Provide, as far as feasible, locks, hinges, and closers of one lock, hinge, or closer manufacturer's make. Modify hardware as necessary to provide features indicated or specified.

1.6 DELIVERY, STORAGE, AND HANDLING

Deliver hardware in original individual containers, complete with necessary appurtenances including fasteners and instructions. Mark each individual container with item number as shown in hardware schedule. Deliver permanent keys and removable cores to the Contracting Officer, either directly or by certified mail. Deliver construction master keys with the locks.

PART 2 PRODUCTS

2.1 TEMPLATE HARDWARE

Hardware to be applied to metal shall be made to template. Promptly furnish template information or templates to door and frame manufacturers. Template hinges shall conform to BHMA A156.7. Coordinate hardware items to prevent interference with other hardware.

2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS

Provide all hardware necessary to meet the requirements of NFPA 80 for fire doors and NFPA 101 for exit doors, as well as to other requirements specified, even if such hardware is not specifically mentioned under paragraph entitled "Hardware Schedule." Such hardware shall bear the label of Underwriters Laboratories, Inc., and be listed in UL Bldg Mat Dir or labeled and listed by another testing laboratory acceptable to the Contracting Officer.

2.3 HARDWARE ITEMS

Hinges, locks, latches, exit devices, bolts, and closers shall be clearly and permanently marked with the manufacturer's name or trademark where it will be visible after the item is installed. For closers with covers, the name or trademark may be beneath the cover.

2.3.1 Hinges

BHMA A156.1, 4 1/2 by 4 1/2 inches unless otherwise specified. Construct loose pin hinges for exterior doors and reverse-bevel interior doors so that pins will be nonremovable when door is closed. Other antifriction bearing hinges may be provided in lieu of ball-bearing hinges.

2.3.2 Locks and Latches

2.3.2.1 Mortise Locks and Latches

BHMA A156.13, Series 1000, Operational Grade 1, Security Grade 2. Provide

mortise locks with escutcheons not less than 7 by 2 1/4 inches with a bushing at least 1/4 inch long. Cut escutcheons to suit cylinders and provide trim items with straight, beveled, or smoothly rounded sides, corners, and edges. Knobs and roses of mortise locks shall have screwless shanks and no exposed screws.

2.3.3 Exit Devices

BHMA A156.3, Grade 1. Provide adjustable strikes for rim type and vertical rod devices. Provide open back strikes for pairs of doors with mortise and vertical rod devices. Touch bars shall be provided in lieu of conventional crossbars and arms. Provide escutcheons, not less than 7 by 2 1/4 inches.

2.3.4 Cylinders and Cores

Provide cylinders and cores for new locks, including locks provided under other sections of this specification. Cylinders and cores shall have six pin tumblers. Cylinders shall be products of one manufacturer, and cores shall be the products of one manufacturer. Rim cylinders and mortise cylinders shall have interchangeable cores which are removable by special control keys. Stamp each interchangeable core with a key control symbol in a concealed place on the core.

2.3.5 Keying System

Provide an extension of the existing keying system. Existing locks were manufactured by Best and have interchangeable cores.

2.3.6 Lock Trim

Cast, forged, or heavy wrought construction and commercial plain design.

2.3.6.1 Knobs and Roses

In addition to meeting test requirements of BHMA A156.2 and BHMA A156.13, knobs, roses, and escutcheons shall be 0.050 inch thick if unreinforced. If reinforced, outer shell shall be 0.035 inch thick and combined thickness shall be 0.070 inch, except knob shanks shall be 0.060 inch thick.

2.3.6.2 Lever Handles

Provide lever handles in lieu of knobs. Lever handles for exit devices shall meet the test requirements of BHMA A156.13 for mortise locks. Lever handle locks shall have a breakaway feature (such as a weakened spindle or a shear key) to prevent irreparable damage to the lock when a force in excess of that specified in BHMA A156.13 is applied to the lever handle. Lever handles shall return to within 1/2 inch of the door face.

2.3.6.3 Texture

Provide knurled or abrasive coated knobs or lever handles for doors which are accessible to blind persons and which lead to dangerous areas.

2.3.7 Keys

Furnish one file key, one duplicate key, and one working key for each key change. Furnish one additional working key for each lock of each keyed-alike group. Furnish 4 construction master keys, and 3 control keys for removable cores. Stamp each key with appropriate key control symbol

and "U.S. property - Do not duplicate." Do not place room number on keys.

2.3.8 Door Bolts

BHMA A156.16. Provide dustproof strikes for bottom bolts, except for doors having metal thresholds. Automatic latching flush bolts: BHMA A156.3, Type 25.

2.3.9 Closers

BHMA A156.4, Series C02000, Grade 1, with PT 4C. Provide with brackets, arms, mounting devices, fasteners, and other features necessary for the particular application. Size closers in accordance with manufacturer's recommendations, or provide multi-size closers, Sizes 1 through 6, and list sizes in the Hardware Schedule. Provide manufacturer's 10 year warranty.

2.3.9.1 Identification Marking

Engrave each closer with manufacturer's name or trademark, date of manufacture, and manufacturer's size designation located to be visible after installation.

2.3.10 Overhead Holders

BHMA A156.8.

2.3.11 Door Protection Plates

BHMA A156.6.

2.3.11.1 Sizes of Kick Plates

Width for single doors shall be 2 inches less than door width; width for pairs of doors shall be one inch less than door width. Height of kick plates shall be 10 inches for flush doors.

2.3.12 Door Stops and Silencers

BHMA A156.16. Silencers Type L03011. Provide three silencers for each single door, two for each pair.

2.3.13 Thresholds

BHMA A156.21. Use J35100, with vinyl or silicone rubber insert in face of stop, for exterior doors opening out, unless specified otherwise.

2.3.14 Weather Stripping Gasketing

BHMA A156.22. Provide the type and function designation where specified in paragraph entitled "Hardware Schedule". A set shall include head and jamb seals, sweep strips, and, for pairs of doors, astragals. Air leakage of weather stripped doors shall not exceed 1.25 cubic feet per minute of air per square foot of door area when tested in accordance with ASTM E 283. Weather stripping shall be one of the following:

2.3.14.1 Extruded Aluminum Retainers

Extruded aluminum retainers not less than 0.050 inch wall thickness with vinyl, neoprene, silicone rubber, or polyurethane inserts. Aluminum shall

be clear (natural) anodized.

2.3.15 Soundproofing Gasketing

BHMA A156.22. A set shall include adjustable doorstops at head and jambs and an automatic door bottom, both of extruded aluminum, clear (natural) anodized, surface applied, with vinyl fin seals between plunger and housing. Doorstops shall have solid neoprene tube, silicone rubber, or closed-cell sponge gasket. Door bottoms shall have adjustable operating rod and silicone rubber or closed-cell sponge neoprene gasket. Doorstops shall be mitered at corners. Provide the type and function designation where specified in paragraph entitled "Hardware Sets".

2.3.16 Rain Drips

Extruded aluminum, not less than 0.08 inch thick, clear anodized. Set drips in sealant conforming to Section 07900A JOINT SEALING and fasten with stainless steel screws.

2.3.16.1 Door Rain Drips

Approximately 1 1/2 inches high by 5/8 inch projection. Align bottom with bottom edge of door.

2.3.16.2 Overhead Rain Drips

Approximately 1 1/2 inches high by 2 1/2 inches projection, with length equal to overall width of door frame. Align bottom with door frame rabbet.

2.3.17 Special Tools

Provide special tools, such as spanner and socket wrenches and dogging keys, required to service and adjust hardware items.

2.4 FASTENERS

Provide fasteners of proper type, quality, size, quantity, and finish with hardware. Fasteners exposed to weather shall be of nonferrous metal or stainless steel. Provide fasteners of type necessary to accomplish a permanent installation.

2.5 FINISHES

BHMA A156.18. Hardware shall have BHMA 630 finish (satin stainless steel), unless specified otherwise. Provide items not manufactured in stainless steel in BHMA 626 finish (satin chromium plated) over brass or bronze, except surface door closers which shall have aluminum paint finish, and except steel hinges which shall have BHMA 652 finish (satin chromium plated). Hinges for exterior doors shall be stainless steel with BHMA 630 finish or chromium plated brass or bronze with BHMA 626 finish. Exit devices may be provided in BHMA 626 finish in lieu of BHMA 630 finish except where BHMA 630 is specified under paragraph entitled "Hardware Sets". Exposed parts of concealed closers shall have finish to match lock and door trim. Hardware for aluminum doors shall be finished to match the doors.

PART 3 EXECUTION

3.1 INSTALLATION

Install hardware in accordance with manufacturers' printed instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Weather Stripping Installation

Handle and install weather stripping so as to prevent damage. Provide full contact, weather-tight seals. Doors shall operate without binding.

3.1.1.1 Stop-Applied Weather Stripping

Fasten in place with color-matched sheet metal screws not more than 9 inches o.c. after doors and frames have been finish painted.

3.1.2 Soundproofing Installation

Install as specified for stop-applied weather stripping.

3.1.3 Threshold Installation

Extend thresholds the full width of the opening and notch end for jamb stops. Set thresholds in a full bed of sealant and anchor to floor with cadmium-plated, countersunk, steel screws in expansion sleeves.

3.2 FIRE DOORS AND EXIT DOORS

Install hardware in accordance with NFPA 80 for fire doors, NFPA 101 for exit doors.

3.3 HARDWARE LOCATIONS

SDI 100, unless indicated or specified otherwise.

- a. Kick and Armor Plates: Push side of single-acting doors. Both sides of double-acting doors.
- b. Mop Plates: Bottom flush with bottom of door.

3.4 FIELD QUALITY CONTROL`

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Submit notice of testing 15 days before scheduled, so that testing can be witnessed by the Contracting Officer. Adjust hinges, locks, latches, bolts, holders, closers, and other items to operate properly. Demonstrate that permanent keys operate respective locks, and give keys to the Contracting Officer. Correct, repair, and finish, as directed, errors in cutting and fitting and damage to adjoining work.

3.5 HARDWARE SETS

3.5.1 Manufacturers

Part and model numbers of various manufacturers are used in the schedule in addition to the ANSI designations where applicable. The names and model

numbers are provided as a convenience to the bidders and are not intended to preclude the use of any other manufacturer whose products meet the specified requirements. The manufacturers whose products are cited are the following:

- a. Hinges: McKinney
- b. Locksets and Latchsets: Arrow
- c. Bolts, Protection Plates, Stops: Rockwood
- d. Closers: Norton
- e. Thresholds, Weatherstripping, Gasketing and Seals: National Guard
- f. Exit Devices: Dorma

Hardware Set 1

Each to have:

4 pair Hinges	A5111 x NRP x 630
1 Flush Bolt	L1425 x 24 x 626
1 Flush Bolt	L1425 x 12 x 626
1 Latchset	B07 x HSL(02) Exit only, x 630 no exterior trim
1 Closer	CLP-1601-T x SN x P x 689
1 OH Holder	C02511 x 626
2 Kick Plates	J102 x .050 x 630
1 Threshold	896 S x J36100
2 Door Sweeps	200 SA x R3E434
1 Gasketing	161 SA x R3E164
1 Astragal	114 SA x R3E634
	Push side inactive leaf

Hardware Set 2

Each to have:

3 pair Hinges	A5111 x NRP x 630
2 Flush Bolt	L14251 x 12 x 626
1 Lockset	B12 x HSL x TC-7 x F07 x 626
* Closer	CLP-1601-T x SN x P x 689
1 OH Holder	C02511 x 626
2 Kick Plates	J102 x .050 x 630
1 Threshold	896 S x J36100
2 Door Sweeps	200 SA x R3E434
1 Gasketing	161 SA x R3E164
1 Astragal	114 SA x R3E634
	Push side inactive leaf

Hardware Set 3

Each to have:

4 pair Hinges	A5111 x NRP x 630
1 Flush Bolt	L1425 x 24 x 626
1 Flush Bolt	L1425 x 12 x 626
1 Lockset	B12 x HSL x (IC-7) x 113 x F07 x 626 No exterior trim
1 Closer	CLP-1601-T x SN x P x 689
1 OH Holder	C02511 x 626
2 Kick Plates	J102 x .050 x 630
1 Threshold	896 S x J36100
2 Door Sweeps	200 SA x R3E434
1 Gasketing	161 SA x R3E164

1 Astragal 114 SA x R3E634
 Push side inactive leaf

Hardware Set 4

Each to have:

1-1/2 pair Hinges A5112 x NRP x 630
 1 Exit Device Type 1, Function 01 x 630
 No exterior trim
 1 Closer CLP-1601 x SN x P x 689
 1 Kick Plates J102 x 0.050 x 630
 1 Threshold 896 S x J36100
 1 Door Sweep 200 SA x R3E434
 1 Gasketing 161 SA x R3E164

Hardware Set 5

Each to have:

1 Set Flush Bolts 1945 (Type 25)
 1 Lockset B17 HSL (AC-7) x F05 x 626

All other hardware shall be part of acoustical door package

Hardware Set 6

Each to have:

3 pair Hinges A8111 x 630
 2 Flush Bolt L14251 x 12 x 626
 1 Lockset B12 x HSL x (IC-7) x F05 x 626
 * Closer CLP-1601 x SN x P x 689
 1 OH Holder C05541 x 630
 (Inactive leaf)
 2 Kick Plates J102 x 0.050 x 630
 3 Silencers L03011 x Gray

Hardware Set 7

Each to have:

1-1/2 pair Hinges A8112 x 626
 1 Lockset B17 x HSL x (IC-7) x F05 x 626
 1 Closer 1600 BF x SN x P x689
 1 Kick Plate J102 x 0.050 x 630
 1 Wall Stop L22101 x 630
 1 Threshold J36100
 3 Silencers L03011 x Gray

Hardware Set 8

Each to have:

3 pair Hinges A8112 x 626
 1 set Flush Bolt 1945 (Type 25)
 1 Lockset B17 x HSL x (IC-7) x F05 x 626
 1 Coordinator 1672 (Type 21)
 2 Closers 1601 BF x SN x P x689
 2 Kick Plate J102 x 0.050 x 630
 2 Wall Stop L22101 x 630
 1 Threshold J36100
 3 Silencers L03011

Hardware Set 9

1-1/2 pair Hinges	A8112 x 626
1 Lockset	B17 x HSL x (IC-7) x F05 x 626
2 Wall Stop	L22101 x 630
3 Silencers	L03011

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - DOORS & WINDOWS

SECTION 08810A

GLASS AND GLAZING

05/97

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 SYSTEM DESCRIPTION
- 1.4 DELIVERY, STORAGE AND HANDLING
- 1.5 PROJECT/SITE CONDITIONS
- 1.6 WARRANTY
 - 1.6.1 Insulating Glass

PART 2 PRODUCTS

- 2.1 FLOAT GLASS
 - 2.1.1 Annealed Glass
- 2.2 ROLLED GLASS
 - 2.2.1 Omitted
 - 2.2.2 Wired Glass
- 2.3 INSULATING GLASS
 - 2.3.1 Omitted
 - 2.3.2 Omitted
 - 2.3.3 Omitted
 - 2.3.4 Low-E Insulating Glass
- 2.4 OMITTED
- 2.5 HEAT-TREATED GLASS
 - 2.5.1 Tempered Glass
- 2.6 LAMINATED GLAZINGS
 - 2.6.1 Laminated Glass
- 2.7 OMITTED
- 2.8 OMITTED
- 2.9 OMITTED
- 2.10 OMITTED
- 2.11 GLAZING ACCESSORIES
 - 2.11.1 Preformed Tape
 - 2.11.2 Sealant
 - 2.11.3 Glazing Gaskets
 - 2.11.3.1 Fixed Glazing Gaskets
 - 2.11.3.2 Wedge Glazing Gaskets
 - 2.11.3.3 Omitted
 - 2.11.4 Putty and Glazing Compound
 - 2.11.5 Setting and Edge Blocking

PART 3 EXECUTION

- 3.1 PREPARATION
- 3.2 INSTALLATION
- 3.3 CLEANING
- 3.4 PROTECTION

-- End of Section Table of Contents --

UFGS-08810A (May 1997)

SECTION 08810A

GLASS AND GLAZING

05/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1 (1984; R 1994) Safety Performance Specifications and Methods of Test for Safety Glazing Materials Used in Buildings

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 509 (1994) Elastomeric Cellular Preformed Gasket and Sealing Material

ASTM C 669 (1995) Glazing Compounds for Back Bedding and Face Glazing of Metal Sash

ASTM C 864 (1999) Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers

ASTM C 920 (1998) Elastomeric Joint Sealants

ASTM C 1036 (1991; R 1997) Flat Glass

ASTM C 1048 (1997b) Heat-Treated Flat Glass - Kind HS, Kind FT Coated and Uncoated Glass

ASTM C 1172 (1996e1) Laminated Architectural Flat Glass

ASTM D 395 (1998) Rubber Property - Compression Set

ASTM E 773 (1997) Accelerated Weathering of Sealed Insulating Glass Units

ASTM E 774 (1997) Classification of the Durability of Sealed Insulating Glass Units

ASTM E 1300 (1998) Determining the Minimum Thickness and Type of Glass Required to Resist a Specified Load

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1201 Safety Standard for Architectural Glazing

Materials

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-378 (Basic) Putty Linseed Oil Type, (for
Wood-Sash-Glazing)

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual (1997) Glazing Manual

GANA Standards Manual (1995) Engineering Standards Manual

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80 (1999) Fire Doors and Fire Windows

NFPA 252 (1995) Fire Tests of Door Assemblies

NFPA 257 (1996) Fire Tests for Window and Glass
Block Assemblies

UNIFIED FACILITIES CRITERIA (UFC)

UFC 4-010-01 (2002) DoD Minimum Antiterrorism Standards
for Buildings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation

Drawings showing complete details of the proposed setting methods, mullion details, edge blocking, size of openings, frame details, materials, and types and thickness of glass.

SD-03 Product Data

Insulating Glass
Glazing Accessories

Manufacturer's descriptive product data, handling and storage recommendations, installation instructions, and cleaning instructions.

SD-04 Samples

Glass

Two 8 x 10 inch samples of each of the following: tinted glass,, heat-absorbing glass, laminated glass and insulating glass units.

SD-07 Certificates

Glass

Certificates stating that the glass meets the specified requirements. Labels or manufacturers marking affixed to the glass will be accepted in lieu of certificates.

1.3 SYSTEM DESCRIPTION

Glazing systems shall be fabricated and installed watertight and airtight to withstand thermal movement and wind loading without glass breakage, gasket failure, deterioration of glazing accessories, and defects in the work. Glazed panels shall comply with the safety standards, as indicated in accordance with ANSI Z97.1. Glazed panels shall comply with indicated wind/snow loading in accordance with ASTM E 1300. Exterior windows shall comply with the requirements of UFC 4-010-01

1.4 DELIVERY, STORAGE AND HANDLING

Glazing compounds shall be delivered to the site in the manufacturer's unopened containers. Glass shall be stored indoors in a safe, well ventilated dry location in accordance with manufacturer's instructions, and shall not be unpacked until needed for installation. Glass shall not be stored on site over 1 month.

1.5 PROJECT/SITE CONDITIONS

Glazing work shall not be started until outdoor temperature is above 40 degrees F and rising, unless procedures recommended by glass manufacturer and approved by Contracting Officer are made to warm the glass and rabbet surfaces. Ventilation shall be provided to prevent condensation of moisture on glazing work during installation. Glazing work shall not be performed during damp or raining weather.

1.6 WARRANTY

1.6.1 Insulating Glass

Manufacturer shall warrant the insulating glass to be free of fogging or film formation on the internal glass surfaces caused by failure of the hermetic seal for a period of 10 years from Date of Substantial Completion. Warranty shall be signed by manufacturer.

PART 2 PRODUCTS

2.1 FLOAT GLASS

2.1.1 Annealed Glass

Annealed glass shall be Type I transparent flat type, Class 1 - clear, Quality q3 - glazing select.

2.2 ROLLED GLASS

2.2.1 Omitted

2.2.2 Wired Glass

Wired glass shall be Type II flat type, Class 1 - translucent, Quality q8 - glazing, Form 1 - wired and polished both sides, conforming to ASTM C 1036.

Wire mesh shall be polished stainless steel Mesh 1 - diamond. Wired glass for fire-rated windows shall bear an identifying UL label or the label of a nationally recognized testing agency, and shall be rated for 45 minutes when tested in accordance with NFPA 257. Wired glass for fire-rated doors shall be tested as part of a door assembly in accordance with NFPA 252.

2.3 INSULATING GLASS

Insulating glass shall be Class A preassembled units of dual-seal construction consisting of lites of glass separated by an aluminum, steel, or stainless steel, spacer and dehydrated space conforming to ASTM E 773 and ASTM E 774. Spacer shall be roll-formed, with bent or tightly welded or keyed and sealed joints to completely seal the spacer periphery and eliminate moisture and hydrocarbon vapor transmission into airspace through the corners. Primary seal shall be compressed polyisobutylene and the secondary seal shall be a specially formulated silicone. Glass types shall be as follows:

- 2.3.1 Omitted
- 2.3.2 Omitted
- 2.3.3 Omitted

2.3.4 Low-E Insulating Glass

Interior glass panes for Low-E insulating units shall be laminated glass as specified in this section and exterior glass panes for Low-E insulating units shall be Type I annealed flat glass, Class 2-tinted with anti-reflective low-emissivity coating on No. 2 surface (inside surface of exterior pane), Quality q3 - glazing select, conforming to ASTM C 1036. Glass performance shall be R-Value/Winter Nighttime 0.34, shading coefficient 0.42. Color shall be gray.

2.4 OMITTED

2.5 HEAT-TREATED GLASS

Heat-treated glass shall conform to the following requirements.

2.5.1 Tempered Glass

Tempered glass shall be kind FT fully tempered transparent flat type, Class 1-clear, Condition A uncoated surface, Quality q3 - glazing select, conforming to ASTM C 1048 and GANA Standards Manual.

2.6 LAMINATED GLAZINGS

2.6.1 Laminated Glass

Laminated glass shall consist of two layers of Type I transparent float glass, Class 1-clear Quality q3 - glazing select, conforming to ASTM C 1036.

Glass shall be bonded together with 0.030 inchthick PVB interlayer under pressure, or alternatives such as resin laminates, conforming to requirements of 16 CFR 1201 and ASTM C 1172. Color shall be clear.

- 2.7 OMITTED
- 2.8 OMITTED

2.9 OMITTED
2.10 OMITTED

2.11 GLAZING ACCESSORIES

2.11.1 Preformed Tape

Preformed tape shall be elastomeric rubber extruded into a ribbon of a width and thickness suitable for specific application. Tape shall be of type which will remain resilient, have excellent adhesion, and be chemically compatible to glass, metal, or wood.

2.11.2 Sealant

Sealant shall be elastomeric conforming to ASTM C 920, Type S or M, Grade NS, Class 12.5, Use G, of type chemically compatible with setting blocks, preformed sealing tape and sealants used in manufacturing insulating glass. Color of sealant shall be as selected.

2.11.3 Glazing Gaskets

Glazing gaskets shall be extruded with continuous integral locking projection designed to engage into metal glass holding members to provide a watertight seal during dynamic loading, building movements and thermal movements. Glazing gaskets for a single glazed opening shall be continuous one-piece units with factory-fabricated injection-molded corners free of flashing and burrs. Glazing gaskets shall be in lengths or units recommended by manufacturer to ensure against pull-back at corners. Glazing gasket profiles shall be as indicated on drawings.

2.11.3.1 Fixed Glazing Gaskets

Fixed glazing gaskets shall be closed-cell (sponge) smooth extruded compression gaskets of cured elastomeric virgin neoprene compounds conforming to ASTM C 509, Type 2, Option 1.

2.11.3.2 Wedge Glazing Gaskets

Wedge glazing gaskets shall be high-quality extrusions of cured elastomeric virgin neoprene compounds, ozone resistant, conforming to ASTM C 864, Option 1, Shore A durometer between 65 and 75.

2.11.3.3 Omitted

2.11.4 Putty and Glazing Compound

Glazing compound shall conform to ASTM C 669 for face-glazing metal sash. Putty shall be linseed oil type conforming to CID A-A-378 for face-glazing primed wood sash. Putty and glazing compounds shall not be used with insulating glass or laminated glass.

2.11.5 Setting and Edge Blocking

Neoprene setting blocks shall be dense extruded type conforming to ASTM D 395, Method B, Shore A durometer between 70 and 90. Edge blocking shall be Shore A durometer of 50 (+ or - 5). Silicone setting blocks shall be required when blocks are in contact with silicone sealant. Profiles, lengths and locations shall be as required and recommended in writing by glass manufacturer.

PART 3 EXECUTION

3.1 PREPARATION

Openings and framing systems scheduled to receive glass shall be examined for compliance with approved shop drawings, GANA Glazing Manual and glass manufacturer's recommendations including size, squareness, offsets at corners, presence and function of weep system, face and edge clearance requirements and effective sealing between joints of glass-framing members. Detrimental materials shall be removed from glazing rabbet and glass surfaces and wiped dry with solvent. Glazing surfaces shall be dry and free of frost.

3.2 INSTALLATION

Glass and glazing work shall be performed in accordance with approved shop drawings, GANA Glazing Manual, glass manufacturer's instructions and warranty requirements. Glass shall be installed with factory labels intact and removed only when instructed. Wired glass and fire/safety rated glass shall be installed in accordance with NFPA 80. Edges and corners shall not be ground, nipped or cut after leaving factory. Springing, forcing or twisting of units during installation will not be permitted.

3.3 CLEANING

Upon completion of project, outside surfaces of glass shall be washed clean and the inside surfaces of glass shall be washed and polished in accordance with glass manufacturer's recommendations.

3.4 PROTECTION

Glass work shall be protected immediately after installation. Glazed openings shall be identified with suitable warning tapes, cloth or paper flags, attached with non-staining adhesives. Reflective glass shall be protected with a protective material to eliminate any contamination of the reflective coating. Protective material shall be placed far enough away from the coated glass to allow air to circulate to reduce heat buildup and moisture accumulation on the glass. Glass units which are broken, chipped, cracked, abraded, or otherwise damaged during construction activities shall be removed and replaced with new units.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09100N

METAL SUPPORT ASSEMBLIES

09/99

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 OMITTED
- 1.3 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Omitted
 - 2.1.2 Materials for Attachment of Gypsum Wallboard
 - 2.1.2.1 Suspended and Furred Ceiling Systems
 - 2.1.2.2 Nonload-Bearing Wall Framing and Furring
 - 2.1.2.3 Furring Structural Steel Columns

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Omitted
 - 3.1.2 Systems for Attachment of Gypsum Wallboard
 - 3.1.2.1 Suspended and Furred Ceiling Systems
 - 3.1.2.2 Nonload-Bearing Wall Framing and Furring
 - 3.1.2.3 Furring Structural Steel Columns
- 3.2 ERECTION TOLERANCES

-- End of Section Table of Contents --

UFGS-09100N (September 1999)

SECTION 09100N

METAL SUPPORT ASSEMBLIES

09/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 463/A 463M	(1997; Rev. A) Steel Sheet, Aluminum-Coated, by the Hot-Dip Process
ASTM A 653/A 653M	(1998) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM C 645	(1998) Nonstructural Steel Framing Members
ASTM C 754	(1997) Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products

UNDERWRITERS LABORATORIES (UL)

UL Fire Resist Dir	(1997) Fire Resistance Directory
--------------------	----------------------------------

1.2 OMITTED

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the job site and store in ventilated dry locations. Storage area shall permit easy access for inspection and handling. If materials are stored outdoors, stack materials off the ground, supported on a level platform, and fully protected from the weather. Handle materials carefully to prevent damage. Remove damaged items and provide new items.

PART 2 PRODUCTS

2.1 MATERIALS

Provide steel materials for metal support systems with galvanized coating ASTM A 653/A 653M, G-60; aluminum coating ASTM A 463/A 463M, T1-25; or a 55-percent aluminum-zinc coating.

2.1.1 Omitted

2.1.2 Materials for Attachment of Gypsum Wallboard

2.1.2.1 Suspended and Furred Ceiling Systems

ASTM C 645.

2.1.2.2 Nonload-Bearing Wall Framing and Furring

ASTM C 645, but not thinner than 0.0284 inch thickness, with 0.0329 inch minimum thickness supporting wall hung items such as cabinetwork, equipment and fixtures .

2.1.2.3 Furring Structural Steel Columns

ASTM C 645. Steel (furring) clips and support angles listed in UL Fire Resist Dir may be provided in lieu of steel studs for erection of gypsum wallboard around structural steel columns.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Omitted

3.1.2 Systems for Attachment of Gypsum Wallboard

3.1.2.1 Suspended and Furred Ceiling Systems

ASTM C 754, except that framing members shall be 16 inches o.c. unless indicated otherwise.

3.1.2.2 Nonload-Bearing Wall Framing and Furring

ASTM C 754, except as indicated otherwise.

3.1.2.3 Furring Structural Steel Columns

Install studs or galvanized steel clips and support angles for erection of gypsum wallboard around structural steel columns in accordance with the UL Fire Resist Dir, design number(s) of the fire resistance rating indicated.

3.2 ERECTION TOLERANCES

Framing members which will be covered by finish materials such as wallboard, plaster, or ceramic tile set in a mortar setting bed, shall be within the following limits:

- a. Layout of walls and partitions: 1/4 inch from intended position;
- b. Plates and runners: 1/4 inch in 8 feet from a straight line;
- c. Studs: 1/4 inch in 8 feet out of plumb, not cumulative; and
- d. Face of framing members: 1/4 inch in 8 feet from a true plane.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09250

GYPSUM BOARD

11/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, STORAGE, AND HANDLING
 - 1.3.1 Delivery
 - 1.3.2 Storage
 - 1.3.3 Handling
- 1.4 ENVIRONMENTAL CONDITIONS
 - 1.4.1 Temperature
 - 1.4.2 Exposure to Weather
- 1.5 QUALIFICATIONS

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Gypsum Board
 - 2.1.1.1 Regular
 - 2.1.1.2 Omitted
 - 2.1.1.3 Type X (Special Fire-Resistant)
 - 2.1.2 Gypsum Backing Board
 - 2.1.2.1 Omitted
 - 2.1.2.2 Omitted
 - 2.1.2.3 Type X (Special Fire-Resistant)
 - 2.1.3 Omitted
 - 2.1.4 Exterior Gypsum Soffit Board
 - 2.1.5 Glass Mat Covered or Reinforced Gypsum Sheathing
 - 2.1.5.1 Glass Mat Covered or Reinforced Gypsum Sheathing Sealant
 - 2.1.6 Omitted
 - 2.1.7 Omitted
 - 2.1.8 Omitted
 - 2.1.9 Joint Treatment Materials
 - 2.1.9.1 Embedding Compound
 - 2.1.9.2 Finishing or Topping Compound
 - 2.1.9.3 All-Purpose Compound
 - 2.1.9.4 Setting or Hardening Type Compound
 - 2.1.9.5 Joint Tape
 - 2.1.10 Fasteners
 - 2.1.10.1 Omitted
 - 2.1.10.2 Screws
 - 2.1.10.3 Omitted
 - 2.1.11 Adhesives
 - 2.1.11.1 Omitted
 - 2.1.11.2 Omitted
 - 2.1.11.3 Adhesive for Laminating
 - 2.1.12 Omitted
 - 2.1.13 Omitted
 - 2.1.14 Accessories

- 2.1.15 Asphalt Impregnated Building Felt
- 2.1.16 Water
- 2.1.17 Sound-Retarding (Acoustic) Insulation

PART 3 EXECUTION

3.1 EXAMINATION

- 3.1.1 Framing and Furring
- 3.1.2 Gypsum Board

3.2 APPLICATION OF GYPSUM BOARD

- 3.2.1 Omitted
- 3.2.2 Omitted
- 3.2.3 Omitted
- 3.2.4 Omitted
- 3.2.5 Omitted
- 3.2.6 Omitted
- 3.2.7 Application of Gypsum Board to Steel Framing and Furring
- 3.2.8 Omitted
- 3.2.9 Omitted
- 3.2.10 Omitted
- 3.2.11 Glass Mat Covered or Fiber Reinforced Gypsum Sheathing
- 3.2.12 Omitted
- 3.2.13 Control Joints

3.3 OMITTED

3.4 FINISHING OF GYPSUM BOARD

- 3.4.1 Uniform Surface

3.5 SEALING

- 3.5.1 Sealing for Glass Mat or Reinforced Gypsum Board Sheathing

3.6 FIRE-RESISTANT ASSEMBLIES

3.7 PATCHING

-- End of Section Table of Contents --

UFGS-09250 (November 2001)

SECTION 09250

GYPSUM BOARD

11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 36/C 36M	(1999) Gypsum Wallboard
ASTM C 79/C 79M	(2001) Standard Specification for Treated Core and Nontreated Core Gypsum Sheathing Board
ASTM C 442/C 442M	(1999; Rev. A) Gypsum Backing Board and Coreboard
ASTM C 475	(1994) Joint Compound and Joint Tape for Finishing Gypsum Board
ASTM C 630/C 630M	(2001) Water-Resistant Gypsum Backing Board
ASTM C 840	(2001) Application and Finishing of Gypsum Board
ASTM C 931/C 931M	(1998) Exterior Gypsum Soffit Board
ASTM C 954	(2000) Steel Drill Screws for the Application of Gypsum Board or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness
ASTM C 1002	(2000) Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases
ASTM C 1047	(1999) Accessories for Gypsum Wallboard and Gypsum Veneer Base
ASTM C 1177/C 1177M	(1999) Standard Specification for Glass Mat Gypsum Substrate for use as Sheathing
ASTM C 1396/C 1396M	(2000) Standard Specification for Gypsum Board
ASTM D 226	(1997) Standard Specification for

Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing

- ASTM D 412 (1998) Standard Test Methods for Vulcanized Rubber and Thermoplastic Rubbers and Thermoplastic Elastomers-Tension
- ASTM D 624 (2000) Standard Test Method for Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
- ASTM D 1149 (1999) Standard Test Method for Rubber Deterioration-Surface Ozone Cracking in a Chamber

GYPSUM ASSOCIATION (GA)

- GA 214 (1996) Recommended Levels of Gypsum Board Finish
- GA 216 (2000) Application and Finishing of Gypsum Board
- GA 253 (1999) Application of Gypsum Sheathing
- GA 600 (2000) Fire Resistance and Sound Control Design Manual

UNDERWRITERS LABORATORIES (UL)

- UL Fire Resist Dir (2000) Fire Resistance Directory

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

SD-03 Product Data

- Glass Mat Covered or Reinforced Gypsum Sheathing
- Glass Mat Covered or Reinforced Gypsum Sheathing Sealant
- Accessories

Submit for each type of gypsum board and for cementitious backer units.

SD-07 Certificates

- Asbestos Free Materials; G, RE
- Certify that gypsum board types, gypsum backing board types, cementitious backer units, and joint treating materials do not contain asbestos.

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 Delivery

Deliver materials in the original packages, containers, or bundles with each bearing the brand name, applicable standard designation, and name of manufacturer, or supplier.

1.3.2 Storage

Keep materials dry by storing inside a sheltered building. Where necessary to store gypsum board and cementitious backer units outside, store off the ground, properly supported on a level platform, and protected from direct exposure to rain, snow, sunlight, and other extreme weather conditions. Provide adequate ventilation to prevent condensation.

1.3.3 Handling

Neatly stack gypsum board and cementitious backer units flat to prevent sagging or damage to the edges, ends, and surfaces.

1.4 ENVIRONMENTAL CONDITIONS

1.4.1 Temperature

Maintain a uniform temperature of not less than 50 degrees F in the structure for at least 48 hours prior to, during, and following the application of gypsum board, cementitious backer units, and joint treatment materials, or the bonding of adhesives.

1.4.2 Exposure to Weather

Protect gypsum board and cementitious backer unit products from direct exposure to rain, snow, sunlight, and other extreme weather conditions.

1.5 QUALIFICATIONS

Manufacturer shall specialize in manufacturing the types of material specified and shall have a minimum of 5 years of documented successful experience. Installer shall specialize in the type of gypsum board work required and shall have a minimum of 3 years of documented successful experience.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to specifications, standards and requirements specified herein. Provide gypsum board types, gypsum backing board types, cementitious backing units, and joint treating materials manufactured from asbestos free materials only.

2.1.1 Gypsum Board

ASTM C 36/C 36M and ASTM C 1396/C 1396M.

2.1.1.1 Regular

48 inches wide, 5/8 inch thick, tapered edges.

2.1.1.2 Omitted

2.1.1.3 Type X (Special Fire-Resistant)

48 inches wide, 5/8 inch thick, tapered edges.

2.1.2 Gypsum Backing Board

ASTM C 442/C 442M, gypsum backing board shall be used as a base in a multilayer system.

2.1.2.1 Omitted

2.1.2.2 Omitted

2.1.2.3 Type X (Special Fire-Resistant)

48 inches wide, 5/8 inch thick, square edges.

2.1.3 Omitted

2.1.4 Exterior Gypsum Soffit Board

Exterior gypsum soffit board shall conform to ASTM C 931/C 931M, regular, 48 inches wide.

2.1.5 Glass Mat Covered or Reinforced Gypsum Sheathing

Exceeds physical properties of ASTM C 79/C 79M and ASTM C 1177/C 1177M. Provide 5/8 inch, gypsum sheathing. Gypsum board shall consist of a noncombustible water-resistant core, with a glass mat surfaces embedded to the gypsum core or reinforcing embedded throughout the gypsum core. Gypsum sheathing board shall be warranted for at least 6 months against delamination due to direct weather exposure. Provide continuous, asphalt impregnated, building felt to cover exterior face of sheathing. All joints, seams and penetrations shall be sealed with compatible sealant.

2.1.5.1 Glass Mat Covered or Reinforced Gypsum Sheathing Sealant

Sealant shall be compatible with gypsum sheathing, rubber washers for masonry veneer anchors, and other associated cavity wall components such as anchors and through wall flashing. Sealants for gypsum sheathing board edge seams and veneer anchor penetrations shall be the type recommended by the gypsum sheathing manufacturer and have the following performance requirements:

- a. ASTM D 412: Tensile Strength - 80 psi
- b. ASTM D 412: Ultimate Tensile Strength (maximum elongation) - 170 psi
- c. ASTM D 624: Tear Strength, dieB, - 27 ppi
- d. ASTM D 1149: Joint Movement Capability after 14 Days cure - percent \pm 50

2.1.6 Omitted

2.1.7 Omitted

2.1.8 Omitted

2.1.9 Joint Treatment Materials

ASTM C 475.

2.1.9.1 Embedding Compound

Specifically formulated and manufactured for use in embedding tape at gypsum board joints and compatible with tape, substrate and fasteners.

2.1.9.2 Finishing or Topping Compound

Specifically formulated and manufactured for use as a finishing compound.

2.1.9.3 All-Purpose Compound

Specifically formulated and manufactured to serve as both a taping and a finishing compound and compatible with tape, substrate and fasteners.

2.1.9.4 Setting or Hardening Type Compound

Specifically formulated and manufactured for use with fiber glass mesh tape.

2.1.9.5 Joint Tape

Cross-laminated, tapered edge, reinforced paper, or fiber glass mesh tape recommended by the manufacturer.

2.1.10 Fasteners

2.1.10.1 Omitted

2.1.10.2 Screws

ASTM C 1002, Type "G", Type "S" or Type "W" steel drill screws for fastening gypsum board to gypsum board, wood framing members and steel framing members less than 0.033 inch thick. ASTM C 954 steel drill screws for fastening gypsum board to steel framing members 0.033 to 0.112 inch thick. Provide cementitious backer unit screws with a polymer coating.

2.1.10.3 Omitted

2.1.11 Adhesives

Do not use adhesive containing benzene, carbon tetrachloride, or trichloroethylene.

2.1.11.1 Omitted

2.1.11.2 Omitted

2.1.11.3 Adhesive for Laminating

For laminating two-ply gypsum board systems, provide adhesive recommended by gypsum board manufacturer.

2.1.12 Omitted

2.1.13 Omitted

2.1.14 Accessories

ASTM C 1047. Fabricate from corrosion protected steel or plastic designed for intended use. Accessories manufactured with paper flanges are not acceptable. Flanges shall be free of dirt, grease, and other materials that may adversely affect bond of joint treatment. Provide prefinished or

job decorated materials.

2.1.15 Asphalt Impregnated Building Felt

The moisture barrier over gypsum sheathing shall be 15-lb asphalt impregnated felt conforming to ASTM D 226 Type I (No. 15).

2.1.16 Water

Clean, fresh, and potable.

2.1.17 Sound-Retarding (Acoustic) Insulation

Sound-retarding insulation shall conform to ASTM C 665, Type I, and shall be manufactured and labeled specifically for use in sound-rated assemblies.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Framing and Furring

Verify that framing and furring are securely attached and of sizes and spacing to provide a suitable substrate to receive gypsum board and cementitious backer units. Verify that all blocking, headers and supports are in place to support plumbing fixtures and to receive soap dishes, grab bars, towel racks, and similar items. Do not proceed with work until framing and furring are acceptable for application of gypsum board and cementitious backer units.

3.1.2 Gypsum Board

Verify that surfaces of gypsum board to be bonded with an adhesive are free of dust, dirt, grease, and any other foreign matter. Do not proceed with work until surfaces are acceptable for application of gypsum board with adhesive.

3.2 APPLICATION OF GYPSUM BOARD

Apply gypsum board to framing and furring members in accordance with ASTM C 840 or GA 216 and the requirements specified herein. Apply gypsum board with separate panels in moderate contact; do not force in place. Stagger end joints of adjoining panels. Neatly fit abutting end and edge joints. Use gypsum board of maximum practical length. Cut out gypsum board as required to make neat close joints around openings. In vertical application of gypsum board, provide panels in lengths required to reach full height of vertical surfaces in one continuous piece. Surfaces of gypsum board and substrate members may be bonded together with an adhesive, except where prohibited by fire rating(s). Treat edges of cutouts for plumbing pipes, screwheads, and joints with water-resistant compound as recommended by the gypsum board manufacturer. Provide type of gypsum board for use in each system specified herein as indicated.

- 3.2.1 Omitted
- 3.2.2 Omitted
- 3.2.3 Omitted
- 3.2.4 Omitted
- 3.2.5 Omitted
- 3.2.6 Omitted

3.2.7 Application of Gypsum Board to Steel Framing and Furring

Apply in accordance with ASTM C 840, System VIII or GA 216.

3.2.8 Omitted

3.2.9 Omitted

3.2.10 Omitted

3.2.11 Glass Mat Covered or Fiber Reinforced Gypsum Sheathing

Apply gypsum sheathing in accordance to gypsum association publication GA 253. Design details for joints and fasteners shall follow gypsum sheathing manufacturer's requirements and be properly installed to protect the substrate from moisture intrusion. Exposed surfaces of the gypsum sheathing shall not be left exposed beyond the manufacture's recommendation without a weather barrier cladding. Provide continuous asphalt impregnated building felt over sheathing surface in shingle fashion with edges and ends lapped a minimum of 6 inch. Openings shall be properly flashed. All joints, seams and penetrations shall be sealed with compatible silicone sealant.

3.2.12 Omitted

3.2.13 Control Joints

Install expansion and contraction joints in ceilings and walls in accordance with ASTM C 840, System XIII or GA 216, unless indicated otherwise. Control joints between studs in fire-rated construction shall be filled with firesafing insulation to match the fire-rating of construction.

3.3 OMITTED

3.4 FINISHING OF GYPSUM BOARD

Tape and finish gypsum board in accordance with ASTM C 840, GA 214 and GA 216. Plenum areas above ceilings shall be finished to Level 1 in accordance with GA 214. Water resistant gypsum backing board, ASTM C 630/C 630M, to receive ceramic tile shall be finished to Level 2 in accordance with GA 214. Walls and ceilings to receive a heavy-grade wall covering or heave textured finish before painting shall be finished to Level 3 in accordance with GA 214. Walls and ceilings without critical lighting to receive flat paints, light textures, or wall coverings shall be finished to Level 4 in accordance with GA 214. Unless otherwise specified, all gypsum board walls, partitions and ceilings shall be finished to Level 5 in accordance with GA 214. Provide joint, fastener depression, and corner treatment. Do not use fiber glass mesh tape with conventional drying type joint compounds; use setting or hardening type compounds only. Provide treatment for water-resistant gypsum board as recommended by the gypsum board manufacturer.

3.4.1 Uniform Surface

Wherever gypsum board is to receive eggshell, semigloss or gloss paint finish, or where severe, up or down lighting conditions occur, finish gypsum wall surface in accordance to GA 214 Level 5. In accordance with GA 214 Level 5, apply a thin skim coat of joint compound to the entire gypsum board surface, after the two-coat joint and fastener treatment is complete and dry.

3.5 SEALING

Seal openings around pipes, fixtures, and other items projecting through gypsum board and cementitious backer units as specified in Section 07900a "Joint Sealing." Apply material with exposed surface flush with gypsum board or cementitious backer units.

3.5.1 Sealing for Glass Mat or Reinforced Gypsum Board Sheathing

Apply silicone sealant in a 3/8 inch bead to all joints and trowel flat. Apply enough of the same sealant to all fasteners penetrating through the glass mat gypsum board surface to completely cover the penetration when troweled flat. Construction and materials shall not be placed behind sheathing until a visual inspection of sealed joints during daylight hours has been completed by Contracting Officer.

3.6 FIRE-RESISTANT ASSEMBLIES

Wherever fire-rated construction is indicated, provide materials and application methods, including types and spacing of fasteners, wall framing in accordance with the specifications contained in UL Fire Resist Dir for the Design Number(s) indicated, or GA 600 for the File Number(s) indicated.

Joints of fire-rated gypsum board enclosures shall be closed and sealed in accordance with UL test requirements or GA requirements. Penetrations through rated partitions and ceilings shall be sealed tight in accordance with tested systems. Fire ratings shall be as indicated.

3.7 PATCHING

Patch surface defects in gypsum board to a smooth, uniform appearance, ready to receive finish as specified.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09510

ACOUSTICAL CEILINGS

07/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL REQUIREMENTS
 - 1.3.1 Omitted
 - 1.3.2 Ceiling Attenuation Class and Test
 - 1.3.3 Ceiling Sound Absorption
 - 1.3.4 Light Reflectance
- 1.4 DELIVERY AND STORAGE
- 1.5 ENVIRONMENTAL REQUIREMENTS
- 1.6 SCHEDULING
- 1.7 WARRANTY

PART 2 PRODUCTS

- 2.1 ACOUSTICAL UNITS
 - 2.1.1 Units for Exposed-Grid System
- 2.2 SUSPENSION SYSTEM
- 2.3 HANGERS
 - 2.3.1 Wires
- 2.4 OMITTED
- 2.5 OMITTED
- 2.6 FINISHES
- 2.7 COLORS AND PATTERNS
- 2.8 ACOUSTICAL SEALANT

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Suspension System
 - 3.1.1.1 Plumb Hangers
 - 3.1.1.2 Splayed Hangers
 - 3.1.2 Wall Molding
 - 3.1.3 Acoustical Units
 - 3.1.4 Caulking
- 3.2 OMITTED
- 3.3 CLEANING
- 3.4 RECLAMATION PROCEDURES

-- End of Section Table of Contents --

UFGS-09510 (July 2002)

SECTION 09510

ACOUSTICAL CEILINGS

07/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 641/A 641M	(1998) Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM C 423	(2001) Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
ASTM C 635	(2000) Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-In Panel Ceilings
ASTM C 636	(1996) Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels
ASTM C 834	(2000e1) Latex Sealants
ASTM E 580	(2000) Application of Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels in Areas Requiring Moderate Seismic Restraint
ASTM E 795	(2000) Mounting Test Specimens During Sound Absorption Tests
ASTM E 1264	(1998) Acoustical Ceiling Products
ASTM E 1414	(2000a) Airborne Sound Attenuation Between Rooms Sharing a Common Ceiling Plenum
ASTM E 1477	(1998a) Luminous Reflectance Factor of Acoustical Materials by Use of Integrating-Sphere Reflectometers

U.S. ARMY CORPS OF ENGINEERS (USACE)

TI 809-04	(1998) Seismic Design for Buildings
-----------	-------------------------------------

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Acoustical Ceiling Systems

Manufacturer's descriptive data, catalog cuts, and installation instructions. Submittals which do not provide adequate data for the product evaluation will be rejected.

SD-07 Certificates

Acoustical Units

Certificate attesting that the mineral based acoustical units furnished for the project contain recycled material and showing an estimated percent of such material.

1.3 GENERAL REQUIREMENTS

Acoustical treatment shall consist of sound controlling units mechanically mounted on a ceiling suspension system. The unit size, texture, finish, and color shall be as specified. . The location and extent of acoustical treatment shall be as shown on the approved detail drawings. Reclamation of mineral fiber acoustical ceiling panels to be removed from the job site shall be in accordance with paragraph RECLAMATION PROCEDURES.

1.3.1 Omitted

1.3.2 Ceiling Attenuation Class and Test

The ceiling attenuation class (CAC) of the ceiling system shall be 35 when determined in accordance with ASTM E 1414. Provide fixture attenuators over light fixtures and other ceiling penetrations, and provide acoustical blanket insulation adjacent to partitions, as required to achieve the specified CAC. Test ceiling shall be continuous at the partition and shall be assembled in the suspension system in the same manner that the ceiling will be installed on the project.

1.3.3 Ceiling Sound Absorption

Determine the NRC in accordance with ASTM C 423 Method of Test.

1.3.4 Light Reflectance

Determine light reflectance factor in accordance with ASTM E 1477 Test Method.

1.4 DELIVERY AND STORAGE

Materials shall be delivered to the site in the manufacturer's original unopened containers with brand name and type clearly marked. Materials

shall be carefully handled and stored in dry, watertight enclosures. Immediately before installation, acoustical units shall be stored for not less than 24 hours at the same temperature and relative humidity as the space where they will be installed in order to assure proper temperature and moisture acclimation.

1.5 ENVIRONMENTAL REQUIREMENTS

A uniform temperature of not less than 60 degrees F nor more than 85 degrees F and a relative humidity of not more than 70 percent shall be maintained for 24 hours before, during, and 24 hours after installation of acoustical units.

1.6 SCHEDULING

Interior finish work such as plastering, concrete and terrazzo work shall be complete and dry before installation. Mechanical, electrical, and other work above the ceiling line shall be completed and heating, ventilating, and air conditioning systems shall be installed and operating in order to maintain temperature and humidity requirements.

1.7 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period shall be provided. Standard performance guarantee or warranty shall contain an agreement to repair or replace acoustical panels that fail within the warranty period. Failures include, but are not limited to, sagging and warping of panels; rusting and manufacturers defects of grid system.

PART 2 PRODUCTS

2.1 ACOUSTICAL UNITS

Contractor shall comply with EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS. Acoustical units shall conform to ASTM E 1264, Class A, and the following requirements:

2.1.1 Units for Exposed-Grid System

Type: III (non-asbestos mineral fiber with painted finish).

Minimum NRC: 0.55 i when tested on mounting Type E-400 of ASTM E 795.

Pattern: C D.

Nominal size: 24 by 24 inches.

Edge detail: Reveal.

Finish: Factory-applied standard finish.

Minimum LR coefficient: LR-1, 0.75 or greater .

Minimum CAC: 35.

Flame Spread: Class A, 25 or less

2.2 SUSPENSION SYSTEM

Suspension system shall be standard exposed-grid standard width flange, and shall conform to ASTM C 635 for intermediate-duty systems. Surfaces exposed to view shall be aluminum or steel with a factory-applied white baked-enamel finish. Wall molding shall have a flange of not less than 15/16 inch. Mitered corners shall be provided. Suspended ceiling framing system shall have the capability to support the finished ceiling, light fixtures, air diffusers, and accessories, as shown. The suspension system shall have a maximum deflection of 1/360 of span length. Seismic details shall conform to the guidance in TI 809-04 and ASTM E 580 as shown on the drawings.

2.3 HANGERS

Hangers and attachment shall support a minimum 300 pound ultimate vertical load without failure of supporting material or attachment.

2.3.1 Wires

Wires shall conform to ASTM A 641/A 641M, Class 1, 0.106 inches in diameter.

2.4 OMITTED

2.5 OMITTED

2.6 FINISHES

Acoustical units and suspension system members shall have manufacturer's standard textures, patterns and finishes as specified. Ceiling suspension system components shall be treated to inhibit corrosion.

2.7 COLORS AND PATTERNS

Colors and patterns for acoustical units and suspension system components shall be as indicated.

2.8 ACOUSTICAL SEALANT

Acoustical sealant shall conform to ASTM C 834, nonstaining.

PART 3 EXECUTION

3.1 INSTALLATION

Examine surfaces to receive directly attached acoustical units for unevenness, irregularities, and dampness that would affect quality and execution of the work. Areas where acoustical units will be cemented shall be free of oils, form residue, or other materials that reduce bonding capabilities of the adhesive. Interior finish work such as plastering, concrete, and terrazzo work shall be completed and dry before installation.

Mechanical, electrical, and other work above the ceiling line shall be completed and approved prior to the start of acoustical ceiling installation. Acoustical work shall be provided complete with necessary fastenings, clips, and other accessories required for a complete installation. Mechanical fastenings shall not be exposed in the finished work. Hangers shall be laid out for each individual room or space. Hangers shall be placed to support framing around beams, ducts, columns, grilles, and other penetrations through ceilings. Main runners and carrying channels shall be kept clear of abutting walls and partitions. At

least two main runners shall be provided for each ceiling span. Wherever required to bypass an object with the hanger wires, a subsuspension system shall be installed, so that all hanger wires will be plumb.

3.1.1 Suspension System

Suspension system shall be installed in accordance with ASTM C 636 and as specified herein. There shall be no hanger wires or other loads suspended from underside of steel decking.

3.1.1.1 Plumb Hangers

Hangers shall be plumb and shall not press against insulation covering ducts and pipes. Where lighting fixtures are supported from the suspended ceiling system, hangers shall be provided at a minimum of four hangers per fixture and located not more than 6 inches from each corner of each fixture. See Section 16415A ELECTRICAL WORK, INTERIOR for additional lighting installation requirements.

3.1.1.2 Splayed Hangers

Where hangers must be splayed (sloped or slanted) around obstructions, the resulting horizontal force shall be offset by bracing, countersplaying, or other acceptable means.

3.1.2 Wall Molding

Wall molding shall be provided where ceilings abut vertical surfaces. Miter corners where wall moldings intersect or install corner caps. Wall molding shall be secured not more than 3 inches from ends of each length and not more than 16 inches on centers between end fastenings. Wall molding springs shall be provided at each acoustical unit in semi-exposed or concealed systems.

3.1.3 Acoustical Units

Acoustical units shall be installed in accordance with the approved installation instructions of the manufacturer. Edges of acoustical units shall be in close contact with metal supports, with each other, and in true alignment. Acoustical units shall be arranged so that units less than one-half width are minimized. Units in exposed-grid system shall be held in place with manufacturer's standard hold-down clips, if units weigh less than 1 psf or if required for fire resistance rating.

3.1.4 Caulking

Seal all joints around pipes, ducts or electrical outlets penetrating the ceiling. Apply a continuous ribbon of acoustical sealant on vertical web of wall or edge moldings. See Section 07900A JOINT SEALING.

3.2 OMITTED

3.3 CLEANING

Following installation, dirty or discolored surfaces of acoustical units shall be cleaned and left free from defects. Units that are damaged or improperly installed shall be removed and new units provided as directed.

3.4 RECLAMATION PROCEDURES

Ceiling tile, designated for recycling by the Contracting Officer, shall be neatly stacked on 4 by 4 foot pallets not higher than 4 foot. Panels shall be completely dry. Pallets shall then be shrink wrapped and symmetrically stacked on top of each other without falling over. Disposal shall be in accordance with Section 01572A CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09650A

RESILIENT FLOORING

07/96

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 FIRE RESISTANCE REQUIREMENTS
- 1.3 SUBMITTALS
- 1.4 DELIVERY AND STORAGE
- 1.5 ENVIRONMENTAL REQUIREMENTS
- 1.6 SCHEDULING
- 1.7 WARRANTY

PART 2 PRODUCTS

- 2.1 VINYL-COMPOSITION TILE TYPES VCT-1 and VCT-2
- 2.2 OMITTED
- 2.3 OMITTED
- 2.4 OMITTED
- 2.5 OMITTED
- 2.6 RESILIENT BASE
- 2.7 OMITTED
- 2.8 OMITTED
- 2.9 TRANSITION STRIP
- 2.10 ADHESIVE
- 2.11 POLISH
- 2.12 CAULKING AND SEALANTS
- 2.13 MANUFACTURER'S COLOR AND TEXTURE

PART 3 EXECUTION

- 3.1 EXAMINATION/VERIFICATION OF CONDITIONS
- 3.2 SURFACE PREPARATION
- 3.3 MOISTURE TEST
- 3.4 INSTALLATION OF VINYL-COMPOSITION TILE
- 3.5 OMITTED
- 3.6 OMITTED
- 3.7 INSTALLATION OF TRANSITION STRIPS
- 3.8 INSTALLATION OF RESILIENT BASE
- 3.9 OMITTED
- 3.10 OMITTED
- 3.11 CLEANING
- 3.12 PROTECTION

-- End of Section Table of Contents --

UFGS-09650A (July 1996)

SECTION 09650A

RESILIENT FLOORING

07/96

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 4078	(1992; R 1996) Water Emulsion Floor Polish
ASTM E 648	(1999) Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source
ASTM E 662	(1997) Specific Optical Density of Smoke Generated by Solid Materials
ASTM F 1066	(1999) Vinyl Composition Floor Tile

1.2 FIRE RESISTANCE REQUIREMENTS

Flooring in corridors and exits shall have a minimum average critical radiant flux of 0.22 watts per square centimeter when tested in accordance with ASTM E 648. The smoke density rating shall be less than 450 when tested in accordance with ASTM E 662.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Resilient Flooring and Accessories

Manufacturer's descriptive data and installation instructions including cleaning and maintenance instructions.

SD-04 Samples

Flooring

Three samples of each indicated color and type of flooring and

base. Sample size shall be minimum 2-1/2 x 4 inches.

SD-06 Test Reports

Moisture Test

Copies of test reports showing that representative product samples of the flooring proposed for use have been tested by an independent testing laboratory within the past three years or when formulation change occurred and conforms to the requirements specified.

1.4 DELIVERY AND STORAGE

Materials shall be delivered to the building site in original unopened containers bearing the manufacturer's name, project identification, and handling instructions. Materials shall be stored in a clean dry area with temperature maintained above 70 degrees F for 2 days prior to installation, and shall be stacked according to manufacturer's recommendations. Materials shall be protected from the direct flow of heat from hot-air registers, radiators and other heating fixtures and appliances.

1.5 ENVIRONMENTAL REQUIREMENTS

Areas to receive resilient flooring shall be maintained at a temperature above 70 degrees F and below 100 degrees F for 2 days before application, during application and 2 days after application. A minimum temperature of 55 degrees F shall be maintained thereafter.

1.6 SCHEDULING

Resilient flooring application shall be scheduled after the completion of other work which would damage the finished surface of the flooring.

1.7 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period shall be provided.

PART 2 PRODUCTS

2.1 VINYL-COMPOSITION TILE TYPES VCT-1 and VCT-2

Vinyl-composition tile shall conform to ASTM F 1066, Class 2, (through pattern tile), Composition 1, asbestos-free, and shall be 12 inches square and 1/8 inch thick. Tile shall have the color and pattern uniformly distributed throughout the thickness of the tile. Flooring in any one continuous area shall be from the same lot and shall have the same shade and pattern.

2.2 OMITTED

2.3 OMITTED

2.4 OMITTED

2.5 OMITTED

2.6 RESILIENT BASE

Base shall be manufacturers standard rubber, coved style (installed with resilient flooring and direct gluedown carpet). Base shall be 6 inches

high and a minimum 1/8 inch thick. Preformed outside corners shall be furnished.

2.7 OMITTED

2.8 OMITTED

2.9 TRANSITION STRIP

A rubber transition strip tapered to meet abutting material shall be provided.

2.10 ADHESIVE

Adhesive for flooring and wall base shall be as recommended by the flooring manufacturer.

2.11 POLISH

Polish shall conform to ASTM D 4078.

2.12 CAULKING AND SEALANTS

Caulking and sealants shall be in accordance with Section 07900A JOINT SEALING.

2.13 MANUFACTURER'S COLOR AND TEXTURE

Color and texture shall be as indicated.

PART 3 EXECUTION

3.1 EXAMINATION/VERIFICATION OF CONDITIONS

The Contractor shall examine and verify that site conditions are in agreement with the design package and shall report all conditions that will prevent a proper installation. The Contractor shall not take any corrective action without written permission from the Government.

3.2 SURFACE PREPARATION

Flooring shall be in a smooth, true, level plane, except where indicated as sloped. Before any work under this section is begun, all defects such as rough or scaling concrete, low spots, high spots, and uneven surfaces shall have been corrected, and all damaged portions of concrete slabs shall have been repaired as recommended by the flooring manufacturer. Concrete curing compounds, other than the type that does not adversely affect adhesion, shall be entirely removed from the slabs. Paint, varnish, oils, release agents, sealers, waxers, and adhesives shall be removed, as recommended by the flooring manufacturer.

3.3 MOISTURE TEST

The suitability of the concrete subfloor for receiving the resilient flooring with regard to moisture content shall be determined by a moisture test as recommended by the flooring manufacturer.

3.4 INSTALLATION OF VINYL-COMPOSITION TILE

Tile flooring shall be installed with adhesive in accordance with the

manufacturer's installation instructions. Tile lines and joints shall be kept square, symmetrical, tight, and even. Edge width shall vary as necessary to maintain full-size tiles in the field, but no edge tile shall be less than one-half the field tile size, except where irregular shaped rooms make it impossible. Flooring shall be cut to, and fitted around, all permanent fixtures, built-in furniture and cabinets, pipes, and outlets. Edge tile shall be cut, fitted, and scribed to walls and partitions after field flooring has been applied.

3.5 OMITTED

3.6 OMITTED

3.7 INSTALLATION OF TRANSITION STRIPS

Edge strips shall be secured with adhesive as recommended by the manufacturer. Edge strips shall be provided at locations where flooring termination is higher than the adjacent finished flooring, except at doorways where thresholds are provided.

3.8 INSTALLATION OF RESILIENT BASE

Wall base shall be installed with adhesive in accordance with the manufacturer's written instructions. Base joints shall be tight and base shall be even with adjacent resilient flooring. Voids along the top edge of base at masonry walls shall be filled with caulk.

3.9 OMITTED

3.10 OMITTED

3.11 CLEANING

Immediately upon completion of installation of tile in a room or an area, flooring and adjacent surfaces shall be cleaned to remove all surplus adhesive. After installation, flooring shall be washed with a cleaning solution, rinsed thoroughly with clear cold water, and, except for raised pattern rubber flooring, rubber tile and sheet rubber flooring, rubber stair treads, and static control vinyl tile, given two coats of polish in accordance with manufacturers written instructions. After each polish coat, floors shall be buffed to an even luster with an electric polishing machine. Raised pattern rubber flooring, rubber tile and sheet rubber flooring, rubber stair treads, and static control vinyl tile shall be cleaned and maintained as recommended by the manufacturer.

3.12 PROTECTION

From the time of laying until acceptance, flooring shall be protected from damage as recommended by the flooring manufacturer. Flooring which becomes damaged, loose, broken, or curled shall be removed and replaced.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09670

FLUID-APPLIED FLOORING

08/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY AND STORAGE
- 1.4 ENVIRONMENTAL CONDITIONS
- 1.5 PROTECTION
- 1.6 QUALIFICATIONS OF INSTALLER

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Primer
 - 2.1.2 Omitted
 - 2.1.3 Binder
 - 2.1.4 Fillers
 - 2.1.5 Top Coating
- 2.2 FLOORING SYSTEMS
 - 2.2.1 Omitted
 - 2.2.2 Epoxy Matrix Floor Surfacing
- 2.3 OMITTED
- 2.4 SEALER AND RESIN
- 2.5 OMITTED
- 2.6 WALL BASE
- 2.7 COLOR

PART 3 EXECUTION

- 3.1 SURFACE PREPARATION
 - 3.1.1 Concrete Surfaces
 - 3.1.1.1 Omitted
 - 3.1.1.2 Omitted
 - 3.1.1.3 Omitted
 - 3.1.1.4 Acid Etching
 - 3.1.1.5 Air Drying
 - 3.1.2 Omitted
 - 3.1.3 Omitted
 - 3.1.4 Filling Cracks, Spalls, Joints, and Other Depressions
- 3.2 MIXING
- 3.3 APPLICATION
 - 3.3.1 Primer
 - 3.3.2 Floor Surfacing
 - 3.3.3 Seal Coat
- 3.4 OMITTED
- 3.5 PROTECTION

-- End of Section Table of Contents --

UFGS-09670 (August 2002)

SECTION 09670

FLUID-APPLIED FLOORING

08/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI 503R (1993; R 1998) Use of Epoxy Compounds with Concrete

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 307 (1999) Tensile Strength of Chemical-Resistant Mortars, Grouts, and Monolithic Surfacing

ASTM C 413 (2001) Absorption of Chemical-Resistant Mortars, Grouts, and Monolithic Surfacing

ASTM C 531 (2000) Linear Shrinkage and Coefficient of Thermal Expansion of Chemical-Resistant Mortars, Grouts, and Monolithic Surfacing, Polymer Concretes

ASTM C 579 (2001) Compressive Strength of Chemical-Resistant Mortars, Grouts, Monolithic Surfacing and Polymer Concretes

ASTM C 580 (1998) Flexural Strength and Modulus of Elasticity of Chemical-Resistant Mortars, Grouts, Monolithic Surfacing, and Polymer Concretes

ASTM C 722 (1994) Chemical-Resistant Resin Monolithic Surfacing

ASTM D 1308 (1987; R 1998) Effect of Household Chemicals on Clear and Pigmented Organic Finishes

ASTM D 4060 (2001) Abrasion Resistance of Organic Coatings by the Taber Abraser

ASTM E 162 (1998e1) Surface Flammability of Materials Using a Radiant Heat Energy Source

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910-SUBPART Z

Toxic and Hazardous Substances

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealer and Resin; G, RE
Floor Surfacing; G, RE
Mixing; G, RE

Flooring manufacturer's descriptive data, mixing, proportioning, and installation instructions. Maintenance literature for resinous flooring shall be included.

SD-04 Samples

Flooring Systems; G, AE

Cured samples of each floor finish or color combination.

SD-07 Certificates

Qualifications of Installer

A written statement from the floor manufacturer that the installer is acceptable.

SD-08 Manufacturer's Instructions

Application

Complete instructions for application of flooring system including any precautions or special handling instructions required to comply with OSHA 29 CFR 1910-SUBPART Z.

SD-10 Operation and Maintenance Data

Flooring Data Package 1

Data package in accordance with Section 01781 OPERATION AND MAINTENANCE DATA.

1.3 DELIVERY AND STORAGE

Deliver the materials to the project site in unopened bags and containers clearly labeled with the name of the manufacturer, type of material, batch number, and date of manufacture. Store materials, other than aggregates, away from fire, sparks, or smoking areas. Maintain the storage area between 50 and 90 degrees F.

1.4 ENVIRONMENTAL CONDITIONS

Maintain the ambient room and floor temperatures at 65 degrees F, or above, for a period extending from 48 hours before installation until one week after installation. Concrete to receive surfacing shall have cured for at least 28 days and shall have been free of water for at least 7 days. Wood substrates shall have a measured moisture content of between 8 and 10 percent prior to application.

1.5 PROTECTION

Protect adjacent surfaces not scheduled to receive the flooring by masking, or by other means, to maintain these surfaces free of the flooring material.

1.6 QUALIFICATIONS OF INSTALLER

Installation shall be performed by an applicator approved by the manufacturer of the floor surfacing materials. The Contractor shall furnish a written statement from the manufacturer that the installer is acceptable.

PART 2 PRODUCTS

2.1 MATERIALS

Materials (except aggregate) used in the flooring shall be the products of a single manufacturer. Industrial resin-based flooring shall be trowel or spray applied 1/8 inch thick, epoxy resinous material conforming to ASTM C 722 with Type A surfacings (chemical resistance and moderate to heavy traffic resistance). Materials shall meet the following requirements:

2.1.1 Primer

Type recommended by the manufacturer to penetrate into the pores of the substrate and bond with the floor surfacing matrix to form a permanent monolithic bond between substrate and surfacing matrix.

2.1.2 Omitted

2.1.3 Binder

Binder shall be thermo-setting epoxy.

2.1.4 Fillers

Fillers, if required, shall be inert silica, quartz or other hard aggregate material as recommended by the flooring manufacturer. Fillers shall be furnished in the quantity necessary to impart the required color and physical characteristics. The filler shall contain sufficient fines to provide an even-textured, nonslip type of surface on the finished topping.

2.1.5 Top Coating

Furnish coating of type recommended by the manufacturer.

2.2 FLOORING SYSTEMS

The complete systems, after curing, shall have the following properties when tested in accordance with the test methods listed for each property.

2.2.1 Omitted

2.2.2 Epoxy Matrix Floor Surfacing

- a. Compressive Strength: ASTM C 579; 10,000 psi minimum at 7 days.
- b. Tensile Strength: ASTM C 307; 600 psi minimum at 7 days.
- c. Flexural Modulus of Elasticity: ASTM C 580; 250,000 psi minimum at 7 days.
- d. Thermal Coefficient of Expansion: ASTM C 531; 0.00004 inches per inch per degree F maximum.
- e. Shrinkage: ASTM C 531; 0.5 percent maximum.
- f. Bond Strength: ACI 503R, 300 psi minimum with 100 percent concrete failure (2500 psi Compressive Strength Concrete).
- g. Flame Spread Index: ASTM E 162; 25 maximum.
- h. Smoke Deposited: ASTM E 162; 4 mg maximum.
- i. Abrasion Resistance: ASTM D 4060; 15 mg maximum weight loss.
- j. Moisture Absorption: ASTM C 413; 1.0 percent maximum.
- k. Chemical Resistance: ASTM D 1308; no effect when exposed to the following reagents for 7 days:

Acetic acid: 5 percent solution
Ammonium Hydroxide: 10 percent solution
Citric Acid: 5 percent solution
Coffee
Coca Cola Syrup
Isopropyl Alcohol
Mineral Oil
Sodium Hydroxide: 5 percent solution
Tri-Sodium Phosphate: 5 percent solution
Urea: 6.6 percent solution

2.3 OMITTED

2.4 SEALER AND RESIN

Sealer shall be a product recommended by the industrial resin-based flooring manufacturer; when applied to the resin topping and dry, it shall be nonslip and resistant to staining. Resin shall be suitable for the type application indicated.

2.5 OMITTED

2.6 WALL BASE

Base shall be as specified in Section 09650A RESILIENT FLOORING.

2.7 COLOR

Color shall be as indicated.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Remove all dirt, dust, debris, and other loose particles by sweeping or vacuum cleaning.

3.1.1 Concrete Surfaces

3.1.1.1 Omitted

3.1.1.2 Omitted

3.1.1.3 Omitted

3.1.1.4 Acid Etching

Apply a 10 percent solution of muriatic acid at a rate of one quart per each 10 square feet of concrete surface. Allow the solution to stand until it stops bubbling but not less than 5 minutes. Remove the acid and wash the surfaces several times, as required, to remove all traces of the acid. Always dilute acid by pouring into water. Use face shield rubber gloves, and other safety equipment when using acids, alkalies, or solvents.

3.1.1.5 Air Drying

After cleaning, allow concrete surface to air dry thoroughly prior to application of surfacing. Blowers or oil free compressed air may be used. Do not use flame-drying methods. Prior to application of surfacing, test concrete surface for excessive moisture in at least two locations. Place rubber mats at each location with smooth side against concrete and place weight on top of mat to hold in position and ensure contact with concrete. Polyethylene with all edges taped may be used in lieu of mats. After 8 hours remove mat or sheeting and examine floor surface for moisture accumulation. If tests indicate accumulation of moisture at either location, additional air drying shall be undertaken until additional tests show no moisture accumulation.

3.1.2 Omitted

3.1.3 Omitted

3.1.4 Filling Cracks, Spalls, Joints, and Other Depressions

Fill all cracks, joints, spalls, and other depressions in the substrate with a latex underlayment, as recommended by the manufacturer compatible with the floor surfacing material.

3.2 MIXING

Proportion and mix the floor surfacing components in accordance with the manufacturer's instructions.

3.3 APPLICATION

Apply primer, floor surfacing, and seal coat in accordance with the manufacturer's recommendations and the following requirements.

3.3.1 Primer

Apply primer uniformly over the entire area to receive floor surfacing using clean rubber squeegees or clean steel trowels. Do not allow primer to collect in depressions. Allow primer to dry thoroughly before the next coat is applied. Reprime porous areas or areas where primer has dried.

3.3.2 Floor Surfacing

Apply mixed surfacing material to provide a finish floor surfacing not less than 3/16 inch thick. The entire surfacing in any one room or area shall be placed in one continuous operation without use of cold joints or divider strips. All surfaces shall be flush, true to plane and line, and level within 1/4 inch in 10 feet.

3.3.3 Seal Coat

Apply seal coat uniformly covering all surfaces after floor surfacing has cured and as recommended by the supplier.

3.4 OMITTED

3.5 PROTECTION

Surfacing shall set for a minimum period of 48 hours before traffic is allowed on the floor. Finished flooring shall be protected from traffic by covering with 30 pound building paper or other equally effective means until final acceptance of the project.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09680A

CARPET

08/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 REGULATORY REQUIREMENTS
- 1.4 DELIVERY AND STORAGE
- 1.5 ENVIRONMENTAL REQUIREMENTS
- 1.6 WARRANTY

PART 2 PRODUCTS

- 2.1 CARPET
 - 2.1.1 Physical Characteristics
 - 2.1.1.1 BROADLOOM CARPET
 - 2.1.2 Performance Requirements
- 2.2 ADHESIVES AND CONCRETE PRIMER
- 2.3 MOLDING
- 2.4 TAPE
- 2.5 COLOR, TEXTURE, AND PATTERN

PART 3 EXECUTION

- 3.1 SURFACE PREPARATION
- 3.2 MOISTURE AND ALKALINITY TESTS
- 3.3 PREPARATION OF CONCRETE SUBFLOOR
- 3.4 INSTALLATION
 - 3.4.1 Broadloom Installation
- 3.5 CLEANING AND PROTECTION
 - 3.5.1 Cleaning
 - 3.5.2 Protection
- 3.6 REMNANTS

-- End of Section Table of Contents --

UFGS-09680A (August 2002)

SECTION 09680A

CARPET

08/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF TEXTILE CHEMISTS AND COLORISTS (AATCC)

AATCC 16	(1998) Test Method: Colorfastness to Light
AATCC 134	(2001) Test Method: Electrostatic Propensity of Carpets
AATCC 165	(1999) Test Method: Colorfastness to Crocking: Carpets - AATCC Crockmeter Method

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 418	(1993; R 1997) Pile Yarn Floor Covering Construction
ASTM D 5252	(2001) Practice for the Operation of the Hexapod Tumble Drum Tester
ASTM D 5417	(1999) Practice for Operation of the Vettermann Drum Tester
ASTM D 5848	(1999) Standard Test Method for Mass Per Unit Area of Pile Yarn Floor Coverings
ASTM E 648	(2000) Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source

CARPET AND RUG INSTITUTE (CRI)

CRI 104	(1996) Commercial Carpet Installation Standard
---------	--

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1630	Standard for the Surface Flammability of Carpet and Rugs (FF 1-70)
40 CFR 247	Comprehensive Procurement Guideline for Products Containing Recovered Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Carpet

Manufacturer's catalog data and printed documentation stating physical characteristics, durability, resistance to fading, and flame resistance characteristics for each type of carpet material and installation accessory.

Surface Preparation Installation

Three copies of the manufacturer's printed installation instructions for the carpet, including preparation of substrate, seaming techniques, and recommended adhesives and tapes.

Regulatory Requirements

Three copies of report stating that carpet contains recycled materials and/or involvement in a recycling or reuse program. Report shall include percentage of recycled material.

SD-04 Samples

Carpet Molding

a. Carpet: Two "Production Quality" samples 18 x 18 inches of each carpet proposed for use, showing quality, pattern, and color specified.

b. Vinyl or Aluminum Moldings: Two pieces of each type at least 12 inches long.

SD-06 Test Reports

Moisture and Alkalinity Tests

SD-07 Certificates

Carpet

Certificates of compliance from a laboratory accredited by the National Laboratory Accreditation Program of the National Institute of Standards and Technology attesting that each type of carpet and carpet with cushion material conforms to the standards specified.

Regulatory Requirements

Report stating that the carpet contains recycled materials and indicating the actual percentage of recycled material.

SD-10 Operation and Maintenance Data

Carpet Cleaning and Protection

Three copies of carpet manufacturer's maintenance instructions describing recommended type of cleaning equipment and material, spotting and cleaning methods, and cleaning cycles.

1.3 REGULATORY REQUIREMENTS

Carpet and adhesives shall bear the Carpet and Rug Institute (CRI) Indoor Air Quality (IAQ) label or demonstrate compliance with testing criteria and frequencies through independent laboratory test results. Carpet type bearing the label will indicate that the carpet has been tested and meets the criteria of the CRI IAQ Carpet Testing Program, and minimizes the impact on indoor air quality. Contractor shall procure carpet in accordance with 40 CFR 247. Carpet shall conform to EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS. Where possible, product shall be purchased locally to reduce emissions of fossil fuels from transporting.

1.4 DELIVERY AND STORAGE

Materials shall be delivered to the site in the manufacturer's original wrappings and packages clearly labeled with the manufacturer's name, brand name, size, dye lot number, and related information. Materials shall be stored in a clean, dry, well ventilated area, protected from damage and soiling, and shall be maintained at a temperature above 60 degrees F for 2 days prior to installation.

1.5 ENVIRONMENTAL REQUIREMENTS

Areas in which carpeting is to be installed shall be maintained at a temperature above 60 degrees F for 2 days before installation, during installation, and for 2 days after installation. A minimum temperature of 55 degrees F shall be maintained thereafter for the duration of the contract. Traffic or movement of furniture or equipment in carpeted area shall not be permitted for 24 hours after installation. Other work which would damage the carpet shall be completed prior to installation of carpet.

1.6 WARRANTY

Manufacturer's standard performance guarantees or warranties including minimum ten (10) year wear warranty, two (2) year material and workmanship and ten (10) year tuft bind and delamination.

PART 2 PRODUCTS

2.1 CARPET

Carpet shall be first quality; free of visual blemishes, streaks, poorly dyed areas, fuzzing of pile yarn, spots or stains, and other physical and

manufacturing defects. Carpet materials and treatments shall be reasonably nonallergenic and free of other recognized health hazards. All grade carpets shall have a static control construction which gives adequate durability and performance.

2.1.1 Physical Characteristics

2.1.1.1 BROADLOOM CARPET

Carpet shall comply with the following:

- a. Carpet Construction: Tufted.
- b. Type: Broadloom 12 feet minimum usable carpet width.
- c. Pile Type: Multilevel loop Cut and loop.
- d. Pile Fiber: Commercial 100% branded (federally registered trademark) nylon continuous filament.
- e. Pile or Wire Height: Minimum 3/16 inch in accordance with ASTM D 418.
- f. Yarn Ply: Minimum 2.
- i. Finished Pile Yarn Weight: Minimum 26 ounces per square yard. This does not include weight of backings. Weight shall be determined in accordance with ASTM D 5848.
- j. Pile Density: Minimum 4000.
- k. Dye Method: Solution dyed or Yarn (or Skein) dyed.
- l. Backing Materials: Primary backing materials shall be those customarily used and accepted by the trade for each type of carpet. Secondary backing to suit project requirements shall be those customarily used and accepted by the trade for each type of carpet, except when a special unitary back designed for gluedown is provided.

2.1.2 Performance Requirements

- a. ARR (Appearance Retention Rating): Carpet shall be tested and have the minimum 3.0-3.5 (Heavy) ARR when tested in accordance with either the ASTM D 5252(Hexapod) or ASTM D 5417 (Vettermann) test methods using the number of cycles for short and long term tests as specified.
- b. Static Control: Static control shall be provided to permanently control static buildup to less than 3.5 kV when tested at 20 percent relative humidity and 70 degrees F in accordance with AATCC 134.
- c. Flammability and Critical Radiant Flux Requirements: Carpet shall comply with 16 CFR 1630. Carpet in corridors and exits shall have a minimum average critical radiant flux of 0.22 watts per square centimeter when tested in accordance with ASTM E 648.

d. Tuft Bind: Tuft bind force required to pull a tuft or loop free from carpet backing shall be a minimum 10 pound average force for loop pile.

e. Colorfastness to Crocking: Dry and wet crocking shall comply with AATCC 165 and shall have a Class 4 minimum rating on the AATCC Color Transference Chart for all colors.

f. Colorfastness to Light: Colorfastness to light shall comply with AATCC 16, Test Option E "Water-Cooled Xenon-Arc Lamp, Continuous Light" and shall have a minimum 4 grey scale rating after 40 hours.

g. Delamination Strength: Delamination strength for tufted carpet with a secondary back shall be minimum of 2.5 lbs./inch.

2.2 ADHESIVES AND CONCRETE PRIMER

Adhesives and concrete primers for installation of carpet shall be waterproof, nonflammable, meet local air-quality standards, and shall be as required by the carpet manufacturer. Seam adhesive shall be waterproof, nonflammable, and nonstaining as recommended by the carpet manufacturer.

2.3 MOLDING

Aluminum molding shall be a hammered surface, pinless clamp-down type, designed for the type of carpet being installed. Finish shall be natural color anodized. Floor flange shall be a minimum 1-1/2 inches wide and face shall be a minimum 5/8 inch wide Vinyl molding shall be heavy-duty and designed for the type of carpet being installed. Floor flange shall be a minimum 2 inches wide. Color shall be as indicated.

2.4 TAPE

Tape for seams shall be as recommended by the carpet manufacturer for the type of seam used in installation.

2.5 COLOR, TEXTURE, AND PATTERN

Color, texture, and pattern shall be as indicated.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Carpet shall not be installed on surfaces that are unsuitable and will prevent a proper installation. Holes, cracks, depressions, or rough areas shall be repaired using material recommended by the carpet or adhesive manufacturer. Floor shall be free of any foreign materials and swept broom clean. Before beginning work, subfloor shall be tested with glue and carpet to determine "open time" and bond.

3.2 MOISTURE AND ALKALINITY TESTS

Concrete slab shall be tested for moisture content and excessive alkalinity in accordance with CRI 104.

3.3 PREPARATION OF CONCRETE SUBFLOOR

Installation of the carpeting shall not commence until concrete substrate is at least 90 days old. The concrete surfaces shall be prepared in accordance with instructions of the carpet manufacturer. Type of concrete sealer, when required, shall be compatible with the carpet.

3.4 INSTALLATION

All work shall be performed by installers who are CFI certified (International Certified Floorcovering Installer Association), or manufacturer's approved installers. Installation shall be in accordance with the manufacturer's instructions and CRI 104. Edges of carpet meeting hard surface flooring shall be protected with molding; installation shall be in accordance with the molding manufacturer's instructions.

3.4.1 Broadloom Installation

Broadloom carpet shall be installed direct glue down and shall be smooth, uniform, and secure, with a minimum of seams. Seams shall be regular, unnoticeable, and treated with a seam adhesive. Side seams shall be run toward the light where practical and where such layout does not increase the number of seams. Breadths shall be installed parallel, with carpet pile in the same direction. Patterns shall be accurately matched. Cutouts, as at door jambs, columns and ducts shall be neatly cut and fitted securely. Seams at doorways shall be located parallel to and centered directly under doors. Seams shall not be made perpendicular to doors or at pivot points. Seams at changes in directions of corridors shall follow the wall line parallel to the carpet direction. Corridors with widths less than 6 feet shall have the carpet laid lengthwise down the corridors.

3.5 CLEANING AND PROTECTION

3.5.1 Cleaning

After installation of the carpet, debris, scraps, and other foreign matter shall be removed. Soiled spots and adhesive shall be removed from the face of the carpet with appropriate spot remover. Protruding face yarn shall be cut off and removed. Carpet shall be vacuumed clean.

3.5.2 Protection

The installed carpet shall be protected from soiling and damage with heavy, reinforced, nonstaining kraft paper, plywood, or hardboard sheets. Edges of kraft paper protection shall be lapped and secured to provide a continuous cover. Traffic shall be restricted for at least 45 hours. Protective covering shall be removed when directed by the Contracting Officer.

3.6 REMNANTS

Remnants remaining from the installation, consisting of scrap pieces more than 2 feet in dimension with more than 6 square feet total, shall be provided. Non-retained scraps shall be removed from site and recycled appropriately.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09836

MULTI-COLOR TEXTURED INTERIOR COATING

02/99

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALITY ASSURANCE
 - 1.3.1 Sample Panel Testing
- 1.4 PRODUCT DELIVERY, STORAGE, AND HANDLING
- 1.5 JOB CONDITIONS AND COORDINATION
 - 1.5.1 Temperature of Work Area
 - 1.5.2 Illumination
 - 1.5.3 Cleaning of Work Area
 - 1.5.4 Coordination

PART 2 PRODUCTS

- 2.1 MULTI-COLOR TEXTURED COATING MATERIAL
 - 2.1.1 Color, Pattern, and Texture
- 2.2 PRIMER

PART 3 EXECUTION

- 3.1 INSPECTION AND ACCEPTANCE OF SURFACES
- 3.2 PREPARATION OF SURFACES
 - 3.2.1 Cleaning of Surfaces
 - 3.2.2 Adjacent Surfaces
- 3.3 EQUIPMENT
- 3.4 APPLICATION
- 3.5 PROTECTION AND CLEAN UP

-- End of Section Table of Contents --

SAVH-09836 (02/99)

SECTION 09836

MULTI-COLOR TEXTURED INTERIOR COATING

02/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 1308 (1987) Effect of Household Chemicals on Clear and Pigmented Organic Finishes

FEDERAL STANDARD (FED-STD)

FED-STD 141 (Rev. C) Paint, Varnish, Lacquer and Related Materials; Methods of Inspection, Sampling, and Testing (Test Methods No. 6141.1 (Washability), No. 6142 (Scrub Resistance), and No. 6271.2 (Mildew Resistance))

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Manufacturer's Catalog Data

Furnish manufacturer's catalog data describing all materials, coating mixing and preparation, and substrate preparation and application instructions for each type of substrate. Data shall include evidence of performance of ASTM D 1308 and FED-STD 141 tests.

SD-04 Samples

Color Samples; G, RE

Color samples, minimum 6 inches square, of each color, texture, and pattern specified.

Sample Panel; G, RE

Prepare a mock-up area not to exceed 100 square feet for each coating on each type of substrate specified for approval. The approved mock-up shall establish a quality of work for the color, pattern, and texture, and will be used in judging the completed work. Mockup(s) shall be retained and protected in undisturbed condition until the work is completed and approved. Mockups may be a part of the completed work provided their locations are noted on the drawings.

SD-07 Certificates

Qualifications

Certification that the applicator is duly trained by the manufacturer in the application of the product to be installed and that the applicator has worked on installations of comparable type and size.

SD-10 Operation and Maintenance Data

Maintenance Data

Six copies of preprinted general maintenance and cleaning instructions for the finished coating(s).

1.3 QUALITY ASSURANCE

Each coat shall be inspected and accepted by the Contracting Officer prior to the application of succeeding coats. The Contracting Officer will determine whether full-coat coverage (film continuity) has been achieved and that the coating is pin-hole free.

1.3.1 Sample Panel Testing

After the coating system has dried but not less than 48 hours after application of the final coat, and in the presence of the Contracting Officer, the Contractor shall perform, at the direction of the Contracting Officer, one or both of the following tests:

a. Test No. 1: The Contractor shall wipe an area with a cloth saturated with mercurochrome solution. After the mercurochrome has dried, remove the resulting stain with liquid household cleaner. Any deficiencies in the coating film will be marked by residual mercurochrome.

b. Test No. 2: The Contractor shall draw a 6 inch line with a water-based felt pen across the coated surface and then wipe it off. Formation of small dots on the wall by the ink reveals that only the pattern coat had been applied.

1.4 PRODUCT DELIVERY, STORAGE, AND HANDLING

Deliver the products in the original containers, with seals unbroken, bearing factory-applied labels intact. Store the materials in the designated locations. Keep these areas well ventilated and observe precautions to avoid danger of fire. Provide approved type fire extinguishers. Maintain temperature of storage areas at not less than 50

degrees F. for at least 48 hours prior to application. Products shall not be exposed to freezing temperatures.

1.5 JOB CONDITIONS AND COORDINATION

1.5.1 Temperature of Work Area

Maintain temperature of work areas between 50 degrees F and 95 degrees F, 24 hours before the application of the material and until the finish has cured and set. Provide adequate ventilation to prevent mildew and improper drying. Prevent wide variation of temperature which might result in condensation on freshly coated surfaces.

1.5.2 Illumination

All applications of the coatings shall occur under the ambient illumination specified for the area.

1.5.3 Cleaning of Work Area

Before application is started in any area, broom clean and remove excessive dust from the area. After application is started, cleaning shall be done with vacuum cleaning equipment only.

1.5.4 Coordination

Schedule and coordinate the work with other trades. Application shall be scheduled after the completion of all other work which would damage the finished surfaces.

PART 2 PRODUCTS

2.1 MULTI-COLOR TEXTURED COATING MATERIAL

Multi-color tone-on-tone, textured, spray-on coating shall consist of two plastic copolymer coats incorporating a high resistance to fungus, mildew, alkalinity, soil and abrasion. The second coat shall be polychromatic, consisting of "beads" of copolymer pigments, suspended in a chemically treated aqueous solution, which rupture and splatter their contents upon contact with the surface. The coating shall have a flame spread of not more than 25 and a smoke developed rating of not more than 50 when tested in accordance with ASTM E 84. The coating system shall have been tested to and passed the tests specified in ASTM D 1308 and FED-STD 141, Test Methods 6141.1, 6142, and 6271. Provide ready mixed textured coating materials. Job tinting and mixing is not acceptable.

2.1.1 Color, Pattern, and Texture

Color, pattern, and texture of the background and pattern coats shall be as scheduled in Section 0900 BUILDING COLOR AND FINISH SCHEDULE. Sheen shall be eggshell.

2.2 PRIMER

Primer shall be as recommended by manufacturer.

PART 3 EXECUTION

3.1 INSPECTION AND ACCEPTANCE OF SURFACES

Follow manufacturer's instructions carefully and apply materials only to the surfaces which are acceptable. Application of the coating materials shall constitute acceptance of the surface, and shall obligate the Contractor for any repairs that are necessary to repair any unsatisfactory finish.

3.2 PREPARATION OF SURFACES

3.2.1 Cleaning of Surfaces

Clean, dry, and adequately protect from dampness the surfaces to be coated. Remove and neutralize mildew. Surfaces shall be smooth, even, true to plane, and free of any flaking, unsound coatings, foreign material, or defects which will adversely affect adhesion or appearance of the applied coating. Fill cracks.

3.2.2 Adjacent Surfaces

Prior to surface preparation and application operations, completely mask, remove, or otherwise adequately protect hardware, accessories, machined surfaces, plates, lighting fixtures, and similar items in contact with the coated surfaces that are not scheduled to receive the textured coating.

3.3 EQUIPMENT

Conventional air spray gun(s) with an internal mix air nozzle assembly shall be used. Airless atomization and external mix air nozzles are not permitted. The compressor shall be of adequate size to provide the necessary volume of air to the spray gun on a continuous basis.

3.4 APPLICATION

Application shall be in accordance with the manufacturer's printed recommendations and instructions, this section, and Section 09900 PAINTING, GENERAL and shall be the same as that used for the approved sample panel. The multi-color textured coating system shall consist of a primer coat followed by a high pressure sprayed-on covering coat (background coat) and a final low-pressure coat (pattern coat) to achieve the multi-color final appearance. Primer coat shall be the type recommended by the manufacturer and shall be applied in as many coats as required to produce a uniform appearance. The high pressure sprayed-on covering coat shall be applied with air pressure higher than fluid pressure in a continuous uniform film to completely cover the primer. The lower pressure or pattern coat shall be applied immediately after the background coat with an air pressure lower than the fluid pressure. The finished appearance shall be equivalent to the approved samples and mock-up(s), free from sags, voids, and excessive tactile texture, and be uniform in pattern and sheen. All touch up and repair work shall be accomplished prior to final acceptance.

3.5 PROTECTION AND CLEAN UP

Protect the adjacent work and materials by suitable covering or other method, during application of the coating. Provide temporary closure as required to confine the spray operation to prevent air pollution of the surrounding environment. Upon completion of the work, remove spots of coating material from floors, glass, and other surfaces. Repair and recoat damaged surfaces.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09840A

ACOUSTICAL WALL TREATMENT

11/01

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY AND STORAGE
- 1.4 WARRANTY

PART 2 PRODUCTS

- 2.1 ACOUSTICAL WALL PANEL SYSTEM FOR SIMULATOR ROOM

PART 3 EXECUTION

- 3.1 OMITTED
- 3.2 INSTALLATION
 - 3.2.1 Metal Wall Panels
- 3.3 CLEANING

-- End of Section Table of Contents --

SECTION 09840A

ACOUSTICAL WALL TREATMENT
11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 423	(1999a) Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Installation

Manufacturer's installation instructions and recommended cleaning instructions.

Acoustical Wall Panel System

Manufacturer's descriptive data and catalog cuts.

SD-07 Certificates

Acoustical Wall Panel System

Certificates of compliance from an independent laboratory accredited by the National Laboratory Accreditation Program of the National Institute of Standards. A label or listing from the testing laboratory will be acceptable evidence of compliance.

1.3 DELIVERY AND STORAGE

Materials delivered and placed in storage shall be stored with protection from the weather, humidity and temperature variations, dirt, dust, or other contaminants.

1.4 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period shall be provided.

PART 2 PRODUCTS

2.1 ACOUSTICAL WALL PANEL SYSTEM FOR SIMULATOR ROOM

Wall panels shall be a system of perforated metal panels with a backing of acoustical insulation. Panels shall be fabricated of thick aluminum or thick steel sheet, sized to fit indicated framing spacing, as long as possible and with profile indicated. Panel system shall include trim and accessories for a complete installation. panels shall be perforated with 1/8-inch diameter holes uniformly spaced with approximately 1075 holes per square foot. Panels and accessories shall receive a siliconized polyester baked enamel finish. Provide sound retarding insulation as specified in Section 09250 GYPSUM WALLBOARD, held in place with wire grid retainers as indicated.

- a. Fire rating for the complete composite system: Class A, 200 or less smoke density and flame spread less than 25, when tested in accordance with ASTM E 84.
- g. Noise Reduction Coefficient (NRC) Range: 0.80-0.90 ASTM C 423.

PART 3 EXECUTION

3.1 OMITTED

3.2 INSTALLATION

Panel installation shall be by personnel familiar with and normally engaged in installation of acoustical wall panels. Panels shall be assembled and constructed in place in accordance with the manufacturer's installation instructions.

3.2.1 Metal Wall Panels

Install metal wall panels horizontally across studs, using manufacturer's standard concealed fastening hardware and accessories. Install acoustic insulation behind panels as indicated.

3.3 CLEANING

Following installation, dirty or stained panel surfaces shall be cleaned in accordance with manufacturer's instructions and left free from defects. Panels that are damaged, discolored, or improperly installed shall be removed and new panels provided as directed.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09900

PAINTS AND COATINGS

02/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 APPLICATOR'S QUALIFICATIONS
 - 1.3.1 Contractor Qualification
- 1.4 QUALITY ASSURANCE
 - 1.4.1 Field Samples and Tests
 - 1.4.1.1 Sampling Procedure
 - 1.4.1.2 Testing Procedure
- 1.5 REGULATORY REQUIREMENTS
 - 1.5.1 Environmental Protection
 - 1.5.2 Lead Content
 - 1.5.3 Chromate Content
 - 1.5.4 Asbestos Content
 - 1.5.5 Mercury Content
 - 1.5.6 Silica
 - 1.5.7 Human Carcinogens
- 1.6 PACKAGING, LABELING, AND STORAGE
- 1.7 SAFETY AND HEALTH
 - 1.7.1 Safety Methods Used During Coating Application
 - 1.7.2 Toxic Materials
- 1.8 ENVIRONMENTAL CONDITIONS
 - 1.8.1 Coatings
- 1.9 COLOR SELECTION
- 1.10 LOCATION AND SURFACE TYPE TO BE PAINTED
 - 1.10.1 Painting Included
 - 1.10.1.1 Exterior Painting
 - 1.10.1.2 Interior Painting
 - 1.10.2 Painting Excluded
 - 1.10.3 Mechanical and Electrical Painting
 - 1.10.3.1 Fire Extinguishing Sprinkler Systems
 - 1.10.4 Omitted
 - 1.10.5 Omitted
 - 1.10.6 Definitions and Abbreviations
 - 1.10.6.1 Qualification Testing
 - 1.10.6.2 Batch Quality Conformance Testing
 - 1.10.6.3 Coating
 - 1.10.6.4 DFT or dft
 - 1.10.6.5 DSD
 - 1.10.6.6 EPP
 - 1.10.6.7 EXT
 - 1.10.6.8 INT
 - 1.10.6.9 micron / microns
 - 1.10.6.10 mil / mils
 - 1.10.6.11 mm
 - 1.10.6.12 MPI Gloss Levels
 - 1.10.6.13 MPI System Number

- 1.10.6.14 Paint
- 1.10.6.15 REX
- 1.10.6.16 RIN

PART 2 PRODUCTS

2.1 MATERIALS

PART 3 EXECUTION

- 3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED
- 3.2 OMITTED
- 3.3 OMITTED
- 3.4 SURFACE PREPARATION
- 3.5 PREPARATION OF METAL SURFACES
 - 3.5.1 New Ferrous Surfaces
 - 3.5.2 Final Ferrous Surface Condition:
 - 3.5.3 Galvanized Surfaces
 - 3.5.4 Non-Ferrous Metallic Surfaces
- 3.6 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE
 - 3.6.1 Concrete and Masonry
 - 3.6.2 Gypsum Board
- 3.7 PREPARATION OF WOOD SURFACES
 - 3.7.1 New Wood Surfaces
 - 3.7.2 Omitted
 - 3.7.3 Interior Wood Surfaces, Stain Finish
- 3.8 APPLICATION
 - 3.8.1 Coating Application
 - 3.8.2 Mixing and Thinning of Paints
 - 3.8.3 Two-Component Systems
 - 3.8.4 Coating Systems
- 3.9 COATING SYSTEMS FOR METAL
- 3.10 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES
- 3.11 COATING SYSTEMS FOR WOOD
- 3.12 PIPING IDENTIFICATION
- 3.13 INSPECTION AND ACCEPTANCE
- 3.14 PAINT TABLES
 - 3.14.1 EXTERIOR PAINT TABLES
 - 3.14.2 INTERIOR PAINT TABLES

-- End of Section Table of Contents --

UFGS-09900 (February 2002)

SECTION 09900

PAINTS AND COATINGS

02/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH TLV-BKLT (1991-1992) Threshold Limit Values (TLVs) for Chemical Substances and Physical Agents and Biological Exposure Indices (BEIs)

ACGIH TLV-DOC Documentation of Threshold Limit Values and Biological Exposure Indices

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 523 (1999) Standard Test Method for Specular Gloss

ASTM D 2092 (1995) Preparation of Zinc-Coated (Galvanized) Steel Surfaces for Painting

ASTM D 4263 (1983; R 1999) Indicating Moisture in Concrete by the Plastic Sheet Method

ASTM D 4444 (1998) Standard Test Methods for Use and Calibration of Hand-Held Moisture Meters

ASTM F 1869 (1998) Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride

CODE OF FEDERAL REGULATIONS (CFR)

29 CFR 1910.1000 Air Contaminants

FEDERAL STANDARDS (FED-STD)

FED-STD-313 (Rev. C) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities

MASTER PAINTERS INSTITUTE (MPI)

MPI 4 (2001) Interior/Exterior Latex Block Filler

MPI 7	(2001) Exterior Oil Wood Primer
MPI 10	(2001) Exterior Latex, Flat
MPI 11	(2001) Exterior Latex, Semi-Gloss
MPI 23	(2001) Surface Tolerant Metal Primer
MPI 39	(2001) Interior Latex-based Wood Primer
MPI 50	(2001) Interior Latex Primer Sealer
MPI 52	(2001) Interior Latex, Gloss Level 3
MPI 57	(2001) Interior Oil Modified Clear Urethane, Satin
MPI 79	(2001) Marine Alkyd Metal Primer
MPI 90	(2001) Interior Wood Stain, Semi-Transparent
MPI 94	(2001) Exterior Alkyd, Semi-Gloss
MPI 95	(2001) Fast Drying Metal Primer
MPI 107	(2001) Rust Inhibitive Primer (Water-Based)
MPI 110	(2001) Interior/Exterior High Performance Acrylic
MPI 134	(2001) Waterborne Galvanized Primer
MPI 139	(2001) High Performance Latex, White and Tints - MPI Gloss Level 3
MPI 141	(2001) High Performance Semigloss Latex, White and Tints - Gloss Level 5

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD-101	(Rev. B) Color Code for Pipelines and for Compressed Gas Cylinders
-------------	--

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS-EPP-SP01-01	(2001) Environmentally Preferable Product Specification for Architectural and Anti-Corrosive Paints
-----------------	---

STEEL STRUCTURES PAINTING COUNCIL (SSPC)

SSPC PA 1	(2000) Shop, Field, and Maintenance Painting
SSPC PA 3	(1995) Safety in Paint Application
SSPC VIS 3	(1993) Visual Standard for Power- and

	Hand-Tool Cleaned Steel (Standard Reference Photographs)
SSPC SP 1	(1982) Solvent Cleaning
SSPC SP 2	(1995) Hand Tool Cleaning
SSPC SP 3	(1995) Power Tool Cleaning
SSPC SP 6	(1994) Commercial Blast Cleaning
SSPC SP 7	(1994) Brush-Off Blast Cleaning

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

In keeping with the intent of Executive Order 13101, "Greening the Government through Waste Prevention, Recycling, and Federal Acquisition", products certified by SCS as meeting SCS-EPP-SP01-01 shall be given preferential consideration over registered products. Products that are registered shall be given preferential consideration over products not carrying any EPP designation.

SD-02 Shop Drawings

Piping identification

Submit color stencil codes

SD-03 Product Data

Coating

Manufacturer's Technical Data Sheets

SD-04 Samples

Color

Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated.

SD-07 Certificates

Applicator's qualifications

Qualification Testing laboratory for coatings

SD-08 Manufacturer's Instructions

Application instructions

Mixing

Detailed mixing instructions, minimum and maximum application temperature and humidity, potlife, and curing and drying times between coats.

Manufacturer's Material Safety Data Sheets

Submit manufacturer's Material Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

SD-10 Operation and Maintenance Data

Coatings:

Preprinted cleaning and maintenance instructions for all coating systems shall be provided.

1.3 APPLICATOR'S QUALIFICATIONS

1.3.1 Contractor Qualification

Submit the name, address, telephone number, FAX number, and e-mail address of the contractor that will be performing all surface preparation and coating application. Submit evidence that key personnel have successfully performed surface preparation and application of coatings on a minimum of three similar projects within the past three years. List information by individual and include the following:

- a. Name of individual and proposed position for this work.
- b. Information about each previous assignment including:

Position or responsibility

Employer (if other than the Contractor)

Name of facility owner

Mailing address, telephone number, and telex number (if non-US) of facility owner

Name of individual in facility owner's organization who can be contacted as a reference

Location, size and description of structure

Dates work was carried out

Description of work carried out on structure

1.4 QUALITY ASSURANCE

1.4.1 Field Samples and Tests

The Contracting Officer may choose up to two coatings that have been delivered to the site to be tested at no cost to the Government. Take samples of each chosen product as specified in the paragraph "Sampling Procedures." Test each chosen product as specified in the paragraph "Testing Procedure." Products which do not conform, shall be removed from the job site and replaced with new products that conform to the referenced specification. Testing of replacement products that failed initial testing shall be at no cost to the Government.

1.4.1.1 Sampling Procedure

The Contracting Officer will select paint at random from the products that have been delivered to the job site for sample testing. The Contractor shall provide one quart samples of the selected paint materials. The samples shall be taken in the presence of the Contracting Officer, and labeled, identifying each sample. Provide labels in accordance with the paragraph "Packaging, Labeling, and Storage" of this specification.

1.4.1.2 Testing Procedure

Provide Batch Quality Conformance Testing for specified products, as defined by and performed by MPI. As an alternative to Batch Quality Conformance testing, the Contractor may provide Qualification Testing for specified products above to the appropriate MPI product specification, using the third-party laboratory approved under the paragraph "Qualification Testing" laboratory for coatings. The qualification testing lab report shall include the backup data and summary of the test results. The summary shall list all of the reference specification requirements and the result of each test. The summary shall clearly indicate whether the tested paint meets each test requirement. Note that Qualification Testing may take 4 to 6 weeks to perform, due to the extent of testing required.

Submit name, address, telephone number, FAX number, and e-mail address of the independent third party laboratory selected to perform testing of coating samples for compliance with specification requirements. Submit documentation that laboratory is regularly engaged in testing of paint samples for conformance with specifications, and that employees performing testing are qualified. If the Contractor chooses MPI to perform the Batch Quality Conformance testing, the above submittal information is not required, only a letter is required from the Contractor stating that MPI will perform the testing.

1.5 REGULATORY REQUIREMENTS

1.5.1 Environmental Protection

In addition to requirements specified elsewhere for environmental protection, provide coating materials that conform to the restrictions of the local Air Pollution Control District and regional jurisdiction. Notify Contracting Officer of any paint specified herein which fails to conform.

1.5.2 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.5.3 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.5.4 Asbestos Content

Materials shall not contain asbestos.

1.5.5 Mercury Content

Materials shall not contain mercury or mercury compounds.

1.5.6 Silica

Abrasive blast media shall not contain free crystalline silica.

1.5.7 Human Carcinogens

Materials shall not contain ACGIH TLV-BKLT and ACGIH TLV-DOC confirmed human carcinogens (A1) or suspected human carcinogens (A2).

1.6 PACKAGING, LABELING, AND STORAGE

Paints shall be in sealed containers that legibly show the contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Pigmented paints shall be furnished in containers not larger than 5 gallons. Paints and thinners shall be stored in accordance with the manufacturer's written directions, and as a minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at temperatures between 40 to 95 degrees F.

1.7 SAFETY AND HEALTH

Apply coating materials using safety methods and equipment in accordance with the following:

Work shall comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01525, "Safety Requirements" and in Appendix A of COE EM-385-1-1. The Activity Hazard Analysis shall include analyses of the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.7.1 Safety Methods Used During Coating Application

Comply with the requirements of SSPC PA 3.

1.7.2 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

- a. The applicable manufacturer's Material Safety Data Sheets (MSDS) or local regulation.
- b. 29 CFR 1910.1000.
- c. ACGIH TLV-BKLT, threshold limit values.

1.8 ENVIRONMENTAL CONDITIONS

1.8.1 Coatings

Do not apply coating when air or substrate conditions are:

- a. Less than 5 degrees F above dew point;

- b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Under no circumstances shall application conditions exceed manufacturer recommendations.

1.9 COLOR SELECTION

Colors of finish coats shall be as indicated or specified. Where not indicated or specified, colors shall be selected by the Contracting Officer. Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors approximate colors indicated and the product conforms to specified requirements.

Tint each coat progressively darker to enable confirmation of the number of coats.

Color, texture, and pattern of wall coating systems shall be in accordance with Section 09000 BUILDING COLOR AND FINISH SCHEDULE.

1.10 LOCATION AND SURFACE TYPE TO BE PAINTED

1.10.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

- a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.
- b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.
- c. Existing coated surfaces that are damaged during performance of the work.

1.10.1.1 Exterior Painting

Includes new surfaces of the building and appurtenances as indicated. Also included are existing coated surfaces made bare by cleaning operations.

1.10.1.2 Interior Painting

Includes new surfaces of the building and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

- a. Exposed columns, girders, beams, joists, and metal deck; and
- b. Other contiguous surfaces.

1.10.2 Painting Excluded

Do not paint the following unless indicated otherwise.

- a. Surfaces concealed and made inaccessible by panelboards, fixed ductwork, machinery, and equipment fixed in place.
- b. Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic spaces, crawl spaces, elevator shafts and chases.
- c. Steel to be embedded in concrete.
- d. Copper, stainless steel, aluminum, brass, and lead except existing coated surfaces.
- e. Hardware, fittings, and other factory finished items.

1.10.3 Mechanical and Electrical Painting

Includes field coating of interior and exterior new surfaces.

- a. Where a space or surface is indicated to be painted, include the following items unless indicated otherwise.
 - (1) Exposed piping, conduit, and ductwork;
 - (2) Supports, hangers, air grilles, and registers;
 - (3) Miscellaneous metalwork and insulation coverings.
- b. Do not paint the following, unless indicated otherwise:
 - (1) New zinc-coated, aluminum, and copper surfaces under insulation
 - (2) New aluminum jacket on piping
 - (3) New interior ferrous piping under insulation.

1.10.3.1 Fire Extinguishing Sprinkler Systems

Clean, pretreat, prime, and paint new fire extinguishing sprinkler systems including valves, piping, conduit, hangers, supports, miscellaneous metalwork, and accessories. Apply coatings to clean, dry surfaces, using clean brushes. Clean the surfaces to remove dust, dirt, rust, and loose mill scale. Immediately after cleaning, provide the metal surfaces with one coat primer per schedules. Shield sprinkler heads with protective covering while painting is in progress. Upon completion of painting, remove protective covering from sprinkler heads. Remove sprinkler heads which have been painted and replace with new sprinkler heads. Provide primed surfaces with the following:

- a. Piping in Unfinished Areas: Provide primed surfaces with one coat of red alkyd gloss enamel applied to a minimum dry film thickness of 1.0 mil in attic spaces, spaces above suspended ceilings, crawl spaces, pipe chases, mechanical equipment room, and spaces where walls or ceiling are not painted or not constructed of a prefinished material. In lieu of red enamel finish coat, provide piping with 2 inch wide red enamel bands or self-adhering red plastic bands spaced at maximum of 20 foot intervals.
- b. Piping in Finished Areas: Provide primed surfaces with two coats

of paint to match adjacent surfaces, except provide valves and operating accessories with one coat of red alkyd gloss enamel applied to a minimum dry film thickness of 1.0 mil. Provide piping with 2 inch wide red enamel bands or self-adhering red plastic bands spaced at maximum of 20 foot intervals throughout the piping systems.

1.10.4 Omitted

1.10.5 Omitted

1.10.6 Definitions and Abbreviations

1.10.6.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.10.6.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing shall only be accomplished by MPI testing lab.

1.10.6.3 Coating

A film or thin layer applied to a base material called a substrate. A coating may be a metal, alloy, paint, or solid/liquid suspensions on various substrates (metals, plastics, wood, paper, leather, cloth, etc.). They may be applied by electrolysis, vapor deposition, vacuum, or mechanical means such as brushing, spraying, calendaring, and roller coating. A coating may be applied for aesthetic or protective purposes or both. The term "coating" as used herein includes emulsions, enamels, stains, varnishes, sealers, epoxies, and other coatings, whether used as primer, intermediate, or finish coat. The terms paint and coating are used interchangeably.

1.10.6.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.10.6.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five (5) levels are generically defined under the Assessment sections in the MPI Maintenance Repainting Manual.

1.10.6.6 EPP

Environmentally Preferred Products, a standard for determining environmental preferability in support of Executive Order 13101.

1.10.6.7 EXT

MPI short term designation for an exterior coating system.

1.10.6.8 INT

MPI short term designation for an interior coating system.

1.10.6.9 micron / microns

The metric measurement for 0.001 mm or one/one-thousandth of a millimeter.

1.10.6.10 mil / mils

The English measurement for 0.001 in or one/one-thousandth of an inch, equal to 25.4 microns or 0.0254 mm.

1.10.6.11 mm

The metric measurement for millimeter, 0.001 meter or one/one-thousandth of a meter.

1.10.6.12 MPI Gloss Levels

MPI system of defining gloss. Seven (7) gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units @ 60 degrees	Units @ 85 degrees
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	
G6	Gloss	70 to 85	
G7	High Gloss		

Gloss is tested in accordance with ASTM D 523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.10.6.13 MPI System Number

The MPI coating system number in each Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN). The Division number follows the CSI Master Format.

1.10.6.14 Paint

See Coating definition.

1.10.6.15 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.10.6.16 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit manufacturer's technical data sheets for specified coatings and solvents.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect, hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, workmen skilled in the trades involved shall reinstall removed items. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 OMITTED

3.3 OMITTED

3.4 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Oil and grease shall be removed prior to mechanical cleaning. Cleaning shall be programmed so that dust and other contaminants will not fall on wet, newly painted surfaces. Exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, shall be spot-primed with a suitable corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas.

3.5 PREPARATION OF METAL SURFACES

3.5.1 New Ferrous Surfaces

- a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances:
Solvent clean or detergent wash in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2, SSPC SP 3, SSPC SP 6, or .
Brush-off blast remaining surface in accordance with SSPC SP 7;
Shop-coated ferrous surfaces shall be protected from corrosion by treating and touching up corroded areas immediately upon detection.

3.5.2 Final Ferrous Surface Condition:

For tool cleaned surfaces, the requirements are stated in SSPC SP 2 and SSPC SP 3. As a visual reference, cleaned surfaces shall be similar to

photographs in SSPC VIS 3.

3.5.3 Galvanized Surfaces

- a. New or Existing Galvanized Surfaces With Only Dirt and Zinc Oxidation Products: Clean with solvent, steam, or non-alkaline detergent solution in accordance with SSPC SP 1. If the galvanized metal has been passivated or stabilized, the coating shall be completely removed by brush-off abrasive blast. New galvanized steel to be coated shall not be "passivated" or "stabilized" If the absence of hexavalent stain inhibitors is not documented, test as described in ASTM D 2092, Appendix X2, and remove by one of the methods described therein.

3.5.4 Non-Ferrous Metallic Surfaces

Aluminum and aluminum-alloy, lead, copper, and other nonferrous metal surfaces.

- a. Surface Cleaning: Solvent clean in accordance with SSPC SP 1 and wash with mild non-alkaline detergent to remove dirt and water soluble contaminants.

3.6 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE

3.6.1 Concrete and Masonry

- a. Curing: Concrete, stucco and masonry surfaces shall be allowed to cure at least 30 days before painting, except concrete slab on grade, which shall be allowed to cure 90 days before painting.
- b. Surface Cleaning: Remove the following deleterious substances.
 - (1) Dirt, Grease, and Oil: Wash new surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, and 4 quarts of warm water. Then rinse thoroughly with fresh water. For large areas, water blasting may be used.
 - (2) Fungus and Mold: Wash new surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, 1 quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.
 - (3) Loose Particles: Remove by wire brushing.
 - (4) Efflorescence: Remove by scraping or wire brushing followed by washing with a 5 to 10 percent by weight aqueous solution of hydrochloric (muriatic) acid. Do not allow acid to remain on the surface for more than five minutes before rinsing with fresh water. Do not acid clean more than 4 square feet of surface, per workman, at one time.
- c. Cosmetic Repair of Minor Defects: Repair or fill mortar joints and minor defects, including but not limited to spalls, in accordance with manufacturer's recommendations and prior to coating application.
- d. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not to surfaces with droplets of water. Do not

apply epoxies to damp vertical surfaces as determined by ASTM D 4263 or horizontal surfaces that exceed 3 lbs of moisture per 1000 square feet in 24 hours as determined by ASTM F 1869. In all cases follow manufacturers recommendations. Allow surfaces to cure a minimum of 30 days before painting.

3.6.2 Gypsum Board

- a. Surface Cleaning: Gypsum board shall be dry. Remove loose dirt and dust by brushing with a soft brush, rubbing with a dry cloth, or vacuum-cleaning prior to application of the first coat material. A damp cloth or sponge may be used if paint will be water-based.
- b. Repair of Minor Defects: Prior to painting, repair joints, cracks, holes, surface irregularities, and other minor defects with patching plaster or spackling compound and sand smooth.
- c. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not surfaces with droplets of water. Do not apply epoxies to damp surfaces as determined by ASTM D 4263. New plaster to be coated shall have a maximum moisture content of 8 percent, when measured in accordance with ASTM D 4444, Method A, unless otherwise authorized. In addition to moisture content requirements, allow new plaster to age a minimum of 30 days before preparation for painting.

3.7 PREPARATION OF WOOD SURFACES

3.7.1 New Wood Surfaces

- a. Wood surfaces shall be cleaned of foreign matter.

Surface Cleaning: Surfaces shall be free from dust and other deleterious substances and in a condition approved by the Contracting Officer prior to receiving paint or other finish. Do not use water to clean uncoated wood.
- b. Moisture content of the wood shall not exceed 12 percent as measured by a moisture meter in accordance with ASTM D 4444, Method A, unless otherwise authorized.
- c. Wood surfaces adjacent to surfaces to receive water-thinned paints shall be primed and/or touched up before applying water-thinned paints.
- d. Cracks and Nailheads: Set and putty stop nailheads and putty cracks after the prime coat has dried.
- e. Cosmetic Repair of Minor Defects:
 - (1) Knots and Resinous Wood: Prior to application of coating, cover knots and stains with two or more coats of 3-pound-cut shellac varnish, plasticized with 5 ounces of castor oil per gallon. Scrape away existing coatings from knotty areas, and sand before treating. Prime before applying any putty over shellacked area.
 - (2) Open Joints and Other Openings: Fill with whiting putty, linseed oil putty. Sand smooth after putty has dried.

(3) Checking: Where checking of the wood is present, sand the surface, wipe and apply a coat of pigmented orange shellac. Allow to dry before paint is applied.

- g. Prime Coat For New Exterior Surfaces: Prime coat trim before wood becomes dirty, warped.

3.7.2 Omitted

3.7.3 Interior Wood Surfaces, Stain Finish

Interior wood surfaces to receive stain shall be sanded. Oak and other open-grain wood to receive stain shall be given a coat of wood filler not less than 8 hours before the application of stain; excess filler shall be removed and the surface sanded smooth.

3.8 APPLICATION

3.8.1 Coating Application

Painting practices shall comply with applicable federal, state and local laws enacted to insure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

At the time of application, paint shall show no signs of deterioration. Uniform suspension of pigments shall be maintained during application.

Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Rollers for applying paints and enamels shall be of a type designed for the coating to be applied and the surface to be coated.

Paints, except water-thinned types, shall be applied only to surfaces that are completely free of moisture as determined by sight or touch.

Thoroughly work coating materials into joints, crevices, and open spaces. Special attention shall be given to insure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

Each coat of paint shall be applied so dry film shall be of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Hiding shall be complete.

Touch up damaged coatings before applying subsequent coats. Interior areas shall be broom clean and dust free before and during the application of coating material.

Apply paint to new fire extinguishing sprinkler systems including valves, piping, conduit, hangers, supports, miscellaneous metal work, and accessories. Shield sprinkler heads with protective coverings while painting is in progress. Remove sprinkler heads which have been painted and replace with new sprinkler heads. For piping in unfinished spaces, provide primed surfaces with one coat of red alkyd gloss enamel to a minimum dry film thickness of 1.0 mil. Unfinished spaces include attic spaces, spaces above suspended ceilings, crawl spaces, pipe chases,

mechanical equipment room, and space where walls or ceiling are not painted or not constructed of a prefinished material. For piping in finished areas, provide prime surfaces with two coats of paint to match adjacent surfaces, except provide valves and operating accessories with one coat of red alkyd gloss enamel. Upon completion of painting, remove protective covering from sprinkler heads.

- a. **Drying Time:** Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.
- b. **Primers, and Intermediate Coats:** Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Each coat shall cover surface of preceding coat or surface completely, and there shall be a visually perceptible difference in shades of successive coats.
- c. **Finished Surfaces:** Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.
- d. **Thermosetting Paints:** Topcoats over thermosetting paints (epoxies and urethanes) should be applied within the overcoating window recommended by the manufacturer.

3.8.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. The written permission shall include quantities and types of thinners to use.

When thinning is allowed, paints shall be thinned immediately prior to application with not more than 0.125 L of suitable thinner per liter. The use of thinner shall not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning shall not cause the paint to exceed limits on volatile organic compounds. Paints of different manufacturers shall not be mixed.

3.8.3 Two-Component Systems

Two-component systems shall be mixed in accordance with manufacturer's instructions. Any thinning of the first coat to ensure proper penetration and sealing shall be as recommended by the manufacturer for each type of substrate.

3.8.4 Coating Systems

- a. **Systems by Substrates:** Apply coatings that conform to the respective specifications listed in the following Tables:

Table

Division 3. Exterior Concrete Paint Table

Division 5. Exterior Metal, Ferrous and Non-Ferrous Paint Table

Division 3. Interior Concrete Paint Table

Division 4. Interior Concrete Masonry Units Paint Table

Division 5. Interior Metal, Ferrous and Non-Ferrous Paint Table

Division 6. Interior Wood Paint Table

Division 9: Interior Gypsum Board

Paint Table

- b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise in the Tables. Coating thickness where specified, refers to the minimum dry film thickness.
- c. Coatings for Surfaces Not Specified Otherwise: Coat surfaces which have not been specified, the same as surfaces having similar conditions of exposure.
- d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:
 - (1) One coat of primer.
 - (2) One coat of undercoat or intermediate coat.
 - (3) One topcoat to match adjacent surfaces.

3.9 COATING SYSTEMS FOR METAL

Apply coatings of Tables in Division 5 for Exterior and Interior.

- a. Apply specified ferrous metal primer on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.
- b. Inaccessible Surfaces: Prior to erection, use one coat of specified primer on metal surfaces that will be inaccessible after erection.
- c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.
- d. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat, but shall be overcoated with the specified ferrous-metal primer prior to application of finish coats.
- e. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.10 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES

Apply coatings of Tables in Division 3, 4 and 9 for Exterior and Interior.

3.11 COATING SYSTEMS FOR WOOD

STEEL / FERROUS SURFACES

Primer:	Intermediate:	Topcoat:
MPI 79	MPI 94	MPI 94
System DFT: 5.25 mils		

EXTERIOR GALVANIZED SURFACES

C. New Galvanized surfaces:

- Waterborne Primer / Latex
MPI EXT 5.3H-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 134 MPI 11 MPI 11
System DFT: 4.5 mils

EXTERIOR SURFACES, OTHER METALS (NON-FERROUS)

D. Aluminum, aluminum alloy and other miscellaneous non-ferrous metal items not otherwise specified except hot metal surfaces, roof surfaces, and new prefinished equipment. Match surrounding finish:

- Alkyd
MPI EXT 5.4F-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 95 MPI 94 MPI 94
System DFT: 5 mils

E. Surfaces adjacent to painted surfaces; Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports, exposed copper piping, and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment. Match surrounding finish:

- Waterborne Light Industrial Coating
MPI EXT 5.1C-G3(Eggshell)
Primer: Intermediate: Topcoat:
MPI 79 MPI 110-G3 MPI 110-G3
System DFT: 5 mils

DIVISION 6: EXTERIOR WOOD; DRESSED LUMBER, PAINT TABLE

A. New Dressed lumber, Wood and plywood, trim, not otherwise specified:

- Latex
MPI EXT 6.3A-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 7 MPI 11 MPI 11
System DFT: 5 mils

3.14.2 INTERIOR PAINT TABLES

DIVISION 3: INTERIOR CONCRETE PAINT TABLE

A. New and uncoated existing concrete, vertical surfaces, not specified otherwise:

DIVISION 3: INTERIOR CONCRETE PAINT TABLE

1. Latex

New; MPI INT 3.1A-G3 (Eggshell) / Existing; MPI RIN 3.1A-G3 (Eggshell)
 Primer: Intermediate: Topcoat:
 MPI 50 MPI 52 MPI 52
 System DFT: 4 mils

DIVISION 4: INTERIOR CONCRETE MASONRY UNITS PAINT TABLE

A. New Concrete masonry:

1. MPI INT 4.2D-G5 (Semigloss)
 Filler Primer: Intermediate: Topcoat:
 MPI 4 N/A MPI 141 MPI 141
 System DFT: 11 mils

Fill all holes in masonry surface

DIVISION 5: INTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

INTERIOR STEEL / FERROUS SURFACES

- A. Metal, Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports, Surfaces adjacent to painted surfaces (Match surrounding finish), and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment:

1. High Performance Architectural Latex

MPI INT 5.1R-G5 (Semigloss)
 Primer: Intermediate: Topcoat:
 MPI 79 MPI 141 MPI 141
 System DFT: 5 mils

- B. Miscellaneous non-ferrous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment. Match surrounding finish:

1. High Performance Architectural Latex

MPI INT 5.4F-G5 (Semigloss)
 Primer: Intermediate: Topcoat:
 MPI 95 MPI 141 MPI 141
 System DFT: 5 mils

DIVISION 6: INTERIOR WOOD PAINT TABLE

A. New Wood not otherwise specified:

1. High Performance Architectural Latex
 MPI INT 6.4S-G3 (Eggshell)
 Primer: Intermediate: Topcoat:
 MPI 39 MPI 139 MPI 139
 System DFT: 4.5 mils

DIVISION 6: INTERIOR WOOD PAINT TABLE

B. New Wood and Plywood, except floors; natural finish or stained:

1. Natural finish, oil-modified polyurethane

New; MPI INT 6.4J-G4

Primer:	Intermediate:	Topcoat:
MPI 57	MPI 57	MPI 57
System DFT: 4 mils		

2. Stained, oil-modified polyurethane

New; MPI INT 6.4E-G4

Stain:	Primer:	Intermediate:	Topcoat:
MPI 90	MPI 57	MPI 57	MPI 57
System DFT: 4 mils			

C. New Wood Doors; Natural Finish or Stained:

1. Natural finish, oil-modified polyurethane

New; MPI INT 6.3K-G4

Primer:	Intermediate:	Topcoat:
MPI 57	MPI 57	MPI 57
System DFT: 4 mils		

Note: Sand between all coats per manufacturers recommendations.

2. Stained, oil-modified polyurethane

New; MPI INT 6.3E-G4

Stain:	Primer:	Intermediate:	Topcoat:
MPI 90	MPI 57	MPI 57	MPI 57
System DFT: 4 mils			

Note: Sand between all coats per manufacturers recommendations.

DIVISION 9: INTERIOR PLASTER, GYPSUM BOARD, TEXTURED SURFACES PAINT TABLE

A. New Wallboard not otherwise specified:

1. Latex

New; MPI INT 9.2A-G3 (Eggshell) / Existing; RIN 9.2A-G3 (Eggshell)

Primer:	Intermediate:	Topcoat:
MPI 50	MPI 52	MPI 52
System DFT: 4 mils		

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 10 - SPECIALTIES

SECTION 10100A

VISUAL COMMUNICATIONS SPECIALTIES

07/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 GENERAL REQUIREMENTS
- 1.3 SUBMITTALS
- 1.4 DELIVERY, STORAGE AND HANDLING
- 1.5 WARRANTY

PART 2 PRODUCTS

- 2.1 COLOR
- 2.2 MATERIALS
 - 2.2.1 Porcelain Enamel
 - 2.2.2 Omitted
 - 2.2.3 Omitted
 - 2.2.4 Omitted
 - 2.2.5 Omitted
 - 2.2.6 Aluminum
- 2.3 OMITTED
- 2.4 MARKERBOARD
- 2.5 OMITTED
- 2.6 OMITTED
- 2.7 OMITTED
- 2.8 OMITTED
- 2.9 OMITTED
- 2.10 PROJECTION SCREEN

PART 3 EXECUTION

- 3.1 OMITTED
- 3.2 INSTALLATION
- 3.3 CLEANING

-- End of Section Table of Contents --

UFGS-10100A (July 2002)

SECTION 10100A

VISUAL COMMUNICATIONS SPECIALTIES

07/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM B 221 (2000) Aluminum and Aluminum-Alloy
Extruded Bars, Rods, Wire, Profiles, and
Tubes

1.2 GENERAL REQUIREMENTS

The term visual display board when used herein includes presentation boards, marker boards, tackboards, board cases, display track system and horizontal sliding units. Visual display boards shall be from manufacturer's standard product line.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Visual Display Boards
Projection Screen

Manufacturer's descriptive data and catalog cuts.
Manufacturer's installation instructions, and cleaning and
maintenance instructions.

07 Certificates

Visual Display Boards

Certificate of compliance signed by Contractor attesting that
visual display boards conform to the requirements specified.

1.4 DELIVERY, STORAGE AND HANDLING

Materials shall be delivered to the building site in the manufacturer's original unopened containers and shall be stored in a clean dry area with

temperature maintained above 50 degrees F. Materials shall be stacked according to manufacturer's recommendations. Visual display boards shall be allowed to acclimate to the building temperature for 24 hours prior to installation.

1.5 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period shall be provided.

PART 2 PRODUCTS

2.1 COLOR

Finish colors for required items shall be as specified in the drawings.

2.2 MATERIALS

2.2.1 Porcelain Enamel

Marker board writing surface shall be composed of porcelain enamel fused to a nominal 28 gauge (0.0149 inches) thick steel, laminated to a minimum 1/4 inch thick core material with a steel or foil backing sheet. Writing surface shall be capable of supporting paper by means of magnets. Marker board surface for display track system may be a powder paint dry erase surface adhered to a nominal 18 gauge (0.0478 inches) thick steel.

2.2.2 Omitted

2.2.3 Omitted

2.2.4 Omitted

2.2.5 Omitted

2.2.6 Aluminum

Aluminum frame extrusions shall be alloy 6063-T5 or 6063-T6, conform to ASTM B 221, and be a minimum 0.06 inches thick. Exposed aluminum shall have an anodized, satin finish. Straight, single lengths shall be used wherever possible. Joints shall be kept to a minimum. Corners shall be mitered and shall have a hairline closure.

2.3 OMITTED

2.4 MARKERBOARD

Markerboard shall have a porcelain enamel writing surface and a chalktray. Markerboard shall be a factory assembled unit complete in one piece, without joints whenever possible. When markerboard dimensions require delivery in separate sections, components shall be prefit at the factory, disassembled for delivery and jointed at the site. Frame shall be aluminum. Chalktray shall be the same material as the frame and extend the full length of the liquid markerboard. The markerboard shall not include a map rail Dry erase markings shall be removable with a felt eraser or dry cloth without ghosting. Each unit shall come complete with an eraser and four different color compatible dry erase markers. The size shall be as shown in the drawings.

2.5 OMITTED

2.6 OMITTED

2.7 OMITTED

2.8 OMITTED

2.9 OMITTED

2.10 PROJECTION SCREEN

Recessed mount motorized projection screen shall have 120V motor that is lubricated for life, quick reversal type, has overload protector, integral gears, and preset accessible limit switches. Recessed mount projection screens shall have an operable closure door and access panel. Screen shall be flame retardant, mildew resistant, and white matte with black masking borders. Bottom of screen fabric shall be weighted with metal rod. Roller shall be a rigid metal at least 3 inches in diameter mounted on sound absorbing supports. Motor will be end mounted or motor-in-roller design. Screen shall have a 3 position control switch to stop or reverse screen at any point. The switch shall be installed in a flush electrical box with cover plate, location(s) as shown on the electrical drawings. All conduit and wiring from the control switch to the projection screen shall be furnished and installed by the Contractor. Ceiling recessed case shall be extruded aluminum or wood with metal lined motor compartment.. Screen shall be UL listed. The size shall be as shown in the drawings.

PART 3 EXECUTION

3.1 OMITTED

3.2 INSTALLATION

Installation and assembly shall be in accordance with manufacturer's printed instructions. Concealed fasteners shall be used. Visual display boards shall be attached to the walls with suitable devices to anchor each unit. The Contractor shall furnish and install trim items, accessories and miscellaneous items in total, including but not limited to hardware, grounds, clips, backing materials, adhesives, brackets, and anchorages incidental to or necessary for a sound, secure, complete and finished installation. Installation shall not be initiated until completion of room painting and finishing operations. Visual display boards shall be installed in locations and at mounting heights indicated. Visual display boards shall be installed level and plumb, and if applicable doors shall be aligned and hardware shall be adjusted. Damaged units shall be repaired or replaced by the Contractor as directed by the Contracting Officer.

3.3 CLEANING

Writing surfaces shall be cleaned in accordance with manufacturer's instructions.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 10 - SPECIALTIES

SECTION 10201N

METAL WALL LOUVERS

09/99

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, STORAGE, AND PROTECTION

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Galvanized Steel Sheet
 - 2.1.2 Aluminum Sheet
 - 2.1.3 Extruded Aluminum
- 2.2 METAL WALL LOUVERS
 - 2.2.1 Extruded Aluminum Louvers
 - 2.2.2 Mullions and Mullion Covers
 - 2.2.3 Screens and Frames
- 2.3 OMITTED
- 2.4 FASTENERS AND ACCESSORIES
- 2.5 FINISHES
 - 2.5.1 Aluminum
 - 2.5.1.1 Anodic Coating

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Wall Louvers
 - 3.1.2 Screens and Frames
- 3.2 PROTECTION FROM CONTACT OF DISSIMILAR MATERIALS
 - 3.2.1 Omitted
 - 3.2.2 Aluminum
 - 3.2.3 Metal
 - 3.2.4 Wood

-- End of Section Table of Contents --

UFGS-10201N (September 1999)

SECTION 10201N

METAL WALL LOUVERS

09/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

THE ALUMINUM ASSOCIATION, INCORPORATED (AA)

AA 45 (1980) Aluminum Finishes

AIR MOVEMENT AND CONTROL ASSOCIATION, INC. (AMCA)

AMCA 500 (1991) Louvers, Dampers and Shutters

AMCA 511 (1991) Certified Ratings Program for Air Control Devices

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 653/A 653M (1998) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM B 209 (1996) Aluminum and Aluminum-Alloy Sheet and Plate

ASTM B 221 (1996) Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Wall louvers

Show all information necessary for fabrication and installation of louvers. Indicate materials, sizes, thicknesses, fastenings, and profiles.

1.3 DELIVERY, STORAGE, AND PROTECTION

Deliver materials to the site in an undamaged condition. Carefully store materials off the ground to provide proper ventilation, drainage, and protection against dampness. Louvers shall be free from nicks, scratches, and blemishes. Replace defective or damaged materials with new.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Galvanized Steel Sheet

ASTM A 653/A 653M, coating designation G90.

2.1.2 Aluminum Sheet

ASTM B 209, alloy 3003 or 5005 with temper as required for forming.

2.1.3 Extruded Aluminum

ASTM B 221, alloy 6063-T5 or -T52.

2.2 METAL WALL LOUVERS

Weather resistant type, with bird screens and made to withstand a wind load of not less than 30 pounds per square foot. Wall louvers shall bear the AMCA certified ratings program seal for air performance and water penetration in accordance with AMCA 500 and AMCA 511. The rating shall show a water penetration of 0.20 or less ounce per square foot of free area at a free velocity of 800 feet per minute, and a free area of not less than 50 percent.

2.2.1 Extruded Aluminum Louvers

Fabricated of extruded 6063-T5 or -T52 aluminum with a wall thickness of not less than 0.081 inch.

2.2.2 Mullions and Mullion Covers

Same material and finish as louvers. Provide mullions where indicated. Provide mullions covers on both faces of joints between louvers.

2.2.3 Screens and Frames

For aluminum louvers, provide 1/2 inch square mesh, 14 or 16 gage aluminum or 1/4 inch square mesh, 16 gage aluminum bird screening. Mount screens in removable, rewirable frames of same material and finish as the louvers.

2.3 OMITTED

2.4 FASTENERS AND ACCESSORIES

Provide stainless steel screws and fasteners for aluminum louvers and zinc-coated or stainless steel screws and fasteners for steel louvers. Provide other accessories as required for complete and proper installation.

2.5 FINISHES

2.5.1 Aluminum

Provide factory-applied anodic coating.

2.5.1.1 Anodic Coating

Clean exposed aluminum surfaces and apply an anodized finish conforming to AA 45 Designation System for Aluminum Finishes, integral color anodized, M10C22A32, Architectural Class II, color as indicated.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Wall Louvers

Install using stops or moldings, flanges, strap anchors, or jamb fasteners as appropriate for the wall construction and in accordance with manufacturer's recommendations.

3.1.2 Screens and Frames

Attach frames to louvers with screws or bolts.

3.2 PROTECTION FROM CONTACT OF DISSIMILAR MATERIALS

3.2.1 Omitted

3.2.2 Aluminum

Where aluminum contacts metal other than zinc, paint the dissimilar metal with a primer and two coats of aluminum paint.

3.2.3 Metal

Paint metal in contact with mortar, concrete, or other masonry materials with alkali-resistant coatings such as heavy-bodied bituminous paint.

3.2.4 Wood

Paint wood or other absorptive materials that may become repeatedly wet and in contact with metal with two coats of aluminum paint or a coat of heavy-bodied bituminous paint.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 10 - SPECIALTIES

SECTION 10270A

RAISED FLOOR SYSTEM

01/97

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SYSTEM DESCRIPTION
 - 1.2.1 Floor Panels
 - 1.2.2 Stringers
 - 1.2.3 Pedestals
 - 1.2.4 Pedestal Adhesive
 - 1.2.5 Bond Strength of Factory Installed Floor Covering
 - 1.2.6 Leakage
 - 1.2.7 Grounding
- 1.3 SUBMITTALS
- 1.4 DELIVERY, STORAGE, AND HANDLING
- 1.5 OMITTED
- 1.6 OPERATION AND MAINTENANCE MANUALS

PART 2 PRODUCTS

- 2.1 FLOOR PANELS
 - 2.1.1 Panel Construction
 - 2.1.1.1 Aluminum Panels
 - 2.1.1.2 Hollow Formed Steel Panels
 - 2.1.1.3 Metal-Clad Wood Core Panels
 - 2.1.2 Floor Covering
 - 2.1.2.1 High Pressure Laminate
 - 2.1.3 Edge Strip
 - 2.1.4 Accessories
 - 2.1.5 Resilient Base
 - 2.1.6 Lifting Device
- 2.2 PANEL SUPPORT SYSTEM
 - 2.2.1 Pedestals
 - 2.2.2 Stringers
- 2.3 OMITTED
- 2.4 OMITTED
- 2.5 OMITTED
- 2.6 TESTS
 - 2.6.1 Load Tests
- 2.7 Test for Bond Strength of Factory Installed Floor Covering
- 2.8 COLOR

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Preparation for Installation
 - 3.1.2 Pedestals
 - 3.1.3 Stringers
 - 3.1.4 Auxiliary Framing
 - 3.1.5 Panels

- 3.1.6 Resilient Base
- 3.1.7 Omitted
- 3.1.8 Repair of Zinc Coating
- 3.2 TESTING OF ELECTRICAL RESISTANCE
- 3.3 CLEANING AND PROTECTION
 - 3.3.1 Cleaning
 - 3.3.2 Protection
- 3.4 FIRE SAFETY

-- End of Section Table of Contents --

UFGS-10270A (January 1997)

SECTION 10270A

RAISED FLOOR SYSTEM

01/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A208.1 (1999) Particleboard Mat formed Woods

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM E 84 (1998e1) Surface Burning Characteristics of Building Materials

CEILINGS & INTERIOR SYSTEMS CONTRACTORS ASSOCIATION (CISCA)

CISCA Access Floors (1987) Recommended Test Procedures for Access Floors

U.S. DEPARTMENT OF COMMERCE (DOC)

PS-1 (1996) Voluntary Product Standard - Construction and Industrial Plywood

INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS (ICBO)

ICBO Building Code (1997) Uniform Building Code (3 Vol.)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA LD 3 (1995) High-Pressure Decorative Laminates

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 75 (1999) Protection of Electronic Computer/Data Processing Equipment

NFPA 99 (1999) Health Care Facilities

1.2 SYSTEM DESCRIPTION

Raised flooring shall be installed at the location and elevation and in the arrangement shown on the drawings. The floor system shall be of the stringer type, complete with all supplemental items, and shall be the standard product of a manufacturer specializing in the manufacture of

raised floor systems.

1.2.1 Floor Panels

Floor panel testing shall be conducted in accordance with CISCA Access Floors. When tested as specified, all deflection and deformation measurements shall be made at the point of load application on the top surface of the panel. Floor panels shall be capable of supporting 1500 pounds concentrated load without deflecting more than 0.080 inch and without permanent deformation in excess of 0.010 inch in any of the specified tests. Floor panels shall be capable of supporting 300 pounds per square foot uniform live load without deflection more than 0.040 inch.

Floor panels shall be capable of supporting 1000 pounds rolling load without deflecting more than 0.040 inch and without permanent deformation in excess of 0.020 inch. In accordance with CISCA Access Floors, the permanent deformation limit under rolling load shall be satisfied in all of the specified tests. In the specified tests, the permanent deformation shall be measured after 10 passes with Wheel 1 and after 10,000 passes with Wheel 2.

1.2.2 Stringers

Stringers shall be capable of supporting a 250 pound concentrated load at midspan without permanent deformation in excess of 0.010 inch.

1.2.3 Pedestals

Pedestals shall be capable of supporting a 5000 pound axial load without permanent deformation.

1.2.4 Pedestal Adhesive

Adhesive shall be capable of securing a pedestal in place with sufficient bonding strength to resist an overturning force of 1000 inch pounds.

1.2.5 Bond Strength of Factory Installed Floor Covering

Bond strength of floor covering shall be sufficient to permit handling of the panels by use of the panel lifting device, and to withstand moving caster loads up to 1000 pounds, without separation of the covering from the panel.

1.2.6 Leakage

When the space below the finished floor is to be an air plenum, air leakage through the joints between panels and around the perimeter of the floor system shall not exceed 0.1 cubic foot of air per minute per linear foot of joint subjected to 0.1 inch, water gauge, positive pressure in the plenum.

1.2.7 Grounding

The raised floor system shall be grounded for safety hazard and static suppression.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When

used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Raised Floor System

Drawings showing layout of the work, sizes and details of components, details at floor perimeter, bracing to resist seismic or other lateral loads, typical cutout details including size and shape limitation, method of grounding, description of shop coating, and installation height above structural floor.

SD-03 Product Data

Raised Floor System

Manufacturer's descriptive data, catalog cuts, and installation instructions. The data shall include information about any design and production techniques, procedures and policies used to conserve energy, reduce material, improve waste management or incorporate green building/recycled products into the manufacturer of their components or products. Cleaning and maintenance instructions shall be included. Design calculations which demonstrate that the proposed floor system meets requirements for seismic loading, prepared in accordance with subparagraph Underfloor Bracing under paragraph PANEL SUPPORT SYSTEM and ICBO Building Code. Certified copies of test reports may be submitted in lieu of calculations.

SD-04 Samples

Raised Floor System

One sample of each panel type and suspension system proposed for use.

SD-06 Test Reports

Tests

Testing of Electrical Resistance

Certified copies of test reports from an approved testing laboratory, attesting that the proposed floor system components meet the performance requirements specified.

SD-07 Certificates

Raised Floor System

Certificate of compliance attesting that the raised floor system meets specification requirements.

1.4 DELIVERY, STORAGE, AND HANDLING

Materials shall be stored in original protective packaging in a safe, dry, and clean location and shall be handled in a manner to prevent damage. Panels shall be stored at temperatures between 40 and 90 degrees F, and

between 20 percent and 70 percent humidity.

1.5 OMITTED

1.6 OPERATION AND MAINTENANCE MANUALS

Provide maintenance instructions for proper care of the floor panel surface. When conductive flooring is specified, require submittal of maintenance instructions to identify special cleaning and maintenance requirements to maintain "conductivity" properties of the panel finish.

PART 2 PRODUCTS

2.1 FLOOR PANELS

2.1.1 Panel Construction

Except for edge panels, panel size shall be 24 by 24 inches. Finished panels shall be within a 0.010 inch tolerance of the nominal size, and shall be square within a tolerance of 0.015 inch measured corner-to-corner. The top surface of panels shall be flat within a 0.020 inch tolerance measured corner-to-corner. Panels shall be permanently marked to indicate load rating and model number.

2.1.1.1 Aluminum Panels

Aluminum panels shall be of die-cast or extruded construction.

2.1.1.2 Hollow Formed Steel Panels

Steel panels shall be of die-formed construction, consisting of a flat steel top sheet welded to one or more formed steel stiffener sheets. Panels shall be chemically cleaned, bonderized, and painted with the manufacturer's standard finish.

2.1.1.3 Metal-Clad Wood Core Panels

Wood core panels shall have cores of wood particleboard conforming to ANSI A208.1, Grade 1-M-3, or of plywood conforming to PS-1, EXT-DFPA-C-C. The core shall be not less than 1 inch thick, and shall be faced on both sides with structurally bonded zinc-coated steel sheets not lighter than 24 gauge. All edges and corners shall be sealed with zinc-coated steel or extruded aluminum. The completed panels shall have a flame spread rating of 25 or less when tested in accordance with ASTM E 84.

2.1.2 Floor Covering

Floor panels shall be surfaced with materials firmly bonded in place with waterproof adhesive. The electrical resistance shall remain stable over the life expectancy of the floor covering. Any antistatic agent used in the manufacturing process shall be an integral part of the material, and shall not be surface applied. Bolt heads or similar attachments shall not rise above the traffic surface.

2.1.2.1 High Pressure Laminate

High pressure laminate surfacing shall conform to NEMA LD 3, Grade HW 62. Total system electrical resistivity from the wearing surface of the floor to the ground connection shall be between 150,000 ohms and 20,000,000,000 ohms.

2.1.3 Edge Strip

Panels shall be edged with extruded vinyl edge strips secured in place with mechanical interlock or adhesive bond, or shall be of a replaceable type. Top of strip shall be approximately 1/8 inch wide, and shall be flush with the floor surfacing.

2.1.4 Accessories

Perforated panels, and plenum dividers shall be provided where indicated, and shall be the manufacturer's standard type. Perforated panels shall be designed to support the same static loads as floor panels without structural failure, and shall be capable of delivering the air volumes indicated. Perforated panels shall be 25 percent open area and shall be equipped with adjustable dampers. 20 percent of panels shall be perforated.

2.1.5 Resilient Base

Base shall be manufacturers standard rubber straight style. Base shall be 4 inches high and a minimum 1/8 inch thick. Performed outside corners shall be furnished.

2.1.6 Lifting Device

Each individual room shall be provided with one floor panel lifting device standard with the floor manufacturer. A minimum of two devices shall be furnished.

2.2 PANEL SUPPORT SYSTEM

2.2.1 Pedestals

Pedestals shall be of steel or aluminum or a combination thereof. Ferrous materials shall have a factory-applied corrosion-resistant finish. Pedestal base plates shall provide a minimum of 16 square inches of bearing surface and shall be a minimum of 1/8 inch thick. Pedestal shafts shall be threaded to permit height adjustment within a range of approximately 2 inches, to permit overall floor adjustment within plus or minus 0.10 inch of the required elevation, and to permit leveling of the finished floor surface within 0.062 inch in 10 feet in all directions. Locking devices shall be provided to positively lock the final pedestal vertical adjustments in place. Pedestal caps shall interlock with panels to preclude tilting or rocking of the panels.

2.2.2 Stringers

Stringers shall be of rolled steel or extruded aluminum, and shall interlock with the pedestal heads to prevent lateral movement.

2.3 OMITTED

2.4 OMITTED

2.5 OMITTED

2.6 TESTS

Raised flooring shall be factory tested by an independent laboratory at the same position and maximum design elevation and in the same arrangement as shown on the drawings for installation so as to duplicate service

conditions as much as possible.

2.6.1 Load Tests

Floor panel, stringer, and pedestal testing shall be conducted in accordance with CISCA Access Floors.

2.7 Test for Bond Strength of Factory Installed Floor Covering

The test panel shall be supported on pedestals and stringers as specified for the installed floor. The supports shall be braced as necessary to prevent sideways movement during the test. A test load of 1000 pounds shall be imposed on the test assembly through a hard plastic caster 3 inches in diameter and 1 inch wide. The caster shall be rolled completely across the center of the panel. The panel shall withstand 20 passes of the caster with no delamination or separation of the covering.

2.8 COLOR

Color shall be as indicated on the drawings.

PART 3 EXECUTION

3.1 INSTALLATION

The floor system shall be installed in accordance with the manufacturer's instructions and with the approved detail drawings. Open ends of the floor, where the floor system does not abut wall or other construction, shall have positive anchorage and rigid support. Areas to receive raised flooring shall be maintained between 60 and 90 degrees F, and between 20 percent and 70 percent humidity for 24 hours prior to and during installation.

3.1.1 Preparation for Installation

The area in which the floor system is to be installed shall be cleared of all debris. Structural floor surfaces shall be thoroughly cleaned and all dust shall be removed. Floor coatings required for dust or vapor control shall be installed prior to installation of pedestals only if the pedestal adhesive will not damage the coating. If the coating and adhesive are not compatible, the coating shall be applied after the pedestals have been installed and the adhesive has cured.

3.1.2 Pedestals

Pedestals shall be accurately spaced, and shall be set plumb and in true alignment. Base plates shall be in full and firm contact with the structural floor, and shall be secured to the structural floor with adhesive.

3.1.3 Stringers

Stringers shall be interlocked with the pedestal caps to preclude lateral movement, and shall be spaced uniformly in parallel lines at the indicated elevation.

3.1.4 Auxiliary Framing

Auxiliary framing or pedestals shall be provided around columns and other

permanent construction, at sides of ramps, at open ends of the floor, and beneath panels that are substantially cut to accommodate utility systems. Special framing for additional lateral support shall be as shown on the approved detail drawings.

3.1.5 Panels

The panels shall be interlocked with supports in a manner that will preclude lateral movement. Perimeter panels, cutout panels, and panels adjoining columns, stairs, and ramps must be fastened to the supporting components to form a rigid boundary for the interior panels. Floors shall be level within 1/16 inch measured with a 10 foot straightedge in all directions. Cut edges of steel and wood-core panels shall be painted as recommended by the panel manufacturer. Cut edges of composite panels shall be coated with a silicone rubber sealant or with an adhesive recommended by the panel manufacturer. Extruded vinyl edging shall be secured in place at all cut edges of all panel cut-outs to prevent abrasion of cables. Where the space below the floor is a plenum, cutouts for conduit and similar penetrations shall be closed using self-extinguishing sponge rubber.

3.1.6 Resilient Base

Base shall be provided at vertical wall intersections. Cracks and voids in walls and other vertical surfaces to receive base shall be filled with an approved filler. The base shall be applied after the floor system has been completely installed. Base shall be applied with adhesive in accordance with the manufacturer's recommendations.

3.1.7 Omitted

3.1.8 Repair of Zinc Coating

Zinc coating that has been damaged, and cut edges of zinc-coated components and accessories, shall be repaired by the application of a galvanizing repair paint. Areas to be repaired shall be thoroughly cleaned prior to application of the paint.

3.2 TESTING OF ELECTRICAL RESISTANCE

Testing of electrical resistance in the completed installation shall be conducted in the presence of the Contracting Officer. Testing shall be in accordance with NFPA 99 modified by placing one electrode on the center of the panel surface and connecting the other electrode to the metal flooring support. Measurements shall be made at five or more locations. Each measurement shall be the average of five readings of 15 seconds duration at each location. During the tests, relative humidity shall be 45 to 55 percent and temperature shall be 69 to 75 degrees F. The panels used in the testing will be selected at random and will include two panels most distant from the ground connection. Electrical resistance shall be measured with instruments that are accurate within 2 percent and that have been calibrated within 60 days prior to the performance of the resistance tests. The metal-to-metal resistance from panel to supporting pedestal shall not exceed 10 ohms. The resistance between the wearing surface of the floor covering and the ground connection, as measured on the completed installation, shall be in accordance with paragraph FLOOR COVERING.

3.3 CLEANING AND PROTECTION

3.3.1 Cleaning

The space below the completed floor shall be free of all debris. Before any traffic or other work on the completed raised floor is started, the completed floor shall be cleaned in accordance with the floor covering manufacturer's instructions.

3.3.2 Protection

Traffic areas of raised floor systems shall be protected with a covering of building paper, fiberboard, or other suitable material to prevent damage to the surface. Cutouts shall be covered with material of sufficient strength to support the loads to be encountered. Plywood or similar material shall be placed on the floor to serve as runways for installation of heavy equipment. Protection shall be maintained until the raised floor system is accepted.

3.4 FIRE SAFETY

An automatic detection system shall be installed below the raised floor meeting the requirements of NFPA 75 paragraph 5-2.1 and shall sound an audible and visual alarm. Air space below the raised floor shall be subdivided into areas not exceeding 10,000 square feet by tight, noncombustible bulkheads. All penetrations for piping and cables shall be sealed to maintain bulkhead properties.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 10 - SPECIALTIES

SECTION 10440

INTERIOR SIGNAGE

07/02

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL
 - 1.3.1 Character Proportions and Heights
 - 1.3.2 Raised and Brailled Characters and Pictorial Symbol Signs (Pictograms)
- 1.4 QUALIFICATIONS
- 1.5 DELIVERY AND STORAGE

PART 2 PRODUCTS

- 2.1 ROOM IDENTIFICATION/DIRECTIONAL SIGNAGE SYSTEM
 - 2.1.1 Standard Room Signs
 - 2.1.2 Changeable Message Strip Signs
 - 2.1.3 Type of Mounting For Signs
 - 2.1.4 Graphics
- 2.2 OMITTED
- 2.3 OMITTED
- 2.4 OMITTED
- 2.5 OMITTED
- 2.6 OMITTED
- 2.7 OMITTED
- 2.8 FABRICATION AND MANUFACTURE
 - 2.8.1 Factory Workmanship
 - 2.8.2 Dissimilar Materials
- 2.9 COLOR, FINISH, AND CONTRAST

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Anchorage
 - 3.1.2 Protection and Cleaning

-- End of Section Table of Contents --

UFGS-10440 (July 2002)

SECTION 10440

INTERIOR SIGNAGE

07/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1 (1984; R 1994) Safety Performance Specifications and Methods of Test for Safety Glazing Materials Used in Buildings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings

Drawings showing elevations of each type of sign, dimensions, details and methods of mounting or anchoring, shape and thickness of materials, and details of construction. A schedule showing the location, each sign type, and message shall be included.

SD-03 Product Data

Installation

Manufacturer's descriptive data, catalogs cuts, installation and cleaning instructions.

1.3 GENERAL

Interior signage shall be of the design, detail, sizes, types, and message content shown on the drawings, shall conform to the requirements specified, and shall be provided at the locations indicated. Signs shall be complete with lettering, framing as detailed, and related components for a complete installation. Recyclable materials shall conform to EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS.

1.3.1 Character Proportions and Heights

Letters and numbers on indicated signs in handicapped-accessible buildings, which do not designate permanent rooms or spaces, shall have a width-to-height ratio between 3:5 and 1:1 and a stroke-width-to-height ratio between 1:5 and 1:10. Characters and numbers on indicated signs shall be sized according to the viewing distance from which they are to be read. The minimum height is measured using an upper case letter "X". Lower case characters are permitted. Suspended or projected overhead signs shall have a minimum character height of 3 inches.

1.3.2 Raised and Brailled Characters and Pictorial Symbol Signs (Pictograms)

Letters and numbers on indicated signs which designate permanent rooms and spaces in handicapped-accessible buildings shall be raised 1/32 inch upper case, sans serif or simple serif type and shall be accompanied with Grade 2 Braille. Raised characters shall be at least 5/8 inch in height, but no higher than 2 inches. Pictograms shall be accompanied by the equivalent verbal description placed directly below the pictogram. The border dimension of the pictogram shall be 6 inches minimum in height. Indicated accessible facilities shall use the international symbol of accessibility.

1.4 QUALIFICATIONS

Signs, plaques, and dimensional letters shall be the standard product of a manufacturer regularly engaged in the manufacture of such products and shall essentially duplicate signs that have been in satisfactory use at least 2 years prior to bid opening.

1.5 DELIVERY AND STORAGE

Materials shall be delivered to the jobsite in manufacturer's original packaging and stored in a clean, dry area in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 ROOM IDENTIFICATION/DIRECTIONAL SIGNAGE SYSTEM

Signs shall be fabricated of acrylic plastic conforming to ANSI Z97.1 .

2.1.1 Standard Room Signs

Signs shall consist of matte finish acrylic plastic or laminated thermosetting Type MP plastic. Units shall be frameless except for end caps. Corners of signs shall be squared.

2.1.2 Changeable Message Strip Signs

Changeable message strip signs shall consist of Type MP plastic captive message magnetic back face with message slots and associated end caps, as detailed, for insertion of changeable message strips. Size of signs shall be as shown on the drawings. Individual message strips to permit removal, change, and reinsertion shall be provided as detailed. Corners of signs shall be squared.

2.1.3 Type of Mounting For Signs

Extruded aluminum brackets, mounted as shown, shall be furnished for hanging, projecting, and double-sided signs. Mounting for framed, hanging, and projecting signs shall be by mechanical fasteners. Surface mounted signs shall be provided with 1/16 inch thick vinyl foam tape or countersunk mounting holes in plaques and mounting screws. Sign inserts shall be provided with 1/16 inch thick foam tape.

2.1.4 Graphics

Signage graphics for modular identification/directional signs shall conform to the following:

Graphics shall be raised 1/32 inch with background painted with low VOC paint.

2.2 OMITTED

2.3 OMITTED

2.4 OMITTED

2.5 OMITTED

2.6 OMITTED

2.7 OMITTED

2.8 FABRICATION AND MANUFACTURE

2.8.1 Factory Workmanship

Holes for bolts and screws shall be drilled or punched. Drilling and punching shall produce clean, true lines and surfaces. Exposed surfaces of work shall have a smooth finish and exposed riveting shall be flush. Fastenings shall be concealed where practicable.

2.8.2 Dissimilar Materials

Where dissimilar metals are in contact, the surfaces will be protected to prevent galvanic or corrosive action.

2.9 COLOR, FINISH, AND CONTRAST

Color shall be as shown on the drawings. In buildings required to be handicapped-accessible, the characters and background of signs shall be eggshell, matte, or other non-glare finish. Characters and symbols shall contrast with their background - either light characters on a dark background or dark characters on a light background.

PART 3 EXECUTION

3.1 INSTALLATION

Signs shall be installed in accordance with approved manufacturer's instructions at locations shown on the detail drawings. Illuminated signage shall be in conformance with the requirements of Section 16415A ELECTRICAL WORK, INTERIOR. Signs shall be installed plumb and true at mounting heights indicated, and by method shown or specified. Required blocking shall be installed as detailed. Signs which designate permanent rooms and spaces in handicapped-accessible buildings shall be installed on the wall adjacent to the latch side of the door. Where there is no wall space to the latch side of the door, including at double leaf doors, signs shall be placed on the nearest adjacent wall. Mounting location for such

signage shall be so that a person may approach within 3 inches of signage without encountering protruding objects or standing within the swing of a door. Signs on doors or other surfaces shall not be installed until finishes on such surfaces have been installed. Signs installed on glass surfaces shall be installed with matching blank back-up plates in accordance with manufacturer's instructions.

3.1.1 Anchorage

Anchorage shall be in accordance with approved manufacturer's instructions.

Anchorage not otherwise specified or shown shall include slotted inserts, expansion shields, and powder-driven fasteners when approved for concrete; toggle bolts and through bolts for masonry; machine carriage bolts for steel; lag bolts and screws for wood. Exposed anchor and fastener materials shall be compatible with metal to which applied and shall have matching color and finish. Where recommended by signage manufacturer, foam tape pads may be used for anchorage. Foam tape pads shall be minimum 1/16 inch thick closed cell vinyl foam with adhesive backing. Adhesive shall be transparent, long aging, high tech formulation on two sides of the vinyl foam. Adhesive surfaces shall be protected with a 5 mil green flatstock treated with silicone. Foam pads shall be sized for the signage as per signage manufacturer's recommendations. Signs mounted to painted gypsum board surfaces shall be removable for painting maintenance. Signs mounted to lay-in ceiling grids shall be mounted with clip connections to ceiling tees.

3.1.2 Protection and Cleaning

The work shall be protected against damage during construction. Hardware and electrical equipment shall be adjusted for proper operation. Glass, frames, and other sign surfaces shall be cleaned in accordance with the manufacturer's approved instructions.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 12 - FURNISHINGS

SECTION 12490A

WINDOW TREATMENT

01/98

PART 1 WORK DESCRIPTION

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL
- 1.4 DELIVERY, STORAGE, AND HANDLING
- 1.5 FIELD MEASUREMENTS
- 1.6 WARRANTY

PART 2 PRODUCTS

- 2.1 WINDOW BLINDS
 - 2.1.1 Horizontal Blinds
 - 2.1.1.1 Head Channel and Slats
 - 2.1.1.2 Controls
 - 2.1.1.3 Intermediate Brackets
- 2.2 OMITTED
- 2.3 COLOR

PART 3 EXECUTION

- 3.1 OMITTED
- 3.2 INSTALLATION

-- End of Section Table of Contents --

UFGS-12490A (January 1998)

SECTION 12490A

WINDOW TREATMENT

01/98

PART 1 WORK DESCRIPTION

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS AA-V-00200

(Rev B) Venetian Blinds

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Window Treatments
Hardware

Manufacturer's data composed of catalog cuts, brochures, product information, and maintenance instructions.

1.3 GENERAL

Window treatment shall be provided, complete with necessary brackets, fittings, and hardware. Each window treatment type shall be a complete unit provided in accordance with paragraph WINDOW TREATMENT PLACEMENT SCHEDULE. Equipment shall be mounted and operated as indicated. Windows to receive a treatment shall be completely covered. The Contractor shall take measurements at the building and shall be responsible for the proper fitting and hanging of the equipment.

1.4 DELIVERY, STORAGE, AND HANDLING

Components shall be delivered to the jobsite in the manufacturer's original packaging with the brand or company name, item identification, and project reference clearly marked. Components shall be stored in a dry location that is adequately ventilated and free from dust, water, or other contaminants and shall have easy access for inspection and handling. Materials shall be stored flat in a clean dry area with temperature maintained above 50 degrees F.

1.5 FIELD MEASUREMENTS

The Contractor shall become familiar with details of the work, verify dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing the work.

1.6 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period shall be provided.

PART 2 PRODUCTS

2.1 WINDOW BLINDS

Each blind, including hardware, accessory items, mounting brackets and fastenings, shall be provided as a complete unit produced by one manufacturer. All parts shall be one color unless otherwise shown, and match the color of the blind slat. Steel features shall be treated for corrosion resistance.

2.1.1 Horizontal Blinds

Horizontal blinds shall conform to FS AA-V-00200, Type II (1 inch slats), except as modified below. Blind units shall be capable of nominally 180 degree partial tilting operation and full-height raising. Blinds shall be inside mount as shown. Tapes for

2.1.1.1 Head Channel and Slats

Head channel shall be steel or aluminum nominal 0.024 for Type II. Slats shall be aluminum, not less than 0.006 inch thick, and of sufficient strength to prevent sag or bow in the finished blind. A sufficient amount of slats shall be provided to assure proper control, uniform spacing, and adequate overlap.

2.1.1.2 Controls

The slats shall be tilted by a transparent tilting wand, hung vertically by its own weight, and shall swivel for easy operation. The tilter control shall be of enclosed construction. Moving parts and mechanical drive shall be made of compatible materials which do not require lubrication during normal expected life. The tilter shall tilt the slats to any desired angle and hold them at that angle so that any vibration or movement of ladders and slats will not drive the tilter and change the angle of slats. A mechanism shall be included to prevent over tightening. The wand shall be of sufficient length to reach to within 5 feet of the floor.

2.1.1.3 Intermediate Brackets

Intermediate brackets shall be provided for installation of blinds over 48 inches wide and shall be installed as recommended by the manufacturer.

2.2 OMITTED

2.3 COLOR

Color shall be as indicated.

PART 3 EXECUTION

3.1 OMITTED

3.2 INSTALLATION

Installation shall be in accordance with the approved detail drawings and manufacturer's installation instructions. Units shall be level, plumb, secure, and at proper height and location relative to window units. The Contractor shall furnish and install supplementary or miscellaneous items in total, including clips, brackets, or anchorages incidental to or necessary for a sound, secure, and complete installation. Installation shall not be initiated until completion of room painting and finishing operations. Upon completion of the installation, window treatments shall be adjusted for form and appearance, shall be in proper operating condition, and shall be free from damage or blemishes. Damaged units shall be repaired or replaced by the Contractor as directed by the Contracting Officer.

-- End of Section --